



CITY OF BATTLE CREEK

ADDENDUM #1 IFB# 2018-041B

TITLE: 2018 Capital Preventative Maintenance Program

ADDENDUM ISSUED: February 23, 2018

***NOTE!* City Hall now has Security on the 1st floor. Please allow extra time to get through Security when dropping off your bid.**

The following changes, additions and deletions have been provided:

REPLACE ~ the existing price page with the attached revised price page.

REPLACE ~ Special Provision for Traffic Maintenance and Control, Special, with attached revised Special Provision for Traffic Maintenance and Control, Special

REPLACE ~ Special Provision for Turf Establishment, Special with attached revised Special Provision for Turf Establishment, Special

Due date and time remain the same.

This addendum must be acknowledged or your bid may be deemed non-responsive.

REVISED PRICE PAGE ADDENDUM #1

2018-041B CAPITAL PREVENTATIVE MAINTENANCE

ITEMS NO.	DESCRIPTION	UNITS	EST. QTY.	UNIT PRICE	ITEM TOTAL
1500001	Mobilization, Max 10%	1	LSUM		
2020002	Tree, Rem, 19 inch to 36 inch	4	Ea		
2020003	Tree, Rem, 37 inch or Larger	2	Ea		
2020004	Tree, Rem, 6 inch to 18 inch	2	Ea		
2040020	Curb and Gutter, Rem	20	Ft		
2040055	Sidewalk, Rem	565	Syd		
2090001	Project Cleanup	1	LSUM		
4030005	Dr Structure Cover, Adj, Case 1	15	Ea		
5010025	Hand Patching	5	Ton		
5020003	Overband Crack Fill, Lane	14.32	Lnmi		
5050001	Seal, Single Chip Type, CM16-Blend	138,235	Syd		
5050001	Seal, Single Chip Type, CS2-Trap	4,875	Syd		
5050001	Seal, Single Chip Type, CST-Trap	167,088	Syd		
5057011	_ Fog Seal	311,848	Syd		
8010005	Driveway, Nonreinf Conc, 6 inch	25	Syd		
8020038	Curb and Gutter, Conc, Det F4	20	Ft		
8030044	Sidewalk, Conc, 4 inch	4,746	Sft		
8030046	Sidewalk, Conc, 6 inch	175	Sft		
8110231	Pavt Mrkg, Waterborne, 4 inch, White	73,100	Ft		
8110232	Pavt Mrkg, Waterborne, 4 inch, Yellow	90,570	Ft		

8117001	_ Pavt Mrkg, Waterborne, 12 inch Crosswalk	2,723	Ft		
8117001	_ Pavt Mrkg, Waterborne, 24 inch Stop Bar	1,385	Ft		
8117001	_ Pavt Mrkg, Waterborne, 6 inch Crosswalk	2,547	Ft		
8117050	_ Pavt Mrkg, Waterborne, Railroad Sym	2	Ea		
8117050	_ Pavt Mrkg, Waterborne, School	3	Ea		
8117050	_ Pavt Mrkg, Waterborne, Lt Turn Arrow Sym	6	Ea		
8120280	Raised Pavt Marker, Temp, Type 1, White, Monodirectional	570	Ea		
8120281	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	740	Ea		
8127050	_ Vehicle Towing, Special	12	Ea		
8127051	_ Traffic Maintenance and Control, Special	1	LSUM		
8167011	_ Turf Establishment, Special	725	Syd		

TOTAL BASE BID \$ _____

**SPECIAL PROVISIONS
FOR
REVISED TRAFFIC MAINTENANCE AND CONTROL, SPECIAL ADDENDUM #1**

1 of 1

ESC/City of BC

January, 2017

a. description

Maintaining traffic shall be in accordance with Section 812 of the 2012 Michigan Department of Transportation Standard Specifications for Construction and these Special Provisions. All traffic control shall conform to the 2011 edition of the Michigan Manual of Uniform Traffic Control Devices (MMUTCD).

Payment for traffic control devices will be made based on a lump sum for the entire contract. At a minimum, the Contractor will be required to provide barricades, plastic drums, and signage per the MMUTCD along with any necessary traffic regulators (equipped to communicate with each other) at the front, end, and at any intersecting street of the lane being treated. Damage from vehicular traffic to newly treated road shall be the Contractor's responsibility.

Contractor is responsible for maintaining traffic at all times while work is being performed. Access to residences and businesses affected by the treatment may be closed for no more than two hour (as explained in the notification) to allow treatment cure time to be completed. Access to emergency vehicles will be maintained at all times.

b. payment

All work for Traffic Maintenance and Control shall be paid as a lump sum price, regardless of the number and type of traffic control devices used, per the following contract items (pay items):

<u>Pay Item</u>	<u>Pay Unit</u>
Traffic Maintenance and Control, Special	LSUM

Items included in Traffic Maintenance and Control, Special may include but are not limited to the following:

- Lighted Arrow, Type C, Furn
- Lighted Arrow, Type C, Oper
- Minor Traf Devices
- Plastic Drum, High Intensity, Furn
- Plastic Drum, High Intensity, Oper
- Sign, Type B, Temp, Prismatic, Furn
- Sign, Type B, Temp, Prismatic, Oper
- Traf Regulator Control

**SPECIAL PROVISION
FOR**

REVISED TURF ESTABLISHMENT, SPECIAL ADDENDUM #1

ESC/City of BC

December, 2016

a. description

Turf Establishment, Special shall be per Section 816 of the 2012 Standard Specifications for Construction and will include placement of 3 inches topsoil, Chemical Fertilizer Nutrient-Class C, Seeding Mixture TUF, Mulch (straw), and Anchoring Mulch at the specified rates.

The salvaged topsoil material shall be free of rock and wood debris. Visible rocks, roots, branches, and other debris will be removed by the Contractor and consider included with this item. When salvaged topsoil is not suitable or there is not a sufficient amount for establishment, it is the contractor's responsibility to bring screened-topsoil as part of the pay-item.

Payment for watering turf will be not be paid separately, but considered included and necessary in this item to establish the turf once the seed has germinated.

A one-year period of establishment commencing at the completion of the initial planting season will be required for all grass. A growing season is defined as the months of June, July and August. All grass shall be in a healthy growing condition at the start of the establishment period. The Engineer will inspect the grass at the end of the first growing season to determine if grass is unacceptable. Unacceptable grass is defined as being dead, missing, unhealthy, or otherwise unsatisfactory at the time of inspection, or grass that was not planted in conformance with these specifications. At the contractor's cost, replacement grass shall be replanted after September 15 following the initial growing season or prior to May 10 of the following spring planting season. This replacement grass shall remain the responsibility of the general contractor of the original contract with no additional payment.

The Contractor will also be responsible for preparing the topsoil a second time prior to the re-establishment of grass following the initial growing season in any unacceptable areas. This will include complete removal of weeds, raking and leveling the prepared soil along with the removal of any rocks or roots.

b. measurement and payment

Turf establishment will be paid up to 2 Ft on either side of sidewalk unless agreed upon by the engineer. All work to prepare and place topsoil for the establishment of turf shall be paid at the appropriate contract unit prices for the following contract items (pay items):

Pay Item

Pay Unit

Turf Establishment, Special Syd