



City of Alamogordo

Purchasing Dept. • 2600 N. Florida Ave. • Alamogordo, NM 88310 • (575) 439-4115 • FAX (575) 439-4117

February 27, 2018

**ADDENDUM NO. 1
PUBLIC WORKS BID NO. 2018-001
OTERO/GREENTREE REGIONAL LANDFILL CELL #5**

Each bidder shall acknowledge receipt of this Addendum Number One (1) by including in the Bid proposal.

Addendum Number 1 is issued to provide changes and/or clarifications to the above referenced PWB as follows:

Question: In the Geosynthetic Clay Liner Specification Section 1.4 it requires certain submittals to be included with the bid. Can this be changed to be post bid since this is something that is normally provided during the submittal process.

Answer: *Bidders shall provide all requested documentation within their bid package as noted within the project manual and construction drawings.*

Question: On Plan Page D100, Detail 2, it states the GCL to be woven on both sides. The GCL specs call out for a Bentomat St. material which is woven on one side and non-woven on the other side. Which material should be priced out on this project?

Answer: *Provide pricing based on Bid Item No. 10 on the Bid Schedule. The item description for Bid Item No. 10 states that the Geosynthetic Clay Liner with Woven Geotextiles on Both Sides, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).*

Question: Earth has been removed from the new future cell. Can you tell us how current the existing topo is and how accurate the quantity of earth to be moved is currently? It was stated at the pre-bid meeting that the quantity of dirt to be removed was not the amount given in the bid proposal. We need an accurate quantity for bid purposes

Answer: *SMA has completed recent topo work since the pre-bid meeting. The updated earthwork quantities are as follows:*

Unclassified excavation cut: 89,700 cy

Unclassified excavation fill: 25,340 cy

Bid Item No. 2 on the Bid Form has been modified to the following information and should be used to bid the project. Unclassified Excavation: Contractor to grade. Finish grade to design plan set 64,360 cy.

Question: The sand layer is an alternate-but the rock and leachate piping is not. This is very difficult to install the piping, without the sand layer being placed at same time. Will the contractor have to remobilize to install these items or how do you propose this work to be done?

Answer: *Means and methods are the responsibility of the contractor.*

Question: Is the sand layer available onsite, and will the sand material meet all specs for this contract?

Answer: *The sand layer will be acquired from on-site materials. The sand material has been previously approved during the construction of earlier cell phases.*

Question: Will the owner furnish all the sand layer onsite and if not, will there be a bid item for importing offsite sand material?

Answer: *The sand layer will be acquired from on site materials. The need for importing is not required and will not be included as a separate bid item.*

Question: Is there a geotechnical report for this project?

Answer: *A geotechnical report has not been provided for this project at this time.*

Question: What is the depth of groundwater?

Answer: *The depth of the groundwater is approximately 200-feet.*

Question: Can you give us an accurate distance to the earth waste disposal sites from the excavation new cell area?

Answer: *Disposal sites will be directly adjacent to Cell No. 5.*

Question: May we have a cad file for the dirt take-off purposes or construction purposes?

Answer: *CAD files will be released to the awarded bidder.*

Question: May we have the subgrade bid item by the sq yard? Why is it bid by cubic yard? Do we have to remove and replace or prep in place?

Answer: *Subgrade bid item has been modified to 55,410 sq. yards. Material shall be scarified, moisture treated and recompacted in place.*

Question: Can you give us a more accurate account of the location of the existing liner?

Answer: *The City of Alamogordo will be responsible for the location of the existing liner.*

Question: Can you give us a bit item for tying onto the existing liner?

Answer: *Tying onto the existing liner is incidental to the placement of the new liner. This will not be included as a separate bid item.*

Question: Could you explain more about the 10% local preference?

Answer: *Refer to Section 2, Instructions to Bidders, sub-section 32.0, Bid Evaluation Criterion for Area Businesses.*

Question: What is the perforation layout on the 12-inch on center leachate pipe?

Answer: *Pattern provided in Detail 3 of Sheet D101 shall be utilized for the perforation layout on the 12-inch leachate pipe.*

Question: Will a SWPPP be required, or can work be done under the landfill permit?
Answer: *Refer to Basic Requirements Section 1.39.C of the Technical Specifications section for all requirements relating to the project's SWPPP.*

Question: Will the 2' soil cushion for Alternate A-1, 33,988 cy be moved to the regular bid item list?
Answer: *The 2' soil cushion will remain as Alternate A-1.*

Clarification:

1. Prospective bidders are advised that UPS and FEDEX cannot guarantee delivery by 2:00 p.m.
2. Construction water will be provided at no cost to the contractor; however, tracking of the loads will be required due to Owner reporting requirements.

All other provisions of the Contract Documents shall remain unchanged. This addendum is hereby made part of the Contract Documents. Each bidder shall acknowledge receipt of this Addendum Number One (1) using this acknowledgement page and submit with the Bid proposal.

Sincerely,

Barbara Pyeatt
Chief Procurement Officer

Received By: _____

Date Received: _____

Business Name: _____

Signature: _____

SECTION 3 - BID SCHEDULE

BIDDER agrees to perform all of the work described in the specifications and shown on the plans for the following unit or lump sum prices. Prices should be written in numerals in the spaces provided.

**Public Works Bid No. 2018-001
Otero/Greentree Regional Landfill Cell #5**

ITEM NO.	ITEM DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	TOTAL PRICE
1	Soil Compaction Testing Allowance (95% of Modified Proctor).	LS	1	\$6,000	\$6,000
2	Unclassified Excavation: Contractor to grade. Finish grade to design plan set	CY	64,360		
3	6" Subgrade compacted to 95% Modified Proctor Density (ASTM1557)	SY	55,410		
4	6-inch Perforated HDPE SDR11 Pipe, including all appurtenances, CIP	LF	730		
5	6-inch Solid HDPE SDR11 Pipe, including all appurtenances, Complete-In-Place (CIP)	LF	255		
6	12-inch Perforated HDPE SDR11 Pipe, including all appurtenances, CIP	LF	30		
7	12-inch Solid HDPE SDR11 Pipe, including all appurtenances, CIP	LF	155		
8	60 Mil HDPE Double Textured, Side-Slope Liner - including weld and integrity testing of the liner and anchor trench, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	18,254		
9	60 Mil HDPE Smooth, Floor Liner - including weld and integrity testing of the liner and anchor trench, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	32,826		
10	Geosynthetic Clay Liner with Woven Geotextiles on Both Sides, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	51,080		
11	Non-Woven Geosynthetic Filter Fabric (6-inch minimum overlap), CIP	SY	820		
12	Coarse Aggregate; Type H (Graded Drain Rock)	CY	257		

13	Stormwater Protection Structure; including earthwork for ditch (95% Modified Proctor for Maximum Dry Density), earthwork for berm, 4x8 CDX with 1/4" or greater thickness plywood sheeting, marker stakes every 50 ft, and marker flag every 50 ft.	LF	730		
14	4 Layers of 200 Mil HDPE Geonet Cushion Covering Leachate Sump Floor, as shown on plans, CIP	SY	80		

TOTAL BASE BID AMOUNT EXCLUDING NMGR \$ _____

A-1	Soil Cushion, 2' (24" thickness) soil layer used for protective layer on top of Geomembrane	CY	33,988		
-----	---	----	--------	--	--

TOTAL ADD. ALT. BID AMOUNT EXCLUDING NMGR \$ _____

TOTAL BASE BID & ADD. ALT. AMOUNTS EXCLUDING NMGR \$ _____

NOTE: Gross receipts tax shall be paid with each pay request as it is submitted at the current tax rate for the County of Otero, New Mexico (6.3125%)

To the City of Alamogordo, New Mexico (hereinafter called "OWNER"), the undersigned, (hereinafter called "BIDDER"), in compliance with your invitation for bids for the construction of **Otero/Greentree Regional Landfill Cell #5, Public Works Bid No. 2018-001**, having carefully examined the Contract Documents and the site of the proposed work, and being familiar with all of the conditions surrounding the construction of the proposed project including the availability of materials and labor, hereby proposes to furnish all labor, materials, and supplies, and to construct the project in accordance with the Contract Documents, within the time set forth herein, and at the unit prices stated above. These prices are to cover all expenses incurred in performing the work required under the Contract Documents of which this Bid Schedule is a part. Quantities shown in this Bid Schedule are estimated and actual payment will be made on the basis of the unit bid prices for confirmed quantities as constructed.

BIDDER acknowledges receipt of the following addenda: _____

CALLOUT NOTICE ACKNOWLEDGMENT:

Authorized Signature of Bidder

Business Name of Bidder

Authorized Signature of Bidder

Printed Name and Title of Authorized Signature

BIDDER'S New Mexico Contractor's License No. & Classification

Address

Telephone

Fax

(SEAL) If Bid Proposal is submitted by a corporation



City of Alamogordo

ATTENDANCE ROSTER
OTERO/GREENTREE LANDFILL CELL #5
PWB 2018-001
PRE-BID CONFERENCE
FEBRUARY 14, 2018 2:00 P.M.
OTERO/GREENTREE REGIONAL LANDFILL

Name: <i>Bob Johnson</i>	Signature: <i>Bob Johnson</i>	
Company: <i>COA-ENG</i>	Phone: <i>575-439-4337</i>	E-Mail: <i>bjohnson@ci.alamogordo.nm.us</i>

Name: <i>Rob Gross Jaime Reyes</i>	Signature: <i>Jaime Reyes</i>	
Company: <i>Mountain States Constructors Inc</i>	Phone: <i>505-252-4427</i>	E-Mail: <i>Robg@msconstructors.com</i>

Name: <i>Londy Martinez</i>	Signature: <i>L. Martinez</i>	
Company: <i>Renegade Const.</i>	Phone: <i>575-523-2600</i>	E-Mail: <i>londymtz@hotmail.com</i>

Name: <i>Mike Heard</i>	Signature: <i>Mike Heard</i>	
Company: <i>Highland Enterprises, Inc.</i>	Phone: <i>575-524-3551</i>	E-Mail: <i>he1@highlandnm.com</i>

Name: <i>Mike Heard</i>	Signature: <i>Mike Heard</i>	
Company: <i>Two Bit Trucking</i>	Phone: <i>575-524-0119</i>	E-Mail: <i>he1@highlandnm.com</i>


Name: <i>DEANIE JACKSON</i>	Signature: <i>Deanie Jackson</i>	
Company: <i>SIERRA VALLEY CONTRACTORS</i>	Phone: <i>575-740-6017</i>	E-Mail: <i>SIERRAVALLEYCONTRACTORS@YAHOO.COM</i>

Name: <i>Wade Longley</i>	Signature: <i>Wade Longley</i>	
Company: <i>CBKN Dirtworks</i>	Phone: <i>505-991-2832</i>	E-Mail: <i>cbkndirtworks@yahoo.com</i>

Name: <i>MARK DeCARLO</i>	Signature: <i>Mark DeCarlo</i>	
Company: <i>SOUTHWEST LINER-SYSTEMS</i>	Phone: <i>505-771-9122</i>	E-Mail: <i>mark@SLSLINER.com</i>

Name: <i>Gary Scott</i>	Signature: <i>Gary Scott</i>	
Company: <i>CSW Contractors</i>	Phone: <i>602-980-1907</i>	E-Mail: <i>Estimating@CSWContractors.com</i>

Name: <i>Alonso Acosta</i>	Signature: <i>Alonso Acosta</i>	
Company: <i>Mesa Verde Ent, Inc</i>	Phone: <i>575-437-2995</i>	E-Mail: <i>alonsoacosta@mesaverdeinc.com</i>



City of Alamogordo

ATTENDANCE ROSTER
OTERO/GREENTREE LANDFILL CELL #5
PWB 2018-001
PRE-BID CONFERENCE
FEBRUARY 14, 2018 2:00 P.M.
OTERO/GREENTREE REGIONAL LANDFILL

Name: JEFF CRAIN	Signature: <i>Jeff Crain</i>	
Company: Alamo Earthwork	Phone: 575-437-3337	E-Mail: jeffcrain@alamoearthworks.com

Name: Steve DeYary	Signature: <i>Steve DeYary</i>	
Company: AJAC, Inc.	Phone: 505-249-8001	E-Mail: AJACENT20@gmail.com

Name: KRISTIN F. MONTOYA	Signature: <i>Kristin Montoya</i>	
Company: SMA	Phone: (575) 647-0799	E-Mail: kristin.montoya@gmail.com

Name: Sarah Garduño	Signature: <i>Sarah Garduño</i>	
Company: SMA	Phone: (575) 647-0799	E-Mail: Sarah.garduño@soudermiller.com

Name: Jim Mitchell	Signature: <i>Jim Mitchell</i>	
Company: J & H SERVICES INC 505-896-9428	Phone: 505-896-9428	E-Mail: jim@jhservicesinc.com

Name: MAMMY GUARDINO/SEDONA	Signature: <i>Mammy</i>	
Company: GUARDINO/SEDONA	Phone: 575-937-3015	E-Mail: mammy@SEDONA CONTRACTING INC.

Name: MORROW Enterprises Inc	Signature: <i>Leonardo Morrow</i>	
Company: LEONARDO MORROW	Phone: 575-526-1178	E-Mail: Bids@MorrowNM.com

Name: Byre Smith	Signature: <i>Byre Smith</i>	
Company: Smithco Construction, Inc.	Phone: 575-894-6161	E-Mail: smithco@smithco.cc

Name: Robert Blanton	Signature: <i>Robert Blanton</i>	
Company: CCA	Phone:	E-Mail:

Name: Larry Gardner	Signature: <i>Larry Gardner</i>	
Company: C.O.A.	Phone: 575-439-4241	E-Mail: