



*City of Alamogordo*

Purchasing Dept. • 2600 N. Florida Ave. • Alamogordo, NM 88310 • (575) 439-4115 • FAX (575) 439-4117

March 1, 2018

**ADDENDUM NO. 2  
PUBLIC WORKS BID NO. 2018-001  
OTERO/GREENTREE REGIONAL LANDFILL CELL #5**

Each bidder shall acknowledge receipt of this Addendum Number Two (2) by including in the Bid proposal.

Addendum Number Two (2) is issued to provide changes and/or clarifications to the above referenced PWB as follows:

**Clarification:**

1. SMA has completed recent topo work since the pre-bid meeting. The updated earthwork quantities are as follows: Unclassified excavation cut: 90,757 cy. Unclassified excavation fill: 12,988 cy. Bid Item No. 2 on the attached revised Bid Schedule has been modified to the following information and should be used to bid the project. Unclassified Excavation: Contractor to grade. Finish grade to design plan set 77,769 cy.

All other provisions of the Contract Documents shall remain unchanged. This addendum is hereby made part of the Contract Documents. Each bidder shall acknowledge receipt of this Addendum Number Two (2) using this acknowledgement page and submit with the Bid proposal.

Sincerely,

Barbara Pyeatt  
Chief Procurement Officer

Received By: \_\_\_\_\_

Date Received: \_\_\_\_\_

Business Name: \_\_\_\_\_

Signature: \_\_\_\_\_

**SECTION 3 - BID SCHEDULE**

BIDDER agrees to perform all of the work described in the specifications and shown on the plans for the following unit or lump sum prices. Prices should be written in numerals in the spaces provided.

**Public Works Bid No. 2018-001  
Otero/Greentree Regional Landfill Cell #5  
Addendum No. 2**

<b>ITEM NO.</b>	<b>ITEM DESCRIPTION</b>	<b>UNIT</b>	<b>EST. QTY.</b>	<b>UNIT PRICE</b>	<b>TOTAL PRICE</b>
1	Soil Compaction Testing Allowance (95% of Modified Proctor).	LS	1	\$6,000	\$6,000
2	Unclassified Excavation: Contractor to grade. Finish grade to design plan set	CY	77,769		
3	6" Subgrade compacted to 95% Modified Proctor Density (ASTM1557)	SY	55,410		
4	6-inch Perforated HDPE SDR11 Pipe, including all appurtenances, CIP	LF	730		
5	6-inch Solid HDPE SDR11 Pipe, including all appurtenances, Complete-In-Place (CIP)	LF	255		
6	12-inch Perforated HDPE SDR11 Pipe, including all appurtenances, CIP	LF	30		
7	12-inch Solid HDPE SDR11 Pipe, including all appurtenances, CIP	LF	155		
8	60 Mil HDPE Double Textured, Side-Slope Liner - including weld and integrity testing of the liner and anchor trench, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	18,254		
9	60 Mil HDPE Smooth, Floor Liner - including weld and integrity testing of the liner and anchor trench, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	32,826		
10	Geosynthetic Clay Liner with Woven Geotextiles on Both Sides, CIP (Anchor and drainage trenches, waste, overlap, or materials used for convenience are considered incidental to project and no extra payment will be made).	SY	51,080		
11	Non-Woven Geosynthetic Filter Fabric (6-inch minimum overlap), CIP	SY	820		
12	Coarse Aggregate; Type H (Graded Drain Rock)	CY	257		

13	Stormwater Protection Structure; including earthwork for ditch (95% Modified Proctor for Maximum Dry Density), earthwork for berm, 4x8 CDX with 1/4" or greater thickness plywood sheeting, marker stakes every 50 ft, and marker flag every 50 ft.	LF	730		
14	4 Layers of 200 Mil HDPE Geonet Cushion Covering Leachate Sump Floor, as shown on plans, CIP	SY	80		

**TOTAL BASE BID AMOUNT EXCLUDING NMGR** \$ \_\_\_\_\_

A-1	Soil Cushion, 2' (24" thickness) soil layer used for protective layer on top of Geomembrane	CY	33,988		
-----	---	----	--------	--	--

**TOTAL ADD. ALT. BID AMOUNT EXCLUDING NMGR** \$ \_\_\_\_\_

**TOTAL BASE BID & ADD. ALT. AMOUNTS EXCLUDING NMGR** \$ \_\_\_\_\_

**NOTE: Gross receipts tax shall be paid with each pay request as it is submitted at the current tax rate for the County of Otero, New Mexico (6.3125%)**

To the City of Alamogordo, New Mexico (hereinafter called "OWNER"), the undersigned, (hereinafter called "BIDDER"), in compliance with your invitation for bids for the construction of **Otero/Greentree Regional Landfill Cell #5, Public Works Bid No. 2018-001**, having carefully examined the Contract Documents and the site of the proposed work, and being familiar with all of the conditions surrounding the construction of the proposed project including the availability of materials and labor, hereby proposes to furnish all labor, materials, and supplies, and to construct the project in accordance with the Contract Documents, within the time set forth herein, and at the unit prices stated above. These prices are to cover all expenses incurred in performing the work required under the Contract Documents of which this Bid Schedule is a part. Quantities shown in this Bid Schedule are estimated and actual payment will be made on the basis of the unit bid prices for confirmed quantities as constructed.

BIDDER acknowledges receipt of the following addenda: \_\_\_\_\_

CALLOUT NOTICE ACKNOWLEDGMENT:

---

Authorized Signature of Bidder

---

Business Name of Bidder

---

Authorized Signature of Bidder

---

Printed Name and Title of Authorized Signature

---

BIDDER'S New Mexico Contractor's License No. & Classification

---

Address

---

Telephone

---

Fax

(SEAL) If Bid Proposal is submitted by a corporation