

Southside Park Phase 1 - Playground Area Improvements

Bid Form

ITEM NUMBER	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
A	Site Preparation and Demolition				
A.1	Site Mobilization	1	LS		
A.2	Bonds & Insurance	1	LS		
A.3	Construction Staking	1	LS		
A.4	Traffic Control	1	LS		
A.5	Asbuilt Construction Plans	1	LS		
A.6	Selective Clearing & Grubbing	28,000	SF		
A.7	Removal & Disposal - Asphalt and Curb	19,000	SF		
A.8	Removal & Disposal - Gravel Paths	13,300	SF		
B	Site Paving				
B.1	18" Curb & Gutter	1,400	LF		
B.2	Flush Ribbon Curb	550	LF		
B.3	Light Duty Asphalt with Base (2" Asphalt w/ 6" Base)	1,300	SY		
B.4	Road Patch for Utilities	2,000	SF		
B.5	Pervious Pavement (15" 57 Stone)	800	SY		
B.6	Decorative vehicular concrete pavers	660	SF		
B.7	Soft paving with steel edge	11,000	SF		
B.8	Soft paving (no edge restraint)	550	SF		
B.9	A.D.A. Detectable Warnings Pavers	200	SF		
B.10	Concrete Sidewalks (4" Thk)	17,500	SF		
B.11	Concrete Sidewalks (6" Thk)	2,400	SF		
B.12	Concrete ADA Parking	450	SF		
B.13	Wheel Stop	47	EA		
B.14	Bollards (standard)	8	EA		
B.15	Bollards (removable)	2	EA		
C	Site Furnishings				
C.1	Decorative Park Entry Gate and Columns (vehicular)	1	LS		
C.2	Benches (owner furnished; contractor installed)	11	EA		
C.3	Trash Receptacle (owner furnished; contractor installed)	3	EA		
C.4	Swing Bench and trellis	4	EA		
C.5	Picnic Table (standard rectangular)	5	EA		
C.6	Picnic Table (ADA rectangular)	1	EA		
C.7	Picnic Table (standard square)	3	EA		
C.8	Picnic Table (ADA square)	1	EA		
C.9	Drinking Fountain with bottle filler (MDF)	1	EA		
C.10	Hose Bibb (MDF)	5	EA		
C.11	Bike rack	3	EA		
C.12	Surface Preparation for Omnia Installation of playground equipment and safety surfacing.	1	LS		
C.13	Decorative brick wall (3' HT.)	90	LF		
C.14	Decorative brick columns	15	EA		
C.15	Decorative metal playground enclosure fencing	580	LF		
C.16	Decorative metal playground gate (Single)	1	EA		
C.17	Decorative metal playground gate (Double)	2	EA		
C.18	Park Entry ID Signage	1	LS		
C.19	Park Entry Gate Signage (hours, exit stop sign, etc.)	1	LS		
C.20	Playground Rules Signage	3	EA		
C.21	Pavilion ID signage	1	EA		
C.22	Pavement Markings	1	LS		
C.23	A.D.A. Striping and Signage	1	LS		
D	Site Grading				
D.1	Rough Grading (Cut)	360	CY		
D.2	Fine Grading	14,000	SY		
D.3	Select Fill	5,400	CY		

Southside Park Phase 1 - Playground Area Improvements

Bid Form

ITEM NUMBER	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
E	Site Drainage				
E.1	18" HP Storm	400	LF		
E.2	24" HP Storm	150	LF		
E.3	30" HP Storm	80	LF		
E.4	36" HP Storm	180	LF		
E.5	Outlet Control Structure	1	EA		
E.6	Grate Inlet	6	EA		
E.7	Bioretention Cell Media	2,000	CY		
E.8	6" Bioretention Underdrain	1,100	LF		
E.9	4" Underdrain	600	LF		
E.10	6" Roofdrain	150	LF		
E.11	8" ADS N-12 pipe	70	LF		
E.12	10" ADS N-12 pipe	85	LF		
E.13	NDS Junction Box	1	EA		
E.14	NDS Yard Inlet	2	EA		
F	Utilities - Sewer				
F.1	Conflict Box (Removed from plans)	4	EA	\$0.00	\$0.00
F.2	Sanitary Sewer Cleanout	10	EA		
F.3	6" PVC Sewer Pipe	472	LF		
F.4	Sewer Service Tie-in	1	EA		
G	Utilities - Water				
G.1	Irrigation System	1	LS		
G.2	1.5" PVC Irrigation Service with associated fittings	800	LF		
G.3	2" PVC Water Service with associated fittings	400	LF		
G.4	6" PVC Fire Hydrant Service with associated fittings	50	LF		
G.5	Water Service Tap Connection	1	EA		
G.6	Gate Valve	4	EA		
G.7	Backflow Preventor	2	EA		
G.8	Water Meter Box	2	EA		
G.9	Fire Hydrant Assembly	1	EA		
H	Erosion Control				
H.1	Silt Fence	5,000	LF		
H.2	Tree Protection	2,800	LF		
H.3	Inlet Protection Type A	7	EA		
H.4	Inlet Protection Type D	7	EA		
H.5	Inlet Protection Type E	4	EA		
H.6	Construction Entrance	1	EA		
H.7	Portable Toilet	1	EA		
H.8	Concrete Washout	1	EA		
H.9	Sediment Dike	1	EA		
H.10	Check Dam	1	EA		
H.11	Rip Rap Outlet Protection	6	EA		
H.12	Erosion Control Maintenance	1	LS		

Southside Park Phase 1 - Playground Area Improvements

Bid Form

ITEM NUMBER	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
I	Utility - Site Electric				
I.1	Light poles, anchor base, aluminum, 14' high, excl concrete base	17	EA		
I.2	Photoelectric control	1	EA		
I.3	Post luminaire, exterior, lantern	17	EA		
I.4	Conduit, 2" diameter, in trench, includes terminations and fittings	3,300	LF		
I.5	2" Electrical Conduit - Security Camera and Gate	1,200	LF		
I.6	2" Fiberoptic Conduit - Security Camera and Gate	1,200	LF		
I.7	Hand Holes 12" x 18" - Security Camera and Gate	6	EA		
I.8	Excavating, chain trencher, utility trench, common earth, 40 H.P., 12" wide, 36" deep	3,300	LF		
I.9	Wire, copper, #8, type THWN-THHN, in raceway	32	CLF		
I.10	Wire, copper, #4, type THWN-THHN, in raceway	64	CLF		
I.11	Receptacle, GFI 30 Amp	2	EA		
I.12	Receptacle, GFI, 15 Amp, incl box & cover	4	EA		
I.13	Circuit breaker, 2 pole, 15 to 60 amp	5	EA		
I.14	Landscape fixtures, low voltag, recessed uplight, incl conduit, wire, trench	2	EA		
I.15	Light Pole Concrete Base	17	EA		
J	Landscaping				
J.1	Palm Trees - SABP	24	EA		
J.2	Palm Trees - WARO	4	EA		
J.3	Canopy Trees - BETN	10	EA		
J.4	Canopy Trees - PITA	8	EA		
J.5	Canopy Trees - QOUN	6	EA		
J.6	Canopy Trees - QUPH	5	EA		
J.7	Canopy Trees - QUVI	22	EA		
J.8	Canopy Trees - TADI	17	EA		
J.9	Canopy Trees - ULDR	11	EA		
J.10	Understory Trees - CECR	4	EA		
J.11	Understory Trees - ILEA	6	EA		
J.12	Understory Trees - LAMO	10	EA		
J.13	Understory Trees - LANA	6	EA		
J.14	Shrubs - ALO XUP	4	EA		
J.15	Shrubs - CLAL	81	EA		
J.16	Shrubs - DIVJ	30	EA		
J.17	Shrubs - ILFL	10	EA		
J.18	Shrubs - ILLFS	6	EA		
J.19	Shrubs - LOCP	23	EA		
J.20	Shrubs - MYCE	15	EA		
J.21	Shrubs - PODO	57	EA		
J.22	Shrubs - SECI	83	EA		
J.23	Shrubs - VIAC	15	EA		
J.24	Shrubs - VISU	38	EA		
J.25	Shrubs - VITI	62	EA		

Southside Park Phase 1 - Playground Area Improvements

Bid Form

ITEM NUMBER	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
J.26	Ground Covers - ANN	189	EA		
J.27	Ground Covers - CAMI	214	EA		
J.28	Ground Covers - PLUM	93	EA		
J.29	Ground Covers - DIVA	37	EA		
J.30	Ground Covers - DIVE	72	EA		
J.31	Ground Covers - HYLI	51	EA		
J.32	Ground Covers - JUCO	250	EA		
J.33	Ground Covers - LAHY	29	EA		
J.34	Ground Covers - LOMK2	296	EA		
J.35	Ground Covers - LOMK	52	EA		
J.36	Ground Covers - MUCA	693	EA		
J.37	Ground Covers - MUCA2	671	EA		
J.38	Ground Covers - PANV	377	EA		
J.39	Ground Covers - PANE	32	EA		
J.40	Ground Covers - PAVN	71	EA		
J.41	Ground Covers - RUFU	114	EA		
J.42	Ground Covers - SPAL	86	EA		
J.43	Ground Covers - SPAB2	382	EA		
J.44	Ground Covers - SPBA	50	EA		
J.45	Ground Covers - TRAS	353	EA		
J.46	Mulch - HWMULCH	20,788	SF		
J.47	Mulch - MLCH	2,197	SF		
J.48	Turf - CYDA	117,193	SF		
J.49	Turf - CYCE	13,061	SF		
K	Pavilion				
K.1	Pavilion with unconditioned restrooms and storage	1	LS		
K.2	Mini-Split HVAC - For Electrical Closet	1	LS		
L	Allowances				
L.1	Arborist Allowance	1	LS	\$7,500	\$7,500
Total Project Price (Items A-L, Inclusive)				\$	