

BID FORM- GREENLAWN DRIVE STREETScape

PART 1 – Boundary Street to Burnside Street

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
1031000	MOBILIZATION	1	UNIT		
1032010	BONDS AND INSURANCE	1	UNIT		
1050800	CONSTRUCTION STAKES, LINES & GRADES	1	EA		
1071000	TRAFFIC CONTROL	1	UNIT		
10890200	AS-BUILT CONSTRUCTION PLANS	1	UNIT		
2011001	CLEARING & GRUBBING WITHIN ROADWAY	1	UNIT		
2023000	REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	0	SY		
2031000	UNCLASSIFIED EXCAVATION	302	CY		
2033000	BORROW EXCAVATION	320	CY		
2081001	FINE GRADING	2861	SY		
2103000	FLOWABLE FILL	60	CY		
2021005	REMOVAL & DISPOSAL OF EXISTING CATCH BASIN	1	EA		
20210-10	REMOVAL & DISPOSAL OF EXISTING DROP INLET	2	EA		
3069900	MAINTENANCE STONE	38	TON		
3100320	HOT MIX ASPHALT BASE COURSE – TYPE –' B'	565	TON		
4011004	LIQUID ASPHALT BINDER PG64-22	71	TON		
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	120	SY		
4020320	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE –'B'	421	TON		
4030340	HOT MIX ASPHALT SURFACE COURSE TYPE –'C'	315	TON		
4030360	HOT MIX ASPHALT SURFACE COURSE TYPE –' E'	68	TON		
6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	148	SF		
6250010	4" WHITE SOLID LINES - (PVT. EDGE LINES) – FAST DRY PAINT	2584	LF		
6250015	8" WHITE SOLID LINES - (CROSSWALKS & CHANNELIZATION) – FAST DRY PAINT	688	LF		
6250025	24" WHITE SOLID LINES - (STOP/DIAGONAL LINES) – FAST DRY PAINT	80	LF		
6250050	HANDICAP SYMBOL – FAST DRY PAINT	2	EA		
6250110	4" YELLOW SOLID LINES - (PVT. EDGE LINES & NO PASSING ZONE) – FAST DRY PAINT	3568	LF		
6271010	4" WHITE SOLID LINES) - THERMOPLASTIC- 90 MIL. (PVT. EDGE LINES)	1292	LF		
6271015	8" WHITE SOLID LINES THERMOPLASTIC - 125 MIL.	344	LF		
6271025	24" WHITE SOLID LINES) -THERMOPLASTIC-125 MIL (STOP/DIAG LINES	40	LF		
6271050	HANDICAP SYMBOL – THERMOPLASTIC – 125 MIL	2	EA		
6271074	4" YELLOW SOLID LINE – THERMOPLASTIC – 90 MIL (PVT EDGE LINES)	1783	LF		
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	12	EA		
6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	65	SF		
6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	96	LF		
6651005	F & I - STREET LIGHT - STANDARD FOUNDATION	17	EA		
6651091	FURNISH & INSTALL – SINGLE DECORATIVE POLE	17	EA		
6750213	2.0" SCHEDULE 40 PVC CONDUIT	1890	LF		
6760060	2.0" SCHEDULE 80 HDPE CONDUIT (TRENCHLESS)	192	LF		
6888110	FURNISH & INSTALL - STREET LIGHT LUMINAIRE	17	LF		

BID FORM- GREENLAWN DRIVE STREETScape

PART 1 – Boundary Street to Burnside Street

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
7141133	18" RC PIPE CULVERT - CL V	69	LF		
7143618	18" SMOOTH WALL PIPE	418	LF		
7143624	24" SMOOTH WALL PIPE	86	LF		
7149999	CLEAN EXISTING PIPE	220	LF		
7191005	CATCH BASIN -TYPE 1	1	EA		
7191605	CATCH BASIN -TYPE 16	7	EA		
7191650	CATCH BASIN -TYPE 18	1	EA		
7192020	DROP INLET (24" X 36")	2	EA		
7192109	MANHOLE WITH STANDARD 6' X 6' BOX	1	EA		
7195551	MANUFACTURED STORMWATER TREATMENT DEVICE - TYPE 1	1	EA		
7196173	CATCH BASIN - TYPE 16 (TOP ONLY)	0	EA		
7198392	JUNCTION BOX – CONVERT CB T-16	1	EA		
7203110	CONCRETE CURB & GUTTER (1'-6") VERTICAL FACE	1933	LF		
7204100	CONCRETE SIDEWALK (4" UNIFORM)	794	SY		
7204900	DETECTABLE WARNING MATERIAL	194	SF		
7205000	CONCRETE DRIVEWAY (6" UNIFORM)	166	SY		
7209000	PEDESTRIAN RAMP CONSTRUCTION	216	SY		
8091010	RIGHT OF WAY MARKER (REBAR&CAP)	9	EA		
8091050	RIGHT OF WAY PLAT	0.60	UNIT		
8100100	PERMANENT COVER	0.15	ACRE		
8100200	TEMPORARY COVER	0.15	ACRE		
8104005	FERTILIZER (NITROGEN)	15	LB		
8104010	FERTILIZER (PHOSPHORIC ACID)	15	LB		
8104015	FERTILIZER (POTASH)	15	LB		
8105005	AGRICULTURAL GRANULAR LIME	300	LB		
8109901	MOWING	0.3	ACRE		
8110000	LANDSCAPING ITEM No. 1 -ROOT BARRIER FABRIC (5 OZ)	3595	SF		
8110220	DOUBLE-SHREDDED HARDWOOD MULCH	3595	SF		
811117H	QUERCUS VIRGINIANA (SOUTHERN LIVE OAK)	15	EA		
8111180	CABBAGE PALM TREE (SABAL PALMETTO)	3	EA		
8111371	LIRIOPE MUSCARI 'MAJESTIC' (MAJESTIC LIRIOPE)	392	EA		
8111445	MULHENBERGIA CAPILLARIS (PINK MUHLY GRASS)	35	EA		
8115500	TREE WATERING BAG SYSTEM	18	EA		
8132000	CENTIPEDE GRASSING (SOD)	3438	SF		
8151203	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - Type 3	0.15	ACRE		
8152004	INLET STRUCTURE FILTER - TYPE F (WEIGHTED)	111	LF		
8152006	INLET STRUCTURE FILTER - TYPE F (NON-WEIGHTED)	111	LF		
8153000	SILT FENCE	1298	LF		
8153090	REPLACE/REPAIR SILT FENCE	130	LF		
8154050	REMOVAL OF SILT RETAINED BY SILT FENCE	325	LF		
8156200	CLEANING INLET STRUCTURE FILTERS	10	EA		
8156215	INLET STRUCTURE FILTER – TYPE D2	2	EA		
8156217	FILTER MATERIAL FOR INLET STRUCTURE FILTER -Type-D2	2	EA		

BID FORM- GREENLAWN DRIVE STREETScape

PART 1 – Boundary Street to Burnside Street

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
8110225	ROOT BARRIER (18" HIGH)	720	LF		
8990097	UTILITY DUCT BANK SYSTEM	1224	LF		
9800200	UTILITY DUCT BANK TURNOUT - ELECTRIC (GROUTED)	6	EA		
9800205	UTILITY DUCT BANK TURNOUT - COMMUNICATION (NON-GROUTED)	12	EA		
PART 1- PROJECT COST (Grand total, inclusive of all above items)					\$

BID FORM- GREENLAWN DRIVE STREETScape

Part 2 – Burnside Street to Greenlawn Circle (North)

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
1031000	MOBILIZATION	1	UNIT		
1032010	BONDS AND INSURANCE	1	UNIT		
1050800	CONSTRUCTION STAKES, LINES & GRADES	1	EA		
1071000	TRAFFIC CONTROL	1	UNIT		
10890200	AS-BUILT CONSTRUCTION PLANS	1	UNIT		
2011001	CLEARING & GRUBBING WITHIN ROADWAY	1	UNIT		
2023000	REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	3216	SY		
2031000	UNCLASSIFIED EXCAVATION	201	CY		
2033000	BORROW EXCAVATION	212	CY		
2081001	FINE GRADING	1906	SY		
2103000	FLOWABLE FILL	40	CY		
2021005	REMOVAL & DISPOSAL OF EXISTING CATCH BASIN	1	EA		
20210-10	REMOVAL & DISPOSAL OF EXISTING DROP INLET	0	EA		
3069900	MAINTENANCE STONE	24	TON		
3100320	HOT MIX ASPHALT BASE COURSE – TYPE –' B'	376	TON		
4011004	LIQUID ASPHALT BINDER PG64-22	46	TON		
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	80	SY		
4020320	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE –'B'	280	TON		
4030340	HOT MIX ASPHALT SURFACE COURSE TYPE –'C'	210	TON		
4030360	HOT MIX ASPHALT SURFACE COURSE TYPE –' E'	44	TON		
6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	100	SF		
6250010	4" WHITE SOLID LINES - (PVT. EDGE LINES) – FAST DRY PAINT	1720	LF		
6250015	8" WHITE SOLID LINES - (CROSSWALKS & CHANNELIZATION) – FAST DRY PAINT	460	LF		
6250025	24" WHITE SOLID LINES - (STOP/DIAGONAL LINES) – FAST DRY PAINT	52	LF		
6250050	HANDICAP SYMBOL – FAST DRY PAINT	2	EA		
6250110	4" YELLOW SOLID LINES - (PVT. EDGE LINES & NO PASSING ZONE) – FAST DRY PAINT	2380	LF		
6271010	4" WHITE SOLID LINES) - THERMOPLASTIC- 90 MIL. (PVT. EDGE LINES)	860	LF		
6271015	8" WHITE SOLID LINES THERMOPLASTIC - 125 MIL.	230	LF		
6271025	24" WHITE SOLID LINES) -THERMOPLASTIC-125 MIL (STOP/DIAG LINES	26	LF		
6271050	HANDICAP SYMBOL – THERMOPLASTIC – 125 MIL	2	EA		
6271074	4" YELLOW SOLID LINE – THERMOPLASTIC – 90 MIL (PVT EDGE LINES)	1190	LF		
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR. - 4"X4"	8	EA		
6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	44	SF		
6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	64	LF		
6651005	F & I - STREET LIGHT - STANDARD FOUNDATION	10	EA		
6651091	FURNISH & INSTALL – SINGLE DECORATIVE POLE	10	EA		
6750213	2.0" SCHEDULE 40 PVC CONDUIT	1260	LF		
6760060	2.0" SCHEDULE 80 HDPE CONDUIT (TRENCHLESS)	128	LF		
6888110	FURNISH & INSTALL - STREET LIGHT LUMINAIRE	10	LF		

BID FORM- GREENLAWN DRIVE STREETScape
PART 2 - Burnside Street to Greenlawn Circle (North)

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
7141133	18" RC PIPE CULVERT - CL V	46	LF		
7143618	18" SMOOTH WALL PIPE	278	LF		
7143624	24" SMOOTH WALL PIPE	56	LF		
7149999	CLEAN EXISTING PIPE	146	LF		
7191005	CATCH BASIN -TYPE 1	0	EA		
7191605	CATCH BASIN -TYPE 16	4	EA		
7191650	CATCH BASIN -TYPE 18	1	EA		
7192020	DROP INLET (24" X 36")	1	EA		
7192109	MANHOLE WITH STANDARD 6' X 6' BOX	0	EA		
7195551	MANUFACTURED STORMWATER TREATMENT DEVICE - TYPE 1	0	EA		
7196173	CATCH BASIN - TYPE 16 (TOP ONLY)	1	EA		
7198392	JUNCTION BOX – CONVERT CB T-16	0	EA		
7203110	CONCRETE CURB & GUTTER (1'-6") VERTICAL FACE	1288	LF		
7204100	CONCRETE SIDEWALK (4" UNIFORM)	529	SY		
7204900	DETECTABLE WARNING MATERIAL	128	SF		
7205000	CONCRETE DRIVEWAY (6" UNIFORM)	110	SY		
7209000	PEDESTRIAN RAMP CONSTRUCTION	150	SY		
8091010	RIGHT OF WAY MARKER (REBAR&CAP)	6	EA		
8091050	RIGHT OF WAY PLAT	0.40	UNIT		
8100100	PERMANENT COVER	0.1	ACRE		
8100200	TEMPORARY COVER	0.1	ACRE		
8104005	FERTILIZER (NITROGEN)	10	LB		
8104010	FERTILIZER (PHOSPHORIC ACID)	10	LB		
8104015	FERTILIZER (POTASH)	10	LB		
8105005	AGRICULTURAL GRANULAR LIME	200	LB		
8109901	MOWING	0.2	ACRE		
8110000	LANDSCAPING ITEM No. 1- ROOT BARRIER FABRIC (5 OZ)	3104	SF		
8110220	DOUBLE-SHREDDED HARDWOOD MULCH (3" deep)	3104	SF		
811117H	QUERCUS VIRGINIANA (SOUTHERN LIVE OAK)	10	EA		
8111180	CABBAGE PALM TREE (SABAL PALMETTO)	2	EA		
8111371	LIRIOPE MUSCARI 'MAJESTIC' (MAJESTIC LIRIOPE)	262	EA		
8111445	MULHENBERGIA CAPILLARIS (PINK MUHLY GRASS)	23	EA		
8115500	TREE WATERING BAG SYSTEM	12	EA		
8132000	CENTIPEDE GRASSING (SOD)	3290	SF		
8151203	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - TYPE 3	0.1	ACRE		
8152004	INLET STRUCTURE FILTER - TYPE F (WEIGHTED)	74	LF		
8152006	INLET STRUCTURE FILTER - TYPE F (NON-WEIGHTED)	74	LF		
8153000	SILT FENCE	864	LF		
8153090	REPLACE/REPAIR SILT FENCE	86	LF		
8154050	REMOVAL OF SILT RETAINED BY SILT FENCE	216	LF		
8156200	CLEANING INLET STRUCTURE FILTERS	7	EA		
8156215	INLET STRUCTURE FILTER – TYPE D2	2	EA		

Section 1.8 - Bid Proposal Documents

SCHEDULE of VALUES

BID FORM - GREENLAWN DRIVE - STREETScape
PART 2 - Burnside Street to Greenlawn Circle (North)

ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	ESTIMATE PRICE
8156217	FILTER MATERIAL FOR INLET STRUCTURE FILTER – TYPE D2	2	EA		
8110225	ROOT BARRIER (18" HIGH)	480	LF		
8990097	UTILITY DUCT BANK SYSTEM	816	LF		
9800200	UTILITY DUCT BANK TURNOUT - ELECTRIC (GROUTED)	4	EA		
9800205	UTILITY DUCT BANK TURNOUT - COMMUNICATION (NON-GROUTED)	8	EA		
	PART 2 - PROJECT COST (Grand total, inclusive of all above items)			\$	
	PART 1 - PROJECT COST (Total from preceding bid tab)			\$	
	PROJECT COST (Grand total, Part 1 plus Part 2 totals, above)			\$	