


HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIRS; PERMIT #111-004D (SL)

FORT VALLEY, PEACH COUNTY, GEORGIA
DECEMBER 2021



TOPOGRAPHIC NOTES:
THIS MAP WAS COMPILED BY STEROPHOTOGRAMMETRIC METHODS FROM PHOTOGRAPH DATED 18 JUNE, 1992, AND FIELD CONTROL SURVEYS CONDUCTED IN JUNE, 1992, AND BY TRIBBLE & RICHARDSON, AND MAY 2004 BY DONALDSON, GARRETT & ASSOCIATES.

TOPOGRAPHIC CONTOUR INTERVAL IS TWO FEET.

DASHED CONTOURS INDICATE AREAS OF DENSE VEGETATION WHERE THE ACTUAL ELEVATION MAY VARY SLIGHTLY FROM THAT SHOWN.

BUILDINGS SHOWN ARE DRAWN AT THE ROOF OVERHANG LINE.

VERTICAL AND HORIZONTAL DATUM PROVIDED BY TRIBBLE & RICHARDSON.

TOPOGRAPHIC MAP UPDATED BY METRO AERIAL SURVEYORS, McDONOUGH, GEORGIA, NOVEMBER 2021. TOPOGRAPHIC ORIENTED ON STATE PLAN COORDINATES.

AERIAL TARGETS 1, 5, 6, & 7, GWA-1, GWC-5, GWC-13R LOCATED BY WELLSTON & ASSOCIATES, NOVEMBER 2021.

THE PROPERTY LINE SHOWN IS APPROXIMATE.

VICINITY MAP
1"=3/4 MILE



Know what's below.
Call before you dig.

<p>PRIMARY PERMITTEE PEACH COUNTY BOARD OF COMMISSIONERS 213 PERSONS STREET FT. VALLEY, GA 31038 PHONE: (478) 825-2535</p>	<p>CIVIL ENGINEER TRIPLE POINT ENGINEERING KENT MCCORMICK, P.E. 5223 RIVERSIDE DRIVE, SUITE 101 MACON, GEORGIA 31210 PHONE: (478) 476-0700 FAX: (478) 476-0776 kmccormick@tpointeng.com</p>	<p>LAND SURVEYOR EXISTING CONDITIONS SHOWN WAS COMPILED BY STEROPHOTOGRAMMETRIC METHODS FROM PHOTOGRAPH DATED 18 JUNE, 1992, AND FIELD CONTROL SURVEYS CONDUCTED IN JUNE, 1992, BY TRIBBLE & RICHARDSON. TOPOGRAPHIC SURVEY IS FOR REFERENCE ONLY & SHOULD NOT BE RELIED UPON.</p>	<p>24 HR CONTACT MICHAELA JONES COUNTY ADMINISTRATOR PEACH COUNTY BOARD OF COMMISSIONERS PHONE: (478) 827-3162</p>	<p>LEGEND</p> <table border="0"> <tr> <td>LIMITS OF DISTURBANCE</td> <td>---</td> <td>---</td> </tr> <tr> <td>SILT FENCE</td> <td>---</td> <td>XX-XX</td> </tr> <tr> <td>SLOPE STABILIZATION MATTING</td> <td>---</td> <td>~~~~~</td> </tr> <tr> <td>PROPERTY LINE</td> <td>---</td> <td>---</td> </tr> <tr> <td>MONITORING WELL</td> <td>⊙</td> <td>⊙</td> </tr> <tr> <td>METHANE MONITORING WELL</td> <td>⊙</td> <td>⊙</td> </tr> <tr> <td>CONTOUR</td> <td>---</td> <td>---</td> </tr> <tr> <td>STORM PIPE</td> <td>---</td> <td>---</td> </tr> </table>	LIMITS OF DISTURBANCE	---	---	SILT FENCE	---	XX-XX	SLOPE STABILIZATION MATTING	---	~~~~~	PROPERTY LINE	---	---	MONITORING WELL	⊙	⊙	METHANE MONITORING WELL	⊙	⊙	CONTOUR	---	---	STORM PIPE	---	---	<p>INDEX TO DRAWINGS</p> <table border="0"> <tr> <th>SHEET NUMBER</th> <th>SHEET TITLE</th> </tr> <tr> <td>--</td> <td>TITLE SHEET</td> </tr> <tr> <td>1.0</td> <td>SITE LAYOUT</td> </tr> <tr> <td>2.0</td> <td>GRADING PLAN</td> </tr> <tr> <td>3.0</td> <td>GRADING PLAN</td> </tr> <tr> <td>4.0</td> <td>POND OUTLET REPAIR PLAN & PROFILE</td> </tr> <tr> <td>5.0</td> <td>POND OUTLET REPAIR NOTES & DETAILS</td> </tr> <tr> <td>6.0</td> <td>INITIAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN</td> </tr> <tr> <td>7.0</td> <td>INTERMEDIATE EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN</td> </tr> <tr> <td>8.0</td> <td>FINAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN</td> </tr> <tr> <td>9.0</td> <td>EROSION CONTROL NOTES AND DETAILS</td> </tr> <tr> <td>10</td> <td>NPDES PLAN</td> </tr> </table>	SHEET NUMBER	SHEET TITLE	--	TITLE SHEET	1.0	SITE LAYOUT	2.0	GRADING PLAN	3.0	GRADING PLAN	4.0	POND OUTLET REPAIR PLAN & PROFILE	5.0	POND OUTLET REPAIR NOTES & DETAILS	6.0	INITIAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN	7.0	INTERMEDIATE EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN	8.0	FINAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN	9.0	EROSION CONTROL NOTES AND DETAILS	10	NPDES PLAN
LIMITS OF DISTURBANCE	---	---																																																			
SILT FENCE	---	XX-XX																																																			
SLOPE STABILIZATION MATTING	---	~~~~~																																																			
PROPERTY LINE	---	---																																																			
MONITORING WELL	⊙	⊙																																																			
METHANE MONITORING WELL	⊙	⊙																																																			
CONTOUR	---	---																																																			
STORM PIPE	---	---																																																			
SHEET NUMBER	SHEET TITLE																																																				
--	TITLE SHEET																																																				
1.0	SITE LAYOUT																																																				
2.0	GRADING PLAN																																																				
3.0	GRADING PLAN																																																				
4.0	POND OUTLET REPAIR PLAN & PROFILE																																																				
5.0	POND OUTLET REPAIR NOTES & DETAILS																																																				
6.0	INITIAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN																																																				
7.0	INTERMEDIATE EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN																																																				
8.0	FINAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN																																																				
9.0	EROSION CONTROL NOTES AND DETAILS																																																				
10	NPDES PLAN																																																				
<p>PROJECT DESCRIPTION THE PROJECT SITE IS LOCATED WITHIN PEACH COUNTY. THESE PLANS DETAIL THE WORK NECESSARY TO REHABILITATE THE POND OUTFALL STRUCTURES AND DAM AT HOUSER'S MILL ROAD SANITARY LANDFILL</p> <p>TOTAL LANDFILL ACREAGE : 55.00 AC TOTAL DISTURBED ACREAGE: 13.2 AC</p>		<p>GENERAL NOTES</p> <p>1. ABOVE GROUND UTILITY LOCATIONS WERE OBTAINED FROM FIELD OBSERVATIONS AND BEST AVAILABLE RECORDS. UNDERGROUND UTILITY LOCATIONS AND EASEMENT LOCATIONS AND/OR REFERENCES WERE FURNISHED TO US BY AGENCIES OR INDIVIDUALS AND WE DO NOT CERTIFY THE ACCURACY OR COMPLETENESS OF THIS INFORMATION. UTILITY LOCATIONS SHOULD BE CONFIRMED IN THE FIELD PRIOR TO PROCEEDING WITH CONSTRUCTION.</p> <p>2. IF ANY CONFLICTS, DISCREPANCIES, OR OTHER UNSATISFACTORY CONDITIONS ARE DISCOVERED EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD CONDITIONS, THE CONTRACTOR MUST NOTIFY THE ENGINEER OR SURVEYOR IMMEDIATELY AND SHALL NOT COMMENCE OR CONTINUE OPERATION UNTIL THE CONFLICTS, DISCREPANCIES, AND/OR OTHER UNSATISFACTORY CONDITIONS ARE RESOLVED.</p> <p>3. THE CONTRACTOR MUST PROTECT WATER, SEWER, DRAINAGE, AND OTHER UNDERGROUND STRUCTURES/UTILITIES DURING CONSTRUCTION. ONCE THE PIPE IS PLACED, ADDITIONAL PROTECTIVE FILL MAY BE NEEDED OVER PIPES DURING THE CONSTRUCTION PROCESS.</p>		<p>811 Know what's below. Call before you dig.</p>																																																	

NO.	DATE	DESCRIPTION

TRIPLE POINT ENGINEERING
5223 Riverside Drive • Suite 101 • Macon, Georgia 31210
phone 478.476.0700 • fax 478.476.0776 • www.tpointeng.com

TITLE SHEET
HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
PEACH COUNTY, GEORGIA




PROJECT NO.:	PCO 058
DATE:	DECEMBER 2021
SCALE:	N.T.S.

DEVEGETATION LINE /TREE REMOVAL

POND OUTLET MAINTENANCE AND REHABILITATION

GRADING AREA #1



TOPOGRAPHIC NOTES:

TOPOGRAPHIC CONTOUR INTERVAL IS ONE FOOT.

TOPOGRAPHIC MAP ON THE LANDFILL AREA UPDATED BY METRO AERIAL SURVEYORS, McDONOUGH, GEORGIA, NOVEMBER 2021. TOPOGRAPHIC ORIENTED ON STATE PLAN COORDINATES. TOPOGRAPHIC INFORMATION ON THE PROPOSED BORROW PIT AREA OBTAINED FROM INFORMATION AVAILABLE FROM INFRAWORKS BY AUTODESK.

DASHED CONTOURS INDICATE AREAS OF DENSE VEGETATION WHERE THE ACTUAL ELEVATION MAY VARY SLIGHTLY FROM THAT SHOWN.

BOUNDARY INFORMATION, MONITORING WELL LOCATIONS, GAS EXTRACTION SYSTEM WELLS AND COMPONENTS WERE OBTAINED FROM A COMPILATION OF VARIOUS PREVIOUS SURVEYS CONDUCTED.

BUILDINGS SHOWN ARE DRAWN AT THE ROOF OVERHANG LINE. GWA-1, GWC-5, GWC-13R LOCATED BY WELLSTON & ASSOCIATES, NOVEMBER 2021.


THE PROPERTY LINE SHOWN IS APPROXIMATE.

GRADING AREA #2

GRADING AREA #3

BORROW SOURCE

NOTE: CONTRACTOR SHALL PROTECT ALL WELLS DURING CONSTRUCTION. THE CONTRACTOR SHALL ABANDON AND REPLACE ANY WELL THAT IS DAMAGED AT THE CONTRACTOR'S COST.




NO.	DATE	DESCRIPTION
1	11/20/2021	ISSUE SEQUENCE
		REVISED NOTES

TRIPLE POINT ENGINEERING
 5223 Riverside Drive • Suite 101 • Macon, Georgia 31210
 phone 478.476.0700 • fax 478.476.0776 • www.triplepointeng.com

SITE LAYOUT

HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
 PEACH COUNTY, GEORGIA



PROJECT NO.: PCO 058
 DATE: DECEMBER 2021
 SCALE: 1"=100'


1.0



NO.	DATE	ISSUE SEQUENCE	DESCRIPTION



TRIPLE POINT ENGINEERING
 5223 Riverstone Drive • Suite 101 • Macon, Georgia 31210
 phone 478.476.0700 • fax 478.476.0776 • www.tpointeng.com

HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
 PEACH COUNTY, GEORGIA



PROJECT NO.: PCO 058
 DATE: DECEMBER 2021
 SCALE: 1"=100'

2.0



LEGEND

EXISTING PROPOSED


- LIMITS OF DISTURBANCE
- BUFFER LINE
- SILT FENCE
- PROPERTY LINE
- MONITORING WELL
- METHANE MONITORING WELL
- METHANE EXTRACTION WELL
- CONTOUR
- VEGETATION
- STAND PIPE
- HEADWALL
- RIP RAP
- EROSION CONTROL MATTING

- NOTES:
- 1) CONTRACTOR SHALL PROTECT ALL GROUNDWATER MONITORING, METHANE MONITORING, AND METHANE EXTRACTION WELLS DURING CONSTRUCTION. THE CONTRACTOR SHALL ABANDON AND REPLACE ANY WELL THAT IS DAMAGED AT THE CONTRACTORS COST.
 - 2) ONLY FILL SHALL BE ALLOWED ON LANDFILL AREAS. CONTRACTOR SHALL NOT EXCAVATE IN EXISTING LANDFILL AREAS.
 - 3) CONTRACTOR SHALL COMPACT SOIL FILL TO 90% STD. PROCTOR.

811
 Know what's below.
 Call before you dig.



© Triple Point Engineering, Inc. 2021. All rights reserved. This document is the property of Triple Point Engineering, Inc. (TPE) and is intended for use only in connection with the project for which it was prepared. No part of this document may be reproduced or transmitted in any form or by any means electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without the prior written permission of TPE, Inc. Use for any other purpose, in whole or in part, is prohibited. TPE, Inc. and its logo are registered trademarks of Triple Point Engineering, Inc. All other marks and logos are the property of their respective owners.




NO.	DATE	DESCRIPTION

TRIPLE POINT
ENGINEERING

5223 Riverside Drive • Suite 101 • Macon, Georgia 31210
phone 478.476.0700 • fax 478.476.0776 • www.triplepointeng.com


GRADING PLAN - BORROW SOURCE

HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
PEACH COUNTY, GEORGIA



PROJECT NO.: PCO 058
DATE: DECEMBER 2021
SCALE: 1"=60'

3.0



LEGEND



EXISTING	PROPOSED
--- (Limits of Disturbance)	--- (Limits of Disturbance)
--- (Buffer Line)	--- (Buffer Line)
--- (Silt Fence)	--- (Silt Fence)
--- (Property Line)	--- (Property Line)
⊙ (Monitoring Well)	⊙ (Monitoring Well)
⊙ (Methane Monitoring Well)	⊙ (Methane Monitoring Well)
⊙ (Methane Extraction Well)	⊙ (Methane Extraction Well)
--- (Contour)	--- (Contour)
--- (Vegetation)	--- (Vegetation)
--- (Stand Pipe)	--- (Stand Pipe)
--- (Headwall)	--- (Headwall)
--- (Rip Rap)	--- (Rip Rap)
--- (Erosion Control Matting)	--- (Erosion Control Matting)

NOTE: CONTRACTOR SHALL PROTECT ALL WELLS DURING CONSTRUCTION. THE CONTRACTOR SHALL ABANDON AND REPLACE ANY WELL THAT IS DAMAGED AT THE CONTRACTORS COST.



Know what's below.
Call before you dig.






ENGLISH I-P UNITS

"A"	"B"	"C"	"D"	"E"	"F"	"G"	"H"
12"	1'-8"	4'-0"	2'-6"	1'-8"	1'-2"	1'-3"	1'-7"
15"	2'-0"	4'-4"	2'-10"	2'-0"	1'-3"	1'-3"	1'-7"
18"	2'-4"	4'-8"	3'-2"	2'-4"	1'-4"	1'-3"	1'-7"
24"	2'-10"	5'-2"	3'-8"	2'-10"	1'-5"	1'-4"	2'-1"
30"	3'-6"	5'-10"	4'-4"	3'-6"	1'-9"	1'-6"	2'-5"
36"	4'-0"	6'-4"	4'-10"	4'-0"	2'-0"	1'-8"	2'-11"
42"	4'-6"	6'-10"	5'-4"	4'-6"	2'-3"	2'-0"	3'-6"
48"	5'-2"	7'-6"	6'-0"	5'-2"	2'-6"	2'-0"	4'-0"
54"	5'-9"	8'-1"	6'-7"	5'-9"	2'-9"	2'-0"	4'-6"
60"	6'-4"	8'-8"	7'-2"	6'-4"	3'-0"	2'-2"	5'-0"

DETAIL - PRECAST CONCRETE HEADWALL
N.T.S.




PROFILE - POND OUTLET, 0+00 - 1+42
SCALE: 1"=100' H., 1"=20' V.

- NOTES:
- 1) CONTRACTOR SHALL TRANSPORT, HAUL, PLACE AND COMPACT CLAY MATERIAL FOR BACKFILL MATERIAL IN AND AROUND THE OUTLET STRUCTURE INCLUDING THE PIPE THROUGH THE DAM.
 - 2) CONTRACTOR SHALL PROTECT ALL WELLS DURING CONSTRUCTION. THE CONTRACTOR SHALL ABANDON AND REPLACE ANY WELL THAT IS DAMAGED AT THE CONTRACTORS COST.

LEGEND

EXISTING	PROPOSED
--- ---	--- ---
---	---
---	---
W GWA-1	W GWA-1
---	---
---	---
---	---
---	---
---	---
---	---
---	---
---	---
---	---



ISSUE SEQUENCE


NO.	DATE	DESCRIPTION

TRIPLE POINT ENGINEERING


5223 Riverside Drive • Suite 101 • Macon, Georgia 31210
phone 478.476.0700 • fax 478.476.0776 • www.triplepointeng.com

POND OUTLET REPAIR PLAN & PROFILE


HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
PEACH COUNTY, GEORGIA



PROJECT NO.: PCO 058
DATE: DECEMBER 2021
SCALE: 1"=30'



SEDIMENT STORAGE CALCULATIONS
 REQUIRED SEDIMENT STORAGE (67CY/AC): 67x14.61=978.9 C.Y.
 SEDIMENT STORAGE PROVIDED IN EXISTING SEDIMENT POND:
 RT: 3935 C.Y.



SOILS LEGEND		HYDROLOGIC SOIL GROUP
AvP	Alluvial land, wet	B/D
LcB	Lucy Sand	B
LcC	Lucy Sand	B
LqB	Lakeland Fine Sand	A
LqD	Lakeland Fine Sand	A
OgA	Orangeburg Loamy Fine Sand	B
OgC	Orangeburg Loamy Fine Sand	B

NOTE:
 EROSION CONTROL WILL BE ACCOMPLISHED ON THE SURFACE OF THE LANDFILL CAP. EXCAVATION IS NOT ALLOWED ON THE SANITARY LANDFILL CAP. THE EXISTING SEDIMENT POND ON SITE WILL BE USED TO PROVIDE SEDIMENT STORAGE FOR THE FILLING AND GRADING ON THE LANDFILL CAP.

St Location	DIAM. (IN) Do	W1	W2	La (FT)	V 25YR (FPS)	Q 25YR (CFS)	d 50*	D
OUTLET PIPE	18"	4.5'	9.5'	9'	8.57	75.01	0.4'	0.9'

*USE G.D.O.T. TYPE 3 RIPRAP
 NOTE: MAXIMUM TAILWATER CONDITIONS

STRUCTURAL PRACTICES				
CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Co	CONSTRUCTION EXIT			A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.
Fr	FILTER RING			A temporary stone barrier constructed at storm drain inlets and pond outlets.
Rt	RETRO FITTING			A device or structure placed in front of a permanent stormwater detention pond outlet structure to serve as a temporary sediment filter.


VEGETATIVE PRACTICES				
CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)			Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Du	DUST CONTROL ON DISTURBED AREAS			Controlling surface and air movement of dust on construction site, roadways and similar sites.
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.

LEGEND

	EXISTING	PROPOSED
LIMITS OF DISTURBANCE		
BUFFER LINE		
SILT FENCE		
PROPERTY LINE		
MONITORING WELL		
METHANE MONITORING WELL		
METHANE EXTRACTION WELL		
CONTOUR		
VEGETATION		
STAND PIPE		
HEADWALL		
RIP RAP		
EROSION CONTROL MATTING		

GSWCC GEORGIA SOIL AND WATER CONSERVATION COMMISSION
 Kent S McCormick
 Level II Certified Design Professional
 CERTIFICATION NUMBER: 0000000430
 ISSUED: 08/17/2020 EXPIRES: 08/17/2023

811
 Know what's below.
 Call before you dig.



NO.	DATE	DESCRIPTION


TRIPLE POINT ENGINEERING
 5223 Riverstone Drive • Suite 101 • Macon, Georgia 31210
 phone: 478-476-0700 • fax: 478-476-0776 • www.tpoinc.com

INITIAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN
 HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
 PEACH COUNTY, GEORGIA

REGISTERED PROFESSIONAL ENGINEER
 KENT S. MCCORMICK
 No. 2138
 1/27/2023

PROJECT NO.: PCO 058
 DATE: DECEMBER 2021
 SCALE: 1"=100'

6.0



St Location	DIAM. (IN) D _o	W1	W2	La (FT)	V 25YR (FPS)	Q 25YR (CFS)	d 50*	D
DN#1	15"	4'	9.5'	8'	1.83	1.7	9"	1.5'
DN#2	18"	4.5'	14'	12'	5.37	8.87	9"	1.5'

*USE G.D.O.T. TYPE 3 RIPRAP
NOTE: MINIMUM TAILWATER CONDITIONS

Sd4-C DRAINAGE AREA 5.0 ACRES
DISTURBED AREA = 4.88 ACRES SHADED
REQUIRED STORAGE = 335 CY
PROVIDED STORAGE (68' WIDE X 143' LONG X 2' DEEP) = 580 CY
STORMWATER DISCHARGE, STORMWATER
LEAVES BY SHEET FLOW, NO MONITORING.


GSWCC GEORGIA SOIL AND WATER
CONSERVATION COMMISSION

Kent S McCormick
Level II Certified Design Professional


CERTIFICATION NUMBER: 0000000430
ISSUED: 08/17/2020 EXPIRES: 08/17/2023

LEGEND

	EXISTING	PROPOSED
LIMITS OF DISTURBANCE	---	---
BUFFER LINE	---	---
SILT FENCE	---	XX
PROPERTY LINE	---	---
MONITORING WELL	⊙	⊙
METHANE MONITORING WELL	⊙	⊙
METHANE EXTRACTION WELL	⊙	⊙
CONTOUR	---	---
VEGETATION	---	---
STAND PIPE	---	---
HEADWALL	---	---
RIP-RAP	---	---
EROSION CONTROL MATTING	---	---



TYPICAL DOWNDRAIN DETAIL
N.T.S.



STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Co	CONSTRUCTION EXIT			A crushed stone pad located at the construction site exit to provide a place for removing mud from tires thereby protecting public streets.
Dn2	PERMANENT DOWNDRAIN STRUCTURE			A paved chute, pipe, sectional conduit or similar material designed to safely conduct surface runoff down a slope.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.
Sd4	TEMPORARY SEDIMENT TRAP			A small temporary pond that drains a disturbed area so that sediment can settle out. The principle feature distinguishing a temporary sediment trap from a temporary sediment basin is the lock of a pipe or riser.
Fr	FILTER RING			A temporary stone barrier constructed at storm drain inlets and pond outlets.
Rt	RETRO FITTING			A device or structure placed in front of a permanent stormwater detention pond outlet structure to serve as a temporary sediment filter.
St	STORM DRAIN OUTLET PROTECTION			A paved or short section of riprap channel at the outlet of a storm drain system preventing erosion from the concentrated runoff.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)			Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Du	DUST CONTROL ON DISTURBED AREAS			Controlling surface and air movement of dust on construction site, roadways and similar sites.
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.

ISSUE SEQUENCE

NO.	DATE	DESCRIPTION

TRIPLE POINT ENGINEERING

5223 Riverstone Drive • Suite 101 • Macon, Georgia 31210
phone 478-476-0700 • fax 478-476-0776 • www.tpointeng.com

INTERMEDIATE EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN

HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
PEACH COUNTY, GEORGIA

REGISTERED PROFESSIONAL ENGINEER
KENT S. MCCORMICK
No. 2138
12/21/2023


PROJECT NO.: PCO 058
DATE: DECEMBER 2021
SCALE: 1"=100'

7.0



STRUCTURAL PRACTICES				
CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
St	STORM DRAIN OUTLET PROTECTION			A paved or short section of riprap channel at the outlet of a storm drain system preventing erosion from the concentrated runoff.

VEGETATIVE PRACTICES				
CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.




LEGEND

LIMITS OF DISTURBANCE	EXISTING	PROPOSED
BUFFER LINE		
SILT FENCE		
PROPERTY LINE		
MONITORING WELL		
METHANE MONITORING WELL		
METHANE EXTRACTION WELL		
CONTOUR		
VEGETATION		
STAND PIPE		
HEADWALL		
RIP RAP		
EROSION CONTROL MATTING		

NO.	DATE	ISSUE SEQUENCE	DESCRIPTION

TRIPLE POINT ENGINEERING
 5223 Riverside Drive • Suite 101 • Macon, Georgia 31210
 phone 478.476.0700 • fax 478.476.0776 • www.tpointeng.com

FINAL EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN
 HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 111-004D(SL)
 PEACH COUNTY, GEORGIA



GSWCC GEORGIA SOLID AND WATER CONSERVATION COMMISSION
 Kent S McCormick
 Level II Certified Design Professional
 CERTIFICATION NUMBER: 0000000430
 ISSUED: 08/17/2020 EXPIRES: 08/17/2023

811
 Know what's below. Call before you dig.
 PROJECT NO.: PCO 058
 DATE: DECEMBER 2021
 SCALE: 1"=100'
 GRAPHIC SCALE IN FEET
 SCALE: 1"=100'

8.0

STORMWATER DISCHARGE FROM THIS SITE IS PERMITTED AND GOVERNED BY NPDES GENERAL PERMIT NO. GAR 100001. THE SAMPLING, RECORD KEEPING, AND INSPECTION REQUIREMENTS OF THE PERMIT ARE THE RESPONSIBILITY OF THE PRIMARY PERMITTEE, AND ARE HEREBY INCORPORATED INTO THIS PLAN. IT IS THE RESPONSIBILITY OF THE PRIMARY PERMITTEE TO CONTACT THE ENGINEER AT 478-476-0700 TO NOTIFY HIM OF THE START OF LAND DISTURBING ACTIVITIES. THE PRIMARY PERMITTEE IS RESPONSIBLE FOR SUBMITTING A NOTICE OF INTENT AT LEAST 14 DAYS PRIOR TO CONSTRUCTION AND A NOTICE OF TERMINATION ONCE FINAL STABILIZATION HAS BEEN ACHIEVED.

- 1. These notes are taken from the Erosion, Sedimentation, and Pollution Control Plan Checklist for stand alone construction projects as published by the Commission on January 1, 2022.
2. The Level II certification number and seal of the certified Design Professional can be found on each sheet pertaining to the ES&PC plan (6-10).
3. The limits of disturbance does not exceed 50 acres within the project area.
4. The name and phone number of the 24-hour local contact responsible for erosion, sedimentation and pollution shall be a designee of the site contractor.
5. Primary Permittee information:
6. Total acreage of project property: ±55 Acres
7. The GPS location of the construction exit for the site is Latitude N 32.571545°, Longitude W 83.758080°.
8. The initial and/or revision date of this plan is depicted on the title block of each plan sheet.
9. The construction activity includes BMP installation and maintenance, outlet structure replacement, installation of an emergency spillway, and repairing/regrading portions of the cover at House's Mill Road Sanitary Landfill in Peach County.
10. A vicinity map showing site's relation to surrounding areas is depicted on the Title Sheet of this plan.
11. The project receiving waters include Dry Run Creek.

- 12. I certify under penalty of law that this plan was prepared after a site visit to the locations described herein by myself or my authorized agent, under my direct supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.
13. I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia".
14. The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements, perimeter control BMPs, and sediment basins in accordance with part IV.A.5 within 7 days after installation.
15. Non-exempt activities shall not be conducted within the 25- or 50-foot undisturbed stream buffers as measured from the point of wretsed vegetation or within 25 feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits.
16. There are no buffer encroachments associated with the work on this plan.
17. Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional.
18. Waste materials shall not be discharged to waters of the State, except as authorized by a section 404 permit.
19. The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities.
20. Erosion control measures shall be maintained at all times. If full implementation of the approved plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source.
21. Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding.
22. This construction activity does not discharge storm water into, or within one linear mile of a Bioti Impaired Stream Segment.
23. This construction activity does not discharge storm water into, or within one linear mile of a Bioti Impaired Stream Segment.
24. Wash water from concrete truck hoppers, chutes and tools used for concrete construction shall be contained in a temporary truck wash area located at the site entrance.
Paint and/or other chemicals shall be stored in secured facilities with restricted access to employees only. Cleanup and disposal of this material shall be in accordance with all recognized local and federal requirements. All disposal shall be in approved of site waste facilities classified to accept that material.

- (3). Sampling by the permittee shall occur for the following qualifying events:
a. For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.50 inch with a storm water discharge that occurs during business hours as defined in this permit after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling location;
b. In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the sampling location, whichever comes first;
c. At the time of sampling performed pursuant to (a) and (b) above, if BMPs in the area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained.
d. Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not required.
e. Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.
*Note that the Permittee may choose to meet the requirements of (a) and (b) above by collecting turbidity samples from any rain event that reaches or exceeds 0.5 inch and allows for monitoring at any time of the day or week.
Sampling shall be collected by "grab samples" performed in accordance with the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001."
(1). Sample container should be labeled prior to collecting the samples.
(2). Samples should be well mixed before transferring to a secondary container.
(3). Large mouth, well cleaned and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.
(4). Manual, automatic or rising stage sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection.
(5). Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.E.

- 25. BMP's for Remediation of Petroleum Leaks & Spills
The location for petroleum storage (if any) is shown on SHEET 4-5.
• Local, State and manufacturer's recommended methods for spill cleanup shall be clearly posted and procedures shall be made available to site personnel.
• Material and equipment necessary for spill cleanup shall be kept in the material storage areas.
• Spill prevention practices and procedures shall be reviewed after a spill and adjusted as necessary to prevent future spills.
• All spills shall be cleaned up immediately upon discovery. All spills shall be reported as required by local, State, and Federal regulations.
• For spills that impact surface water (leave a sheen on surface water), the EPA's National Response Center (NRC) shall be contacted within 24 hours at 1-800-424-8802.
• For spills of an unknown amount, the EPA's National Response Center (NRC) shall be contacted within 24 hours at 1-800-424-8802.
• For spills greater than 25 gallons and no surface water impacts occur, the Georgia E.P.D. shall be contacted within 24 hours at 1-800-241-4413.
• For spills less than 25 gallons and no surface water impacts occur, the spill shall be cleaned up and local agencies shall be contacted as required.
The contractor shall notify the licensed professional who prepared this Plan if more than 1200 gallons of petroleum is stored onsite (this includes capacities of equipment) or if any one piece of equipment has a capacity greater than 600 gallons.
All petroleum products shall be stored and used in an area that provides a secondary containment feature, and shall be located in an area with the least foreseeable impact if a catastrophic event should occur.
26. The following measures will be installed during construction to control pollutants in stormwater after construction operations have been completed.
27. Stored building materials shall be covered with a tarp on site at the material staging area selected by the contractor.
28. Product Specific Practices
Petroleum Based Products- Containers for products such as fuels, lubricants, and tars shall be inspected daily for leaks and spills.
Paints/Finishes/Solvents- All products shall be stored in tightly sealed original containers when not in use.
Concrete Truck Washing- NO concrete trucks shall be allowed to wash out or discharge surplus concrete or drum wash water onsite.
Fertilizer/Herbicides- These products shall be applied at rates that do not exceed the manufacturers specifications or above the guidelines set forth in the crop establishment or in the GSWCC Manual for Erosion and sediment control in Georgia.
Building Materials- No building or construction materials shall be buried or disposed of onsite.
29. A description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization) is depicted on Sheet 7 of this plan.
b. The downstream sample for each receiving water(s) must be taken downstream of the confluence of the last storm water discharge from the permitted activity (i.e., the discharge farthest downstream at the site) but upstream of any other storm water discharge not associated with the permitted activity.
c. Ideally the samples should be taken from the horizontal and vertical center of the receiving water(s) or the storm water outfall channel(s).
d. Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall storm water channel.
e. The sampling container should be held so that the opening faces upstream.
f. The samples should be kept free from floating debris.
g. Sheet flow that flows onto undisturbed natural areas or areas stabilized by the project is not required to be sampled.
h. All sampling pursuant to this permit must be done in such a way (including generally accepted sampling methods, locations, timing and frequency) as to accurately reflect whether storm water runoff from the construction site is in compliance with the standard set forth in Parts III.D.3. or III.D.4., whichever is applicable.
34. In accordance with Appendix B, the maximum NTU's from each outfall shall not exceed 50 NTUs.
35. The sampling locations are depicted on Sheets 6-7 of this plan.
36. This plan is phased into an initial sediment storage and perimeter control BMP plan, and intermediate grading and drainage BMP plan, and a final BMP plan as follows:
37. A graphic scale and north arrow are depicted on Sheets 1-4, 6-8.
38. Existing and proposed contour lines are depicted on Sheet 1-4, 6-8.
39. No alternate BMP's are proposed in this plan.
40. No alternate BMP's are proposed in this plan.
41. Delineation of undisturbed state water buffers are shown on sheet 1 of this plan.
42. Dry Run Creek is located within 200' of the project site.
43. The acreage of contributing drainage basins to the sediment pond is 42 acres. The basin is delineated on this sheet.

- 30. Inspections & Record Keeping:
a. Permittee requirements.
(1) Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect:
(2) Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday.
(3) Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches or greater (unless such storms and after 5:00 PM on any Friday or on any non-working Sunday, or any non-working Federal holiday, in which case the inspection shall be completed by the end of the next business day and/or working day, whichever comes first).
(4) Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is received by EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
(5) Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection.
(6) A report of each inspection that includes the name(s) of personnel making each inspection, the date(s) of each inspection, major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan and actions taken in accordance with Part IV.D.4.a.(5) of GAR 100001 shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction site that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD.
31. Sampling Frequency and Reporting of Results:
(1) The Primary Permittee must sample at least once for each rainfall event described below.
(2) However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the storm water discharge.
PAGE 8 OF 8
44. No hydrology report is necessary for this project.
45. The pre-construction curve number is estimated to be 65.
46. One new storm-drain pipe is proposed that has a velocity of 8.57 fps.
47. Soil series and their delineation are depicted on Sheet 6 of this plan.
48. The limits of disturbance is shown within the shaded area outlined by a dashed heavy gray line and labeled "limits of construction, limits of disturbance," as shown on 6-7.
49. 67 cubic yards of sediment storage per disturbed acre drained will be stored in excavated inlet sediment traps & sediment traps.
50. Best management practices depicted on Sheets 6-8 of this plan are consistent with the requirements of the Manual for Erosion and Sediment Control in Georgia.
51. Detailed drawings for all structural practices are depicted on sheet 9 of this plan.
52. A vegetative plan, noting temporary and permanent vegetative practices, is depicted on Sheet 9 of this plan.



DRAINAGE BASIN MAP



GSWCC GEORGIA SOIL AND WATER CONSERVATION COMMISSION
Kent S McCormick
Level II Certified Design Professional
CERTIFICATION NUMBER: 0000000430
ISSUED: 08/17/2020 EXPIRES: 08/17/2023

TRIPLE POINT ENGINEERING
5223 Riverstone Drive • Suite 101 • Macon, Georgia 31210
phone 478-476-0700 • fax 478-476-0776 • www.tpointeng.com
NPDES PLAN
HOUSER'S MILL ROAD SANITARY LANDFILL COVER & POND OUTLET REPAIR; PERMIT # 11-11-004D(SL)
PEACH COUNTY, GEORGIA
PROJECT NO.: PCO 058
DATE: DECEMBER 2021
SCALE: N.T.S.
10