

ADDENDUM NO. 3

DATE: September 9, 2019

TO: All Bidders

FROM: Penny Owens, Assistant Purchasing Agent

SUBJECT: Addendum No. 3 – Sheffield Drive Sidewalk Project

BIDS TO BE OPENED: September 11, 2019, at 11:00:00 a.m. (Eastern)

This addendum becomes a part of the Contract Document and modifies the original specifications as noted.

Bid Proposal

A revised bid proposal form is attached to this addendum. The following is a summary of the changes made:

1. Item No. 20.11, 6” Concrete Pipe has been removed.
2. Item No. 20.11, 6” PVC Pipe (Schedule 80) has been added.

Clarification of Contract Documents and Specifications:

The following are responses to questions received from potential bidders:

Questions

1. Q: Our suppliers tell us 6” Concrete Pipe does not exist. Is PVC and a Fernco Fitting acceptable?

A: Yes, the Contractor shall use Schedule 80 PVC pipe to tie into the existing 6” concrete pipe at 403 Wesley Road. The Contractor shall run the new PVC pipe behind the curb and into the back of the new catch basin (structure 9). All materials, equipment, and labor necessary to perform this work and connections to existing pipe and new catch basin will be included in the unit cost for Item No. 20.11, 6” PVC Pipe (Schedule 80), and be paid for per linear foot.

2. Q: Are TDOT structures really required?

A: Yes, for the purpose of the bid, all bidders should use the references TDOT Standard Structures.

END OF ADDENDUM NO. 3

BID PROPOSAL
CITY OF KNOXVILLE, TENNESSEE

Sheffield Drive Sidewalk Improvements Project
Project No. 19D-S-0675

TO THE PURCHASING AGENT
CITY OF KNOXVILLE, TENNESSEE

_____ hereby propose(s) to furnish all material, labor, and appliances and do all work required to complete the Contract for the Sheffield Drive Sidewalk Improvements Project, Project No. 19D-S-0675, located in the City of Knoxville, Tennessee, in a workmanlike manner and in accordance with the plans of the Department of Engineering and specifications herewith attached.

Bidder further agrees that in case of failure to sign a delivered contract within thirty (30) days, the certified check or bid bond accompanying this bid and the proceeds thereof shall be the property of the City of Knoxville if the City chooses to retain said bid bond or check.

BID SCHEDULE

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	PRICE PER UNIT	TOTAL PRICE PER ITEM
1.10	Mobilization of Forces, Supplies and Equipment	LS	1	_____	_____
2.10	Clearing and Grubbing	LS	1	_____	_____
3.10	Removal of Structures and Obstructions	LS	1	_____	_____
4.20	Common Excavation	CY	1,050	_____	_____
4.40	Borrow Excavation	CY	100	_____	_____
5.10	Mineral Aggregate Base	TON	390	_____	_____
5.30	Maintenance Stone	TON	435	_____	_____
7.10	Tack Coat	GAL	85	_____	_____
9.20	Bituminous Plant Mix, Grading B-M	TON	170	_____	_____
9.50	Bituminous Plant Mix, Grading C-S	TON	25	_____	_____
10.10	Asphaltic Concrete Surface, Grading D	TON	40	_____	_____
12.62	6" Concrete Combined Curb & Gutter, Type 6-30	LF	70	_____	_____
12.65	6" Detached Concrete Curb, Sloping	LF	207	_____	_____

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	PRICE PER UNIT	TOTAL PRICE PER ITEM
13.10	Concrete Sidewalks	SF	19,200		
13.20	Concrete Driveways	SF	1,000		
13.21	Concrete Driveways, High Early Strength	SF	4,000		
20.10	Gutter Drain (4" PVC)	LF	25		
20.11	6" PVC Pipe (Schedule 80)	LF	8		
20.12	15" R.C.P. (Class III)	LF	26		
20.13	15" R.C.P. (Class V)	LF	68		
20.14	18" R.C.P.	LF	34		
20.16	24" R.C.P.	LF	39		
20.33	19" X 30" R.C.E.P.	LF	35		
20.41	8" Non-Perforated HDPE	LF	8		
20.42	15" HDPE	LF	25		
21.10	Infiltration	LF	140		
21.20	French Drain	LF	30		
22.10	No. 10 Catch Basin	EA	1		
22.12	No. 12 Catch Basin (0' - 4' Deep)	EA	2		
22.14	No. 14 Catch Basin (0' - 4' Deep)	EA	2		
22.21	15" Flared End Section, HDPE	EA	1		
22.41	Drop Inlet	EA	1		
25.10	Hard Armor	SF	15		
26.10	Topsoil	SY	3,300		
27.10	Seed/Straw	SY	330		
28.10	Sodding	SY	3,300		
31.10	Erosion & Sediment Control	LS	1		
34.10	Construction Area Traffic Control	LS	1		
35.10	Residential Light Pole Relocation	LS	1		
39.10	Thermoplastic Pavement Marking (Line)	LF	240		
42.10	Concrete Ditch	SF	240		
63.10	Signage	LS	1		
70.20	Tactile Warning System, Cast-In-Place	EA	6		
TOTAL BID				\$	

TOTAL BID (In Words):