

# Tom Green County



113 W. Beauregard  
San Angelo, Texas 76903  
325-659-6500/Fax 325-659-5441

## RFB 21-008 4<sup>th</sup> Road Low Water Crossing

November 18, 2020

### ADDENDUM NO 1: Notice to Bidders

1. Addition to Scope:  
Vendor is responsible for materials testing and reporting for compaction, concrete, and asphalt testing.
2. The drawing shows the new concrete to be wider than the existing road. Do you have the exact width measurements for the material to be installed?  
TGC Response: Width of concrete to be installed shall match existing concrete, 24' wide.
3. The drawing shows "purple" as the existing concrete low water crossing. Will that area be removed and replaced or will that stay in place  
TGC Response: Existing concrete will stay in place.
4. If it is to stay in place, do we need to dowel into the existing concrete with the newly poured concrete.  
TGC Response: Yes, new concrete shall be doweled into existing concrete structure.
5. Are there any specs for expansion joints or saw cuts  
TGC Response: As needed
6. Can the road be closed for the entire project including curing time for concrete?  
TGC Response: Yes the road may be closed for the duration of the entire project.

Please include this signed addendum with your Response.

Sincerely,

Dustin Klein  
Procurement Supervisor  
Tom Green County

\_\_\_\_\_  
Company

\_\_\_\_\_  
Date

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Please Print Name and Title