

ADDENDUM NUMBER ONE
FIRE STATION, COLFAX COUNTY DISTRICT 8

April 9, 2019 Page 1 of 2

The Plans set dated March 22, 2019 with the Project Manual dated March 22, 2019 is revised as described in this Addendum. When in conflict with other information issued prior to the date of this addendum then this addendum takes precedence. All cost and schedule implications of these revisions are to be incorporated into the Bid.

Project Manual

Page 5 of 11

At the end of the first paragraph in the Cabinet description add:
"Cabinets will be Executive series."

Plans

Sheet A3

Cross out the project title along the right edge of the sheet labeling a cabin project. Change the project title to the Raton Fire Station #1 project to match the other A sheets.

At the Altered Kitchen north wall detail found in the upper left corner of the sheet, change the 48" cabinet width dimension to 18".

At the Altered Kitchen east wall detail found near the upper center of the sheet, add the note:
"Microwave cabinet customized by manufacturer to 16" deep. Line all 5 sides of the interior with 3/16 inch maple veneer panel from manufacturer. Field cut and install the maple veneer lining over the interior birch veneer. Coordinate final installation details with architect and provide accessories as needed."

Sheet M1

At the Mechanical Floor Plan in room 101 Kitchen add the note:

"Extend the two ducts into the cabinet soffits so that the two registers are at the vertical face of the soffits instead of at the east wall of the kitchen."

At the Mechanical Floor Plan eliminate the reference to a soffit along the south edge of 104 East Sleeping Room.

At Mechanical Keyed Note 5 regarding 104 East Sleeping Room add:

"Sufficient space is present above the lay-in ceiling and below the steel girder so a transition in duct size to 16" x 6" is not required under the girder."

Sheet E-101

Above the General Notes add:

"General Notes and Electrical Specifications are general for all of the engineer's projects so not all items apply. Examples include references to drinking fountains and exterior lighting which are not a part of this project."

At Electrical Specifications note 8 change the third sentence regarding pitch pans to:

"Coordinate with roofing subcontractor for sealing conduit penetrations through roof."

Sheet E-102

At the Modified Lighting Plan eliminate the reference to a soffit along the south edge of 104 East Sleeping Room.

At the Modified Power Plan add the note:

“Consult fire chief during construction for location of up to eight new wall receptacles not shown. New receptacles will be in new and existing framed walls in the project area.”

and

“Exposed conduit will be used at the surface of existing masonry walls where concealing the conduit and wiring isn’t an option. Conduit can be metal pipe painted to match the wall or can be metal wiremold.”

At Keyed Note 5 add:

“All new and existing wall receptacles and wall switches will be fitted with new receptacles, switches, and plates, white in color.”

END OF ADDENDUM NO. 1