

CITY OF GRIFFIN  
GRIFFIN GOLF COURSE BRIDGE REPLACEMENTS  
BID # 24-007

FROM: PARAGON CONSULTING GROUP, INC.  
350 AIRPORT ROAD  
GRIFFIN, GA 30224

TO: ALL BIDDERS OF RECORD

RE: Addendum No. 4, dated March 14, 2024

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 2024.

This Addendum consists of one (1) page and a revised Bid Tabulation consisting of four (4) pages.

CONTRACT DOCUMENTS AND SPECIFICATIONS

- Add. 1.1 Modification: A revised Bid Tabulation dated March 14, 2024 (REVISION #2), is attached to this Addendum and becomes a part of the Contract Documents. All Bidders should use the revised Bid Tabulation when submitting a bid.
- Add. 1.2 Modification: The line item 'ROAD BARRICADES FOR TRAFFIC CONTROL' under section **EROSION CONTROL** has been removed. This change applies to the Bid Tabulation for Bridge B.
- Add. 1.3 Modification: The line item 'PERMANENT GRASSING, INCLUDING MULCH' has been added with a quantity of 2,000 SF. This change applies to the Bid Tabulation for Bridge B.
- Add. 1.4 Modification: The duplicate line item 'TRENCH ROCK' has been removed from the Bid Tabulation for Bridge B.

End of Addendum No. 4

**CITY OF GRIFFIN  
GRIFFIN GOLF COURSE BRIDGE REPLACEMENTS  
BID TABULATION**

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>BRIDGE A</b>					
<b>GENERAL</b>					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING BY REGSITERED SURVEYOR	LS	1		
4.	AS-BUILT SURVEY BY REGISTERED SURVEYOR	LS	1		
<b>General Subtotal =</b>					
<b>DEMOLITION/REMOVAL</b>					
5.	COMPLETE DEMOLITION OF EXISTING CONCRETE BRIDGE INCLUDING OFFSITE DISPOSAL	LS	1		
6.	SAW CUT ASPHALT (VARIOUS DEPTHS)	LF	130		
7.	REMOVAL OF ASHPALT PAVING COMPLETE INCLUDING OFFSITE DISPOSAL (VARIOUS THICKNESSES)	SY	163		
8.	REMOVAL OF DEBRIS AND CONCRETE IN STREAM	LS	1		
9.	REMOVAL OF EXISTING GATES & POSTS	LS	1		
10.	REMOVAL & DISPOSAL OF CONCRETE POURED WALL SECTION (VERTICAL SAW CUT INCLUDED)	LS	1		
11.	REMOVAL & DISPOSAL OF STACKED CONCRETE WALL SECTION	LS	1		
<b>Demolition/Removal Subtotal =</b>					
<b>NEW STRUCTURE - CONTECH ALUMINUM BOX CULVERT #51</b>					
12.	ALUMINUM BOX CULVERT ASSEMBLY & INSTALLATION INCLUDING ALUMINUM WING WALLS COMPLETE	LS	1		
13.	ALUMINUM BOX CULVERT FOUNDATION SYSTEM COMPLETE PER PLANS	LS	1		
14.	PREPARATION FOR INSTALLATION OF CONTECH STRUCTURE, WING WALL EMBEDMENT & TIE BACKS	LS	1		
15.	#4 STONE FOR FOUNDATION BASE	TN	35		
16.	G.A.B. IN PLACE FOR BACKFILL OF CULVERT & WINGWALLS	TN	591		
17.	ASPHALT PAVING (6 : 2 : 1 1/2) SECTION)	SY	163		
18.	GRADING COMPLETE (TOPSOIL & FINE GRADING)	LS	1		
<b>New Struction - Contech Aluminum Box Culvert #51 Subtotal =</b>					
<b>ASPHALT PAVING &amp; CONCRETE FLATWORK</b>					
19.	8" REINFORCED CONCRETE BRIDGE SLAB INCLUDING REINFORCING PER DETAIL	SF	540		
20.	32" TALL CONCRETE BARRIER	LF	56		
21.	CONCRETE CURB AT BASE OF BARRIER ON BRIDGE	LF	56		
22.	CONCRETE AT CART PATH - 5" THICK	SF	245		
<b>Paving &amp; Concrete Flatwork Subtotal =</b>					
<b>EROSION CONTROL &amp; DIVERSION</b>					
23.	TYPE 'C' SILT FENCE INLCUDING MAINTENANCE & REMOVAL	LF	525		
24.	SAND BAGS FOR FLOW DIVERSION, INCLUDING MAINTENANCE & REMOVAL	LF	140		
25.	FLOW DIVERSION & FOUNDATION EXCAVATION WATER CONTROL BY CONTRACTOR MEANS	LS	1		
26.	HAY BALES, INCLUDING MAINTENANCE & REMOVAL	LF	100		
27.	BERMUDA SOD	SF	550		
28.	STRAW/COCONUT MATTING	SF	600		
29.	GABION EROSION SYSTEM - SCOURLOK	LF	44		
30.	REINFORCED SLOPE STABILIZATION - ARMORMAX	SY	42		

Item	Description	Unit	Quantity	Unit Price	Item Total
31.	TEMPORARY GRASSING, INCLUDING MULCH	SF	650		
32.	PERMANENT GRASSING, INCLUDING MULCH	SF	2,000		
33.	TYPE III RIP RAP	TN	50		
34.	CONCRETE WASHOUT PER PLANS	EA	2		
<b>Erosion Control &amp; Diversion Subtotal =</b>					
<b>MISCELLANEOUS</b>					
35.	ONE WAY SIGNS INCLUDING INSTALLATION	EA	3		
36.	SINGLE SWING GATE - 18' LONG	EA	1		
37.	BARRIER REFLECTORS - SHUR-TITE 3" WHITE	EA	14		
38.	4-INCH WHITE STRIPING (PARKING SPACES) THERMOPLASTIC	LF	34		
39.	ROAD BARRICADES FOR TRAFFIC CONTROL	LF	146		
40.	ORANGE BARRIER FENCE - 4' HIGH	LF	130		
39.	WING WALL TO EXISTING CONCRETE WALL DETAIL	LS	1		
40.	WING WALL TO EXISTING STACKED CONCRETE WALL DETAIL	LS	1		
41.	36-INCH DIAMETER TREE REMOVAL AND DISPOSAL	LS	1		
42.	TRENCH ROCK	CY	10		
<b>Miscellaneous Subtotal =</b>					
<b>TOTAL CONSTRUCTION</b>					

**CITY OF GRIFFIN  
GRIFFIN GOLF COURSE BRIDGE REPLACEMENTS  
BID TABULATION**

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>BRIDGE B</b>					
<b>GENERAL</b>					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING BY REGSITERED SURVEYOR	LS	1		
4.	AS-BUILT SURVEY BY REGISTERED SURVEYOR	LS	1		
<i>General Subtotal =</i>					
<b>DEMOLITION/REMOVAL</b>					
5.	COMPLETE DEMOLITION OF EXISTING CONCRETE BRIDGE INCLUDING OFFSITE DISPOSAL	LS	1		
6.	SAW CUT ASPHALT (VARIOUS DEPTHS)	LF	79		
7.	REMOVAL OF ASHPALT PAVING COMPLETE INCLUDING OFFSITE DISPOSAL (VARIOUS THICKNESSES)	SY	162		
8.	REMOVAL OF DEBRIS AND CONCRETE IN STREAM	LS	1		
9.	REMOVAL OF EXISTING GATE & POSTS	LS	1		
10.	REMOVAL OF CONCRETE FLUME NOTED ON DEMO PLAN	LS	1		
<i>Demolition/Removal Subtotal =</i>					
<b>NEW STRUCTURE - CONTECH ALUMINUM BOX CULVERT #52</b>					
11.	ALUMINUM BOX CULVERT ASSEMBLY & INSTALLATION INCLUDING ALUMINUM WING WALLS COMPLETE	LS	1		
12.	ALUMINUM BOX CULVERT FOUNDATION SYSTEM COMPLETE PER PLANS	LS	1		
13.	PREPARATION FOR INSTALLATION OF CONTECH STRUCTURE, WING WALL EMBEDMENT & TIE BACKS	LS	1		
14.	#4 STONE FOR FOUNDATION BASE	TN	35		
15.	G.A.B. IN PLACE FOR BACKFILL OF CULVERT & WINGWALLS	TN	618		
16.	ASPHALT PAVING (6 : 2 : 1 1/2) SECTION)	SY	162		
17.	GRADING COMPLETE (TOPSOIL, FINE GRADING, & REPLACEMENT OF EXISTING FILL EXCAVATED)	LS	1		
<i>New Structure - Contech Aluminum Box Culvert #52 Subtotal =</i>					
<b>PAVING &amp; CONCRETE FLATWORK</b>					
18.	8" REINFORCED CONCRETE BRIDGE SLAB INCLUDING REINFORCING PER DETAIL	SF	540		
19.	32" TALL CONCRETE BARRIER	LF	56		
20.	CONCRETE CURB AT BASE OF BARRIER ON BRIDGE	LF	56		
21.	CONCRETE FLUME	LS	1		
<i>Paving &amp; Concrete Flatwork Subtotal =</i>					
<b>STORM DRAINAGE</b>					
22.	18" CLASS III RCP	LF	14		
23.	4' DIAMETER MANHOLE	VF	7		
24.	4' FLAT LID WITH SQUARE OPENING	EA	1		
25.	4X4 RAISED LID WITH PEDESTALS	EA	1		
30.	CONCRETE FILL AT GABION	EA	1		
31.	CONCRETE HEADWALL	EA	1		
<i>Storm Drainage Subtotal =</i>					

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>EROSION CONTROL</b>					
32.	TYPE 'C' SILT FENCE INCLUDING MAINTENANCE & REMOVAL	LF	640		
33.	SAND BAGS FOR FLOW DIVERSION, INCLUDING MAINTENANCE & REMOVAL	LF	140		
34.	FLOW DIVERSION & FOUNDATION EXCAVATION WATER CONTROL BY CONTRACTOR MEANS	LS	1		
35.	HAY BALES, INCLUDING MAINTENANCE & REMOVAL	LF	100		
36.	BERMUDA SOD	SF	600		
37.	STRAW/COCONUT MATTING	SF	1,000		
38.	GABION EROSION SYSTEM - SCOURLOK	LF	100		
39.	REINFORCED SLOPE STABILIZATION - ARMORMAX	SY	56		
40.	TEMPORARY GRASSING, INCLUDING MULCH	SF	500		
41.	PERMANENT GRASSING, INCLUDING MULCH	SF	2,000		
42.	TYPE III RIP RAP	TN	50		
43.	CONCRETE WASHOUT PER PLANS	EA	2		
<b>Erosion Control Subtotal =</b>					
<b>MISCELLANEOUS</b>					
44.	STOP SIGN WITH POST COMPLETE	EA	1		
45.	ONE WAY SIGNS INCLUDING INSTALLATION	EA	2		
46.	12-INCH WHITE STOP BAR - 12' IN LENGTH	EA	1		
47.	DOUBLE SWING GATE - 10' LONG	EA	2		
48.	BARRIER REFLECTORS - SHUR-TITE 3" WHITE	EA	14		
49.	4-INCH WHITE STRIPING (PARKING SPACES) THERMOPLASTIC	LF	40		
50.	CONCRETE DUMPSTER PAD - 10'X10'X8"	LS	1		
51.	ROAD BARRICADES FOR TRAFFIC CONTROL	LF	100		
52.	ORANGE BARRIER FENCE - 4' HIGH	LF	146		
52.	45-INCH DIAMETER TREE REMOVAL AND DISPOSAL	LS	1		
53.	TRENCH ROCK	CY	10		
<b>Miscellaneous Subtotal =</b>					
<b>TOTAL CONSTRUCTION</b>					

TOTAL CONSTRUCTION FOR BRIDGE A \_\_\_\_\_

TOTAL CONSTRUCTION FOR BRIDGE B \_\_\_\_\_

**TOTAL CONSTRUCTION FOR BRIDGE A & BRIDGE B** \_\_\_\_\_