



THE CITY OF DAYTONA BEACH
OFFICE OF THE PURCHASING AGENT

Post Office Box 2451
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080
Fax (386) 671-8085

ADDENDUM NO. 4

DATE: November 28, 2018

PROJECT: ITB 19023
DR. MARTIN LUTHER KING, JR. BOULEVARD ROADWAY &
PEDESTRIAN IMPROVEMENTS PROJECT

OPENING DATE: DECEMBER 19, 2018, 2:00 PM

This addendum is hereby incorporated into the Request for Proposal for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~strikethrough~~.

1. Questions and Answers:

Q1: Will they be adding Directional Bores to the Pay Items as there are none at this time?

A1: **There are no directional bores in this project. The intent is that all of the lighting/ITS conduit be installed by an open cut while the contractor has the streets and sidewalks demolished.**

Q2: Note 31 says to add 1 spare 3" conduit to every bore with a pull box will these pull boxes be added to the pay items or be incidental to the bores?

A2: **Since there are no bores in the project it will not be required to install the additional 3" conduit and pull box.**

Q3: Note 37 talks about walls and bridges and working with the structural contractor. Are there to be any light pole pilasters on this project?

A3: **There are no walls or bridges in the project so there will be no structural engineer required. There are no light pole pilasters on the project – the poles are attached to a galvanized plate within the sidewalk. Refer to the "Typical Pole Detail" on sheet RL-13. Sheet RL-5 details the luminaire in the legend.**

2. All other terms and conditions remain the same.

Proposers will acknowledge receipt of this addendum where indicated on BID PROPOSAL FORM.

The City of Daytona Beach
Kirk Zimmerman, CPPB
Buyer