

**BID SCHEDULE  
FY21 ZADIE E. KUEHL DOG PARK**

BID DATE: \_\_\_\_\_

COMPANY NAME: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

Contractor shall furnish and install items as shown on the Drawings or called for in the Specifications. All costs not included in the schedule that are necessary to provide a complete, functional project as depicted in the Drawings and Specifications are to be considered incidental and merged with costs of other related bid items.

LS = Lump Sum    R&R = Remove and Replace    LF = Linear Feet    F&I = Furnish and Install  
SY = Square Yard    CY = Cubic Yard    EA = Each    Ton = Ton    LB = Pounds

**Schedule A**

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
1	Mobilization	LS	1		
2	Clearing and Grubbing	LS	1		
3	Earthwork	CY	700		
4	F&I Asphalt Concrete Pavement (411-E)	Ton	142		
5	F&I Asphalt Binder (307-BM)	Ton	189		
6	F&I Tack Coat	Ton	1		
7	F&I Prime Coat	Ton	3		
8	F&I Granular Base (303-01 Type A, Grade D )	Ton	435		
9	F&I 6-30 Curb and Gutter	LF	312		
10	F&I Select Backfill (sand)	CY	50		
11	F&I Temporary Silt Fence (with backing)	LF	220		
12	F&I Type E Headwall	EA	2		
13	F&I Machined Rip-Rap (Class A-1)	Ton	8		
14	F&I 24" Reinforced Concrete Pipe (Class III)	LF	30		
15	F&I Seed with Mulch	SY	725		
16	F&I Sod	SY	1035		
17	<b>F&amp;I 4" Class A Concrete Pad</b>	<b>SF</b>	200		
18	F&I 1" PVC pipe	LF	270		

19	F&I Black PVC Chain Link Fence (with 24 terminal posts)	LF	1200		
20	F&I River Creek Stone	Ton	53		
21	F&I 8' Wide Maintenance Gates	EA	2		
22	F&I Wall Gates	EA	6		
23	F&I Human/Dog Water Fountains	EA	2		
24	F&I Black Thermoplastic Benches	EA	5		
25	F&I Lighting Layout	LS	1		
26	Material/ Density Test	EA	1	\$2,000	
27	F&I Parking Lot Wheel Stops	EA	21		
28	Parking Lot Striping	LS	1		
29	F&I Temporary Construction Fence	LF	180		
30	<del>R&amp;R Handicap Parking Space and Ramp</del>	LS	4		
31	F&I Accessible Parking Sign	EA	2		
32	<b>Undercut</b>	CY	500		
33	<b>Utility Allowance</b>	LS	1	\$10,000	
				Total Bid Schedule A	

**Total Base Bid :** \_\_\_\_\_

\_\_\_\_\_ Dollars (\$ \_\_\_\_\_).