



HIGHLANDS COUNTY BOARD OF COUNTY
COMMISSIONERS (HCBCC)
PURCHASING DIVISION
600 S. Commerce Ave
Sebring, FL 33870
(863) 402-6500

DATE: February 18, 2022

BID NO. 22-003 ITB ADDENDUM No. 3

Project.: West Stryker Road Roadway Improvements Highlands County Project No.18008

The following represents clarification, additions, deletions, and/or modifications to the above referenced solicitation. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged. Words, phrases or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded, phrases or sentences represent additions to the original solicitation, as applicable.

Questions and Answers

Q1 I am a little confused on what we are supposed to do on Stryker Rd from STA 2+12.43 to STA39+40.47, STA 43+53.16 to STA79+78.46, and STA 85+40.19 to STA100+69.72. The typical calls for Mill 2.4" and to place 3" SP Asphalt and Base Group 9 (10" Base). It notes there is 8" existing base. Are we to simply mill the 2.4" and add the widening. Add to the existing Base to get 10" base or re Construct. I understand the total reconstruct from 39+40.47 to 43+53.16 and 79+78.46 to 85+40.19 and Oleander DR but am not clear on the other area. Please advise.

A1 From STA 2+12.43 to STA39+40.47, STA 43+53.16 to STA79+78.46, and STA 85+40.19 to STA100+69.72, all of the existing asphalt paving is to be milled. Using an average thickness of eight (8) inches for the existing shell rock, additional shell rock or limerock shall be added to achieve a completed base of 10-inch thickness. Please refer to the attached Geotechnical Report for additional reference in regards to existing material thickness of the roadway.

Attachments: A3-1 Revised Plan (5 Sheets)

A3-2 Geotech Report (17 Sheets)

Attached are the revised construction plan sheets and the following is a description of the changes:

Sheet 3 of 59: Changed Pay Item Footnote #3 from "Items No. 26 through 30..." to read "Items No. 27 through 31..."

Sheet 4 of 59: Removed "Milling" from Typical Section (STA. 39+40.47 TO STA. 43+53.16, STA. 79+78.46 TO STA. 85+40.19). Added a note to the "PAVEMENT RECONSTRUCTION" for the same Typical Section. Removed "Milling from Typical Section N. Oleander Drive.

Sheet 5 of 59: Changed note 2 under "BASE MATERIALS METHOD" to read "The contractor shall conduct testing for base materials per FDOT Specifications." Removed "& QUANTITIES" from the sheet title. Added symbol for "Flag cable Television".

Sheet 41 of 59: Added note to cross-section.

Sheet 42 of 59: Added note to cross-section.