



**BID TABULATION & EVALUATION REPORT**  
 Summary of Bid Proposals Received

BID NO. 2019-14																				EOR																					
Rank: Apparent Low Bidder																				Engineer's Opinion of Probable Cost																					
BIDDER: >>> Metro Express																				BIDDER: >>> V ENGINEERING & CONSULTING CORPORATION Miami, Florida				BIDDER: >>> National Water Main Cleaning Co.				BIDDER: >>> Pabon Engineering, Inc.				Engineer's Opinion of Probable Cost									
Item No.	MAP PAGE NO.	REPAIR ID	ADDRESS	BREAK LOCATION	Description of Work	Quantity	Unit	Unit Price	Bid Amount	Quantity	Unit	Unit Price	Bid Amount	Quantity	Unit	Unit Price	Bid Amount	Quantity	Unit	Unit Price	Amount																				
1	N/A	N/A	N/A	N/A	Mobilization and demobilization of all work	Lump Sum	1	Lump Sum	\$ 30,000.00	Lump Sum	1	Lump Sum	\$ 7,400.00	Lump Sum	1	Lump Sum	\$ 10,000.00	Lump Sum	1	Lump Sum	\$ 25,000.00	To Be Determined By Contractor																			
<b>Pump Station 300 - Town of Medley</b>																																									
2	2	LL1-300-4 LL2-300-4	NW 89th Ave & NW 100th Ter.	MH 304 to MH 303	Two (2) 6" diameter sewer lateral connection repairs with Top Hat pipe lining. One at 122 ft. and the other at 151 ft. from MH 304. Mainline is 10" diameter. MOT Included.	EA	2	\$4,200.00	\$ 8,400.00	EA	2	\$7,000.00	\$ 14,000.00	EA	2	\$4,600.00	\$ 9,200.00	EA	2	\$11,500.00	\$ 23,000.00	EA	2	\$ 5,600.00	\$ 11,200.00																
<b>Pump Station MCC - Town of Medley</b>																																									
3	5	LL1-MCC-1-2-D LL2-MCC-1-2-D LL3-MCC-1-2-D	NW 95th Ave. & NW 101st St.	MH MCC-22-1-2-D to MH MCC22-1-1	Three (3) 6" diameter sewer lateral connection repairs with Top Hat pipe lining at 57 ft., 123 ft. and at 221 ft. from manhole MCC-22-1-2-D. Mainline is 8" diameter. MOT Included.	EA	3	\$4,200.00	\$ 12,600.00	EA	3	\$7,000.00	\$ 21,000.00	EA	3	\$4,600.00	\$ 13,800.00	EA	3	\$10,500.00	\$ 31,500.00	EA	3	\$ 5,600.00	\$ 16,800.00																
4	6	PR-MCC-1-1	NW 95th Ave. & NW 101st St.	MH MCC-22-1-2-D to MH MCC22-1-2	8" diameter mainline pipe replacement (MH to MH). Repair to be conducted in three (3) phases (120 LF EA). Reestablishment of laterals. Dewatering allowed for repair and or excavation. To include Type I pavement full lane repair and restoration. MOT Included.	LF	360	\$185.00	\$ 66,600.00	LF	360	\$240.00	\$ 86,400.00	LF	360	\$340.00	\$ 122,400.00	LF	360	\$330.00	\$ 118,800.00	LF	360	\$ 250.00	\$ 90,000.00																
<b>Pump Station FEC-1 - Town of Medley</b>																																									
5	3	LL1-FEC-1-4-1	NW 116th Way & NW 100th Rd.	FEC-1-4-1 and FEC-1-1-1	One (1) 6" diameter sewer lateral connection repair with Top Hat pipe lining at 175 ft. from MH-FEC-1-4-1. Mainline is 8" diameter. MOT Included.	EA	1	\$4,200.00	\$ 4,200.00	EA	1	\$6,200.00	\$ 6,200.00	EA	1	\$5,000.00	\$ 5,000.00	EA	1	\$10,500.00	\$ 10,500.00	EA	1	\$ 5,600.00	\$ 5,600.00																
<b>Pump Station FEC-2 - Town of Medley</b>																																									
6	4	LL1-FEC-2	NW 116th Way & NW 106th Ter.	MH FEC-2-3-1 to MH FEC-2-1-2-D	One (1) 6" diameter sewer lateral connection repair with Top Hat pipe lining at ~2.5 ft. from MH FEC-2-3-1. One (1) 6" diameter sewer lateral connection repair with Top Hat pipe lining at ~0.5 ft. from MH FEC-2-1-2-D. Mainline is 8" diameter. MOT Included.	EA	1	\$4,200.00	\$ 4,200.00	EA	1	\$6,000.00	\$ 6,000.00	EA	1	\$5,000.00	\$ 5,000.00	EA	1	\$10,500.00	\$ 10,500.00	EA	1	\$ 5,600.00	\$ 5,600.00																
7	8	PR-FEC-2-2-5	NW 118th Way & NW 102nd Rd.	MH FEC 2-2-5 to MH FEC-2-2-4	6" diameter lateral is located at 62 ft. from FEC-2-2-5. Lateral Break is located at ~86 ft from the cleanout towards the mainline. No dewatering, only wet condition repair and excavation. To include Type I pavement full lane repair and restoration. Mainline is 8" diameter. MOT Included.	LF	10	\$850.00	\$ 8,500.00	LF	10	\$600.00	\$ 6,000.00	LF	10	\$2,675.00	\$ 26,750.00	LF	10	\$1,100.00	\$ 11,000.00	LF	10	\$ 800.00	\$ 8,000.00																
<b>Pump Station 703 - Town of Medley</b>																																									
8	7	PR-703-5	NW 122nd St. & Sysco Way.	MH 703-5 to MH 703-4	8" diameter mainline point repair at ~74 ft. from MH 703-5. Dewatering allowed for repair and or excavation. To include Type I pavement full lane repair and restoration. MOT Included.	LF	10	\$800.00	\$ 8,000.00	LF	10	\$800.00	\$ 8,000.00	LF	10	\$2,735.00	\$ 27,350.00	LF	10	\$1,100.00	\$ 11,000.00	LF	10	\$ 600.00	\$ 6,000.00																
<b>OTHER COSTS</b>																																									
9	Bonds and Insurance (INCLUDED IN ALL BID ITEMS)																				N/A																				
10	Maintenance of Traffic (INCLUDED IN ALL BID ITEMS)																				N/A																				
									Subtotal (Items 1 -8):	\$ 142,500.00										\$ 153,000.00										\$ 219,500.00										\$ 241,300.00	\$ 143,200.00
11	Contingency 10% (Items 1-8) NOT INCLUDED IN THIS CONTRACT																				N/A																				
<b>TOTAL BID AMOUNT (CORRECTED):</b>									\$ 142,500.00										\$ 153,000.00										\$ 219,500.00										\$ 241,300.00	\$ 143,200.00	
<b>SUBMITTED BID AMOUNT (AS WRITTEN):</b>									\$142,500.00										\$153,000.00										\$219,500.00										\$241,300.00		
<b>Discrepancy:</b>									\$0.00										\$0.00										\$0.00										\$0.00	\$143,200.00	

OTHER BIDS RECEIVED		
Rank	BIDDER'S NAME / Location	Bid Amount
5	E&M Equipment, Corp.	\$253,557.36
6	Ric-Man Internation, Inc.	\$405,500.00

**CERTIFICATION:**

I hereby certify to the Town of Medley that this Bid Tabulation and Evaluation is a true representation and summary of the Bids opened on October 15, 2019 for Town of Medley Bid No. ITB 2019-014, Emergency Repair Sanitary Sewer Project. All bids were evaluated by the Technical Review Committee meeting at the Town of Medley Utility Department on October 17, 2019 at 10:00 AM.

*Rodney Carrero-Santana* 10/17/19  
 Rodney Carrero-Santana PE, CFM, LEED AP  
 Snubbs Consulting, Inc.