

CITY OF GRIFFIN
DEPARTMENT OF CENTRAL SERVICES PAVING PROJECTS
SHOAL CREEK C&D LANDFILL AND TRANSFER STATION/RECYCLING CENTER
BID TABULATION

Item	Description	Unit	Quantity	Unit Price	Item Total
PROJECT A - TRANSFER STATION/RECYCLING CENTER PAVING					
GENERAL					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING (LAYOUT) BY REGISTERED SURVEYOR	LS	1		
4.	AS BUILT BY REGISTERED SURVEYOR	LS	1		
General Subtotal =					
PAVEMENT					
5.	SURFACE PREPARATION	SY	6,500		
6.	12" FDR BASE	SY	6,500		
7.	ASPHALT BINDER - 2" OF 19.5 MM SUPERPAVE	SY	6,500		
8.	ASPHALT TOPPING - 1.5" OF 12.5 MM SUPERPAVE	SY	6,500		
Pavement Subtotal =					
MISCELLANEOUS					
9.	24" RCP CLASS III	LF	60		
10.	GRAVEL STRIP	SY	164		
11.	FUEL TANK PAD	EA	2		
12.	SAW CUT CONCRETE DRIVE EDGE	LF	30		
Miscellaneous Subtotal =					
TOTAL CONSTRUCTION =					

CITY OF GRIFFIN
DEPARTMENT OF CENTRAL SERVICES PAVING PROJECTS
SHOAL CREEK C&D LANDFILL AND TRANSFER STATION/RECYCLING CENTER
BID TABULATION

Item	Description	Unit	Quantity	Unit Price	Item Total
PROJECT B - SHOAL CREEK C&D LANDFILL ENTRY DRIVE					
GENERAL					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING (LAYOUT) BY REGISTERED SURVEYOR	LS	1		
4.	AS-BUILT SURVEY BY REGISTERED SURVEYOR	LS	1		
5.	TRAFFIC CONTROL	LS	1		
				<i>General Subtotal =</i>	
				<i>Sanitary Sewer Subtotal =</i>	
PAVEMENT					
6.	SURFACE PREPARATION	SY	9,500		
7.	12" FDR BASE	SY	9,500		
8.	ASPHALT BINDER - 2" OF 19.5 MM SUPERPAVE	SY	9,500		
9.	ASPHALT TOPPING - 1.5" OF 12.5 MM SUPERPAVE	SY	9,500		
				<i>Pavement Subtotal =</i>	
EROSION CONTROL					
10.	GRASSING TEMPORARY	SF	6,500		
11.	GRASSING PERMANENT	SF	6,500		
12.	SILT FENCE	LF	275		
13.	CHECK DAMS - ROCK	EA	15		
14.	FILTER RING	LS	1		
				<i>Erosion Control Subtotal =</i>	
MISCELLANEOUS					
15.	CONCRETE RADIUS BLOCK	EA	2		
16.	18" RCP CLASS III	LF	155		
17.	36" RCP CLASS III	LF	12		
18.	36" CONCRETE HEADWALL	EA	1		
19.	CLEARING BRUSH	AC	0.2		
20.	DITCH GRADING	LS	1		
20.	STEEL BOLLARDS	EA	15		
21.	ADJUST CHAIN LINK GATE HEIGHT	LS	1		
22.	5'x5' TRAFFIC RATED LID W/ 18" x 24" TRAFFIC RATED GRATE	EA	1		
				<i>Miscellaneous Subtotal =</i>	
				TOTAL CONSTRUCTION =	

CITY OF GRIFFIN
DEPARTMENT OF CENTRAL SERVICES PAVING PROJECTS
SHOAL CREEK C&D LANDFILL AND TRANSFER STATION/RECYCLING CENTER
BID TABULATION

Item	Description	Unit	Quantity	Unit Price	Item Total
PROJECT C - SHOAL CREEK C&D LANDFILL ACCESS ROAD					
GENERAL					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING (LAYOUT) BY REGISTERED SURVEYOR	LS	1		
General Subtotal =					
PAVEMENT					
4.	ROAD IMPROVEMENT COMPLETE PER DETAIL	SY	4,000		
5.	15" RCP CLASS III	LF	60		
Pavement Subtotal =					
MISCELLANEOUS					
6.	SILT FENCE	LF	1,630		
7.	RIP RAP	TON	5		
Miscellaneous Subtotal =					
TOTAL CONSTRUCTION =					

PROJECT A - TRANSFER STATION/RECYCLING CENTER PAVING _____

PROJECT B - SHOAL CREEK C&D LANDFILL ENTRY DRIVE _____

PROJECT C - SHOAL CREEK C&D LANDFILL ACCESS ROAD _____

TOTAL CONSTRUCTION FOR PROJECT A, PROJECT B, AND PROJECT C _____