

BID SCHEDULE
Springview Lane Drainage Improvements

<u>Item Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Item Cost</u>
Mobilization	LS	1		
Const. Stakes Lines & Grades	EA	1		
Traffic Control	EA	1		
As-built Construction Plans	EA	1		
Clearing & Grubbing	AC	1.58		
Removal and Disposal of Exist JB and DI	EA	3		
Unclassified Excavation	CY	10582		
Muck Excavation	CY	390		
Maintenance Stone	TON	50		
15" Smooth Wall Pipe (HDPE)	LF	40		
18" RC Pipe	LF	20		
24" Smooth Wall Pipe (HDPE)	LF	20		
Drop Inlet (24"x36")	EA	1		
Catch Basin - Type 9 MH	EA	1		
Concrete Sidewalk (4" Uniform)	SY	6		
Permanent Cover	AC	1.58		
Straw or Hay Mulch with Tackifier	AC	1.58		
Fertilizer (Nitrogen)	LB	158		
Fertilizer (Phosphoric Acid)	LB	158		

Fertilizer (Potash)	LB	158		
Agricultural Granular Lime	LB	3160		
Tree Protection	EA	8		
Mowing	AC	1.58		
Silt Fence	LF	1160		
Replace/Repair Silt Fence	LF	116		
Removal of Silt Ret. By Silt Fence	LF	290		
Inlet Structure Filter - Type A	EA	1		
Stabilized Constr. Entrance	SY	1091		
Tideflex Series 35-1 Check valve or Equivalent	EA	2		
Eight Feet Tall Wooden Privacy Fence	LF	200		
Total				

200' Privacy Fence shall be eight feet tall. Fence shall be framed with 4"x4" treated posts eight feet apart on center. Posts may be set in concrete, but not required. Posts shall be a minimum of three feet below grade. Stringers made of treated 2x4 boards between posts and shall be a minimum of three stringers between each post equidistant apart. Fence shall use dogeared wooden pickets. Pickets shall be eight feet tall and nailed to stringers. The entire fence shall be treated with an opaque sealant to protect it from weathering.

Unclassified Excavation materials may be transported and dumped at the Town of Summerville Public Works Facility located at 1105 Yancey Street.