

April 25, 2022

ADDENDUM TO ADVERTISED CONTRACT

PROJECT NAME: CITY OF HOLLY SPRINGS HOLLY SPRINGS
PARKWAY WIDENING PROJECT PH II

PROJECT NUMBER: 2022-02

CITY: CITY OF HOLLY SPRINGS

AMENDMENT NUMBER: 2

LETTING DATE: APRIL 28, 2022

THE FOLLOWING CHANGES ARE HEREBY MADE TO THIS CONTRACT. THE BIDDER IS RESPONSIBLE FOR MAKING ANY NECESSARY CHANGES IN INK IN THE PROPOSAL. BIDDER SHALL ACKNOWLEDGE THIS AMENDMENT BY CHECKING THE APPROPRIATE SPACE ON THE AMENDMENT CERTIFICATION PAGE.

.....

QUESTIONS/CLARIFICATIONS

1. Is there a utility adjustment schedule for this project? **In the bid docs under the section of “GENERAL CONDITIONS” item number “I” lists anticipated Utility adjustment timeframes from the 3 main utility companies. These were from discussions from each of the listed utilities.**
2. Dwelling at Culvert are we to remove? **At this time, the City is planning to remove this dwelling on Parcel 18 outside of the roadway contract.**
3. No Rip Rap or Fabric in redirected creek or culvert ends? **Not at this time, waiting for final confirmation from USACOE and EPD**
4. Temporary Asphalt Tapers at 137+50 to 140+00 are they to be removed? **Yes, however this maybe adjusted in the field if Phase III project follows PH II as planned.**
5. Can we abandon the existing storm drain to be removed with flowable fill? **Generally, the answer would be yes...however, there will be no additional pay item for flowable fill as the demo for pipe would be covered under Grading Complete item.**
6. On the detail on sheet 05-002 for the “City of Holly Springs Stamped Brick Paver Sidewalk”, it mentions that the bricks are to be “English Edge Cut, Pinehall color (Typ). Is this the stamp pattern or are brick pavers required? **The current project will be a stamped brick pattern with that color. The color should match as close as possible to the colors used on Phase I. No brick pavers will be used on this project.**