



Addendum No. Two

Date: August 2, 2022
Project: Putnam County Rec. Department- Splash Pad & Pavilion, SE No. 2021-159
Engineer: Simonton Engineering, LLC.
Greensboro & Hinesville, Georgia

The original plans, specifications, and bid documents are amended to include the following:

Plan Set:

Replace the original "Barrier Netting Note" on sheet C2.0 with the following note:

Barrier Netting Note:

1. Barrier netting system to be 20' high system manufactured by "Beacon Built". System to include all mounting and hardware. Netting to be #24 twisted knotted nylon 1-3/4" square mesh netting (UV-Treated) or approved equal. Heavy duty schedule 40 Aluminum uprights to be used, along with hoisting block and halyards to raise and lower from the ground.

Proposal:

Replace the original bid item list with the enclosed revised Bid item Page P-2 & P-3.



-END-

Bid Items - Putnam County Recreation Dept. Splash Pad & Pavilion
for
Scott Haley
SE Project No. 2021-159

Item No.	Estimated Quantity	Units	Description	Unit Price	Total Price
1. GENERAL					
A.	1	LS	Demolition		\$
B.	1	LS	Clearing & Grubbing		\$
C.	1	LS	Grading		\$
D.	1	LS	Splash Pad Complete w/ Rubberized Coating		\$
E.	1	LS	Pavilion Complete		\$
F.	1	LS	Electrical		\$
G.	1	EA	Outdoor Shower/Drinking Fountain	\$	\$
H.	155	SY	9.5mm Asphalt Overlay	\$	\$
I.	160	SY	4" Concrete Sidewalk & Splash Pad	\$	\$
J.	265	LF	4' Metal Rail Fence	\$	\$
K.	113	LF	Concrete Seating Wall	\$	\$
GENERAL SUBTOTAL:					\$
2. SANITARY SEWER					
A.	1	EA	Doghouse Manhole	\$	\$
B.	730	LF	4" PVC Gravity Sewer Service	\$	\$
C.	840	CY	Rock Removal for Sewer Service	\$	\$
SANITARY SEWER SUBTOTAL:					\$
3. EROSION & SEDIMENT CONTROL					
A.	1,205	LF	Type "NS" Silt Fence (Non-Sensitive)	\$	\$
B.	3	EA	Composite Filter Sock Check Dam (18" Ø)		\$
C.	1	LS	Temporary Grassing		\$
D.	1	LS	Permanent Grassing		\$
EROSION & SEDIMENT CONTROL SUBTOTAL:					\$
4. WATER					
A.	1	EA	Connection to Ex. Water Main	\$	\$
B.	1,335	LF	4" PVC Water Service	\$	\$
C.	105	LF	2" PVC Water Service	\$	\$
WATER SUBTOTAL:					\$
5. MISCELLANEOUS					
A.	1	LS	Mobilization		\$
B.	1	LS	Splash Pad Warning Signage		\$
C.	1	EA	Emergency Hard-Lined Phone	\$	\$
MISCELLANEOUS SUBTOTAL:					\$
TOTAL:					\$

Bid Items - Putnam County Recreation Dept. Splash Pad & Pavilion
for
Scott Haley
SE Project No. 2021-159

Item No.	Estimated Quantity	Units	Description	Unit Price	Total Price
<u>ALTERNATE BID ITEMS #1</u>					
1	742	LF	2" PVC Force Main	\$ _____	\$ _____
2	1	EA	Air Release / Vacuum Valve	\$ _____	\$ _____
3	1	EA	Duplex Eone Grinder Pump	\$ _____	\$ _____
ALTERNATE BID ITEMS #1 SUBTOTAL:					\$ _____
<u>ALTERNATE SEWER ROUTE #2</u>					
1	1	EA	8"x6" Connection to Existing Sewer Main	\$ _____	\$ _____
2	275	LF	Trench Cut 6" PVC Sewer Service (0'-4')	\$ _____	\$ _____
3	75	LF	Trench Cut 6" PVC Sewer Service (4'-6')	\$ _____	\$ _____
4	605	LF	Trench Cut 6" PVC Sewer Service (6'-8')	\$ _____	\$ _____
5	20	LF	6" Sewer Service at Creek Crossing w/ Ductile Iron Pipe w/ Concrete Supports Both Sides	\$ _____	\$ _____
6	10	EA	Sewer Service Cleanout	\$ _____	\$ _____
7	230	CY	Rock Removal for Sewer Service	\$ _____	\$ _____
ALTERNATE SEWER ROUTE #2 SUBTOTAL:					\$ _____