



## ADDENDUM NO. 4

Issue Date: February 22, 2021

Project Name: Central WWTF RAS/WAS Pump & RDT Replacement

Bid Number: 2021022

Bid Opening Date: ~~February 18, 2021~~ **Updated February 25, 2021**

This addendum is being released to answer questions received. The information and documents contained in this addendum are hereby incorporated in the invitation to bid. **This addendum must be acknowledged where indicated on the bid form, or the bid will be declared non-responsive.**

### Questions

1. **Are the aluminum plate and flange with threaded connection shown in detail 2/M-06 existing?**  
No, they are not existing.

2. **There is a note on sheet M-01 that states that we may need to raise the elevation of the RAS pump header for pumps 4, 5, and 6. This work is also shown in detail 1/D-02. Please confirm that this applies to RAS pumps 1, 2, and 3 as well per general note 1 on sheet M-01.**

Pumps 4, 5, and 6 were added after pumps 1, 2 and 3. The alignment is slightly different. It is not expected that the header for pumps 1, 2 and 3 will need to be moved. It will be the contractor's responsibility to field verify.

3. **Drawing E02 (One-Lines) calls for a 3/4" conduit with 3-#6, 3-#12, and 1-#10 for each pump. This size conduit is too small for this amount of wire to be pulled.**

The existing conduit is at least 1 1/4" according to the as-builts, not the 3/4 inch as indicated in the plans. This is large enough to accommodate the proposed wires.