



Addendum No. 2

Date of Addendum Issuance: October 24, 2019

Project: Old Phoenix Road Auxiliary Lane Construction

Bid Item #: 19-42001-003

The following Schedule of Items, dated 10/24/2019, shall be utilized when submitting a bid on the referenced project:

(corrected 10/24/2019)

(BIDDERS MUST RETURN THIS FORM WITH BID RESPONSE)
BID SCHEDULE OF ITEMS – OLD PHOENIX ROAD AUXILIARY LANE CONSTRUCTION

PAY ITEM	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	TOTAL AMOUNT
150-1000	TRAFFIC CONTROL	LS	LS		
210-0100	GRADING COMPLETE	LS	LS		
163-0232	TEMPORARY GRASSING	AC	0.20		
163-0240	MULCH	TN	1.00		
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	10		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE - TYPE A	LF	200		
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	10		
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	400		
310-5060	GR AGGR BASE CRS, 6 IN, INCL MATL	SY	133		
310-5120	GR AGGR BASE CRS, 12 IN, INCL MATL	SY	506		
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	82		
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	41		
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	55		
413-0750	TACK COAT	GAL	98		
441-0018	DRIVEWAY CONCRETE, 8 IN TK	SY	35		
441-0754	CONC MEDIAN, 7 1/2 IN	SY	23		
441-4030	CONC VALLEY GUTER, 8 IN	SY	35		
441-6216	CONC CURB & GUTTER, 8" X 24", TYPE 2	LF	504		
446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	LF	345		
500-9999	CLASS B CONCRETE, PVMT WIDENING	CY	15		
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	8		
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	8		
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	8		
611-3000	RECONSTRUCT CATCH BASIN	EA	1		
611-3100	RECONSTRUCT JUNCTION BOX	EA	4		
611-8040	ADJUST DROP INLET TO GRADE	EA	1		

636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	13		
636-2070	GALV STEEL POSTS, TP 7	LF	25		
641-1200	GUARDRAIL, TYPE W	LF	96		
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	2		
641-5015A	GUARDRAIL TERMINAL, TP 12A, 31 IN, NON-FLARED, ENERGY-ABSORBING	EA	1		
647-2120	PULL BOX, PB-2	EA	1		
647-6300	LOOP DETECTOR, 6 FT X 40 FT, QUADRUPOLE	EA	2		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	3		
653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	385		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	15		
653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5IN, WHITE	GLF	80		
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	20		
668-1100	CATCH BASIN, GP 1	EA	1		
668-2100	DROP INLET, GP 1	EA	2		
700-6910	PERMANENT GRASSING	AC	0.20		
700-7000	AGRICULTURAL LIME	TN	1.00		
700-8000	FERTILIZER MIXED GRADE	TN	1.00		
700-8100	FERTILIZER NITROGEN CONTENT	LB	10		
700-9300	SOD	SY	500		
				TOTAL BID	\$

Print Total Bid Price: (print) _____

In compliance with the attached Specification, the undersigned offers and agrees that if this Bid is accepted, by the Putnam County Board of Commissioners within Ninety (90) days of the date of Bid opening, that he will furnish any or all of the Items upon which Prices are quoted, at the Price set opposite each Item, delivered to the designated point(s) within the time specified in the Bid Schedule.

COMPANY _____

ADDRESS _____

AUTHORIZED SIGNATURE _____

PRINT / TYPE NAME _____

TITLE _____