



**Beaufort County School District**

**Addendum 1**

Solicitation Number: 20-018  
Date Printed: November 11, 2019  
Date Issued: November 27, 2019  
Procurement Officer: Kaylee Yinger  
Phone: 843-322-2349

Email: [Kaylee.Yinger@beaufort.k12.sc.us](mailto:Kaylee.Yinger@beaufort.k12.sc.us)

**Invitation for Bid (IFB)**

DESCRIPTION: **Theatrical Stage Rigging Repairs**  
SUBMIT OFFER BY (Opening Date & Time): **December 2, 2019 2:00 PM**  
QUESTIONS MUST BE RECEIVED BY: **November 25, 2019**  
NUMBER OF COPIES TO BE SUBMITTED: Two (2) originals

**Offers must be submitted in a sealed package. Solicitation Number & Opening Date must appear on package exterior.**

SUBMIT YOUR SEALED OFFER TO EITHER OF THE FOLLOWING ADDRESSES:

MAILING ADDRESS:  
Beaufort County School District  
Procurement Office  
P.O. Drawer 309  
Beaufort, SC 29901-0309

PHYSICAL ADDRESS:  
Beaufort County School District  
Procurement Office  
2900 Mink Point Blvd  
Beaufort, SC 29902

**AWARDS & AMENDMENTS:**

Award will be posted at the Physical Address stated above on or after December 2, 2019. The award, this solicitation, and any amendments will be posted at the following web address: [www.beaufort.k12.sc.us](http://www.beaufort.k12.sc.us)

You must submit a signed copy of this form with Your Offer. By submitting a bid or proposal, You agree to be bound by the terms of the Solicitation. You agree to hold Your Offer open for a minimum of ninety (90) calendar days after the Opening Date.

NAME OF OFFEROR: \_\_\_\_\_ (Full legal name of business submitting the offer) ENTITY TYPE: \_\_\_\_\_

AUTHORIZED SIGNATURE (Person signing must be authorized to submit binding offer to enter contract on behalf of Offeror named above)

PRINTED NAME \_\_\_\_\_ TITLE \_\_\_\_\_

Instructions regarding Offeror's name: Any award issued will be issued to, and the contract will be formed with, the entity identified as the Offeror above. An offer may be submitted by only one legal entity. The entity named as the Offeror must be a single and distinct legal entity. Do not use the name of a branch office or a division of a larger entity if the branch or division is not a separate legal entity, i.e., a separate corporation, partnership, sole proprietorship, etc.

**PAGE TWO**  
**(Return Page Two with Your Offer)**

<b>HOME OFFICE ADDRESS</b> (Address for offeror's home office/ Principal place of business):     	<b>NOTICE ADDRESS</b> (Address to which all procurement and contract related notices should be sent):     
<b>PHONE NUMBER:</b>	
<b>EMAIL ADDRESS:</b>	

<b>PAYMENT ADDRESS</b> (Address to which payments will be sent):          <input type="checkbox"/> Payment Address Same as Home Office Address <input type="checkbox"/> Payment Address Same as Home Notice Address (check one only)	<b>ORDER ADDRESS</b> (Address to which all purchase orders will be sent):          <input type="checkbox"/> Payment Address Same as Home Office Address <input type="checkbox"/> Payment Address Same as Notice Address (check one only)
--	---

<b>ACKNOWLEDGEMENT OF AMENDMENTS:</b>	<u>Amendment Number</u>	<u>Amendment Issue Date</u>
Offerors acknowledges Receipt of amendments by Indicating amendment number and its date of issue		

<b>MINORITY PARTICIPATION-</b> Are you a Minority Business Enterprise: Yes <input type="checkbox"/> No <input type="checkbox"/> If yes, please include a copy of your certification.
---

## Questions and Answers:

### 3.1 SCOPE OF WORK / MINIMUM SPECIFICATIONS AND SERVICE REQUIREMENTS (to include but not limited to):

#### Beaufort High School Auditorium

a) Replace damaged loft block idlers – We did not see evidence of any broken idlers.

**Damage verified. Replace**

b) Install new safety bolts. - Factory does not require safety bolts, but trim chain should be 1/4" instead of existing 3/16" chain

**Install new**

c) Install cable thimbles in all head block cable tie-offs. - These need to be addressed

**On deficiency report**

d) Replace all dead hung support chains - These need to be addressed

**with proper size**

e) Replace fire curtain safety chains - These need to be addressed

f) Install idler rollers in fire curtain rigging system - We were unable to identify "idler rollers" on the fire curtain system.

**Confirmed in place and needing replacement**

g) Install mounting clips on fire curtain head block – Clips appear present on existing fire curtain head block.

**Replace clips with larger style having greater friction**

h) Replace all malleable cable clamps with forged clamps. - These need to be addressed

**On deficiency report**

i) Replace lift cable on line-set #6 - These need to be addressed

j) Replace electronic fire curtain release system These need to be addressed

#### Beaufort High School PAC

a) Replace fire curtain release system. – Existing Fire curtain release system just needs to be adjusted

**System has been professionally adjusted and will not maintain adjustment therefore replacement justified.**

b) Replace fire line roller brackets. – Unable to identify “fire line roller brackets” on existing system

**Replace existing brackets with heavier duty units and appropriate anchors**

c) Install cable thimbles in all head block cable tie-offs – No tie offs were identified on existing system

**On deficiency report**

d) Install mounting clips on fire curtain head block. – Clips appear present on existing fire curtain head block

**Replace clips with larger style having greater friction**

e) Replace all malleable cable clamps with forged clamps. – No Malleable clips were identified on current system

**On deficiency report**

f) Replace fire curtain head block and hydraulic damper. – We could identify no issues with current system but will replace if requested.

**See “a)” above**

g) Install cable management system for S/O cables. – Due to nature of existing SO cable layout, movable rigging is not suggested.

**On deficiency report and confirmed existing system not functioning as designed**

### **REVISED SCOPE**

#### **Hilton Head High School SCC**

**On 11/26/2019 the Director of Maintenance advised that Hilton Head Island High School SCC work had already been completed and there were currently no issues with items a-e. Due to the above delete all Hilton Head High SCC below objectives.**

a) Raise bottom arbor stop to correct tension block issues

b) 02. Re-crimp all copper swage fittings

c) 03. Correct locking collar issues

d) 04. Install anti-sag bars to correct cable management issues

e) 05. Realign head blocks and loft blocks

f) 06. Replace bent arbor