

Bid Form

The following Bid Form is presented to assist the Village in evaluating the Bid. This Bid Form reflects estimated quantities for the Total Bid as described above. After award, the Village reserves the right to modify estimated quantities subject to the unit price, and eliminate line items if necessary. Payment shall be made for the items listed on the Bid Form on the basis of the Work actually performed and completed. Bid prices stated in the proposal include all costs and expenses for labor, equipment, materials, contractor's overhead and profit.

ITEM	ITEM DESCRIPTION	UNITS	QTY	COST
101-1	MOBILIZATION/DEMOBILIZATION	LS	1	
102-1	MOT	LS	1	
102-10-A	OFF-DUTY LAW ENFORCEMENT OFFICER	LS	1	
110-1-1	CLEARING AND GRUBBING	LS	1	
160-4	TYPE "B" STABILIZATION (12" Thick) (Min. C.B.R. 30)	SY	18	
162-1-11	PREPARED SOIL LAYER 6"	SY	1,035	
285-709	OPTIONAL BASE, BASE GROUP 09	SY	18	
327-7-01	MILLING EXISTING PAVEMENT	SY	2801	
334-1-13	SP TRAFFIC C	TON	173	
520-1-10	TYPE F CURB AND GUTTER	LF	574	
520-2-2	TYPE B CURB AND GUTTER	LF	118	
520-2-4	TYPE D CURB AND GUTTER	LF	433	
522-1	4" CONCRETE SIDEWALK	SY	454	
522-2	6" CONCRETE SIDEWALK	SY	20	
526-1-2	CONCRETE PAVERS	SY	73	
527-2	DETECTABLE WARNINGS	SF	80	
570-1-2	SODDING (Pensacola Bahia or match existing) (includes watering)	SY	1,085	
630-2-11	CONDUIT, F & I, OPEN TRENCH (600' W + 100' E)	LF	700	
635-2-11	PULL & SPLICE BOX, F & I, 13" X 24" COVER SIZE (8 EA W. + 4 EA E.)	EA	12	
639-1-620	ELECTRICAL POWER SERVICE, REMOVE COMPLETE SERVICE	AS	1.00	
639-2-6	ELECTRICAL WIRE REMOVAL	LF	250	
649-36-300	MAST ARM, REMOVE SHALLOW FOUNDATION, BOLT ON ATTACHMENT	EA	4.00	
670-5-600	TRAFFIC CONROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.00	
700-1-11	SINGLE POST SIGN F&I, 12-20 SF	AS	32	
700-1-60	SINGLE POST SIGN, REMOVE	AS	4	
706-3	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	140	
710-90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1	
711-11-123	THERMOPLASTIC, STANDARD-WHITE SOLID 12"	LF	260	

BASE BID AMOUNT (IN WORDS) _____

Bidder:

By:

Title:
