

ADDENDUM SIX
WALNUT STEET PEDESTRIAN BRIDGE REPAIR AND CONSTRUCTION PHASE 1
CONTRACT NO. E-13-002-201
CITY OF CHATTANOOGA, TENNESSEE

The following amendments and clarifications will be made to the Contract Documents, Specifications, and Drawings:

I. Regarding Bid Date

Project will be rebid on June 7, 2016. Replace Request for Bidder Information page 00009-1R1 with the attached page 00009-1R2. Replace Contractor's Identification page 00201-1R1 with the attached page 00201-1R2.

II. Regarding Contractor Questions on Repointing of Stone Masonry Joints

- 1. The plans specify that repointing work may only be performed, when the ambient temperature is between 41 and 86 degrees F, and predicted to remain above 41 degrees, for several days. This job is also planned for winter months. If weather prevents masonry work from being completed, will the city add time to the job, or should the contractor add contingency money into the unit price, to account for the worst-case weather scenario? *In Addendum Three, the number of calendar days was increased to 180 days. The Contractor should plan the work such that the Project can be completed in this time.***
- 2. The specified quantity for Masonry repointing is 9000 LF, but the plans state that this number may be increased, at the Engineer's discretion. If this quantity is increased, will there be a change order, adding a commensurate amount of time, to complete the additional repairs? *No change order will be necessary. The Contractor will be paid based on the established unit price for any approved amount over the 9,000 LF stated in the bid documents.***
- 3. Is there to be a containment method used, to prevent mortar and other debris from entering the river, when deteriorated and loose mortar is removed? *It is up to the Contractor to provide an approved containment method.***
- 4. Is the number of loose stones, on the piers known? The procedure states that any loose stones encountered are to be removed and reset, and this cost is to be included in the repointing item. Does the City have an estimate of how many of these stones exist? *We do not believe there will be any loose stones to be removed and reset. This language was put in the plans on the outside chance that this could occur. During the inspection not every square foot of surface area on the piers were inspected, thus the need for this kind of language was justified. The vast majority of the work will be to remove loose rock material on the individual stones and repoint the mortar joints.***

III. Regarding Steel Pack Rust Repair Details

Remove Note No. 5 from Sheet 37 that deals with prohibiting pressure washing between steel plies.

IV. Regarding Contractor Questions

Deadline to receive additional Contractor Questions will be 4:30 pm EST on June 2, 2016.

June 1, 2016

/s/ Justin C. Holland, Administrator
City of Chattanooga