

**ADDENDUM NUMBER 3
BID NUMBER RFP 22-028**

Athletic Field Improvements – Sumner Academy

ISSUED: January 25, 2023

PURCHASING DEPARTMENT
UNIFIED SCHOOL DISTRICT 500
2010 N. 59th STREET, ROOM 370
KANSAS CITY, KANSAS 66104
(913) 551-3200

Note the following changes to the above-mentioned bid. This information is to be taken into consideration when responding to the original bid document.

1. Response to Bidder Questions:

1	What is the earliest start date and desired completion date?
KCKPS	Construction can begin upon receipt and approval of all required submittals, and any other required applications, submissions, etc. The District will work with the selected vendor to begin work as soon as possible to ensure completion by the start of school, mid-August, 2023
2	Could you please advise on how we need to bid the existing sanitary sewer that runs thru the middle of the field and out of the north side? Would you like to see an add price if we need to replace/fix the existing if a problem arises during construction. Based on the information we have that sanitary is over 100 yrs. old
KCKPS	The sewer lines are public utilities owned and maintained by BPU. The district has been in communication with BPU and anticipates BPU will complete any necessary work on their utilities. Although we believe at this time that their work will not impact that of the selected vendor, the vendor should be prepared to coordinate efforts with BPU if necessary.
3	For clarification on the lighting requirements, can you please clarify that lighting is not in the project? What is the expectation of scope of work to prepare for future lighting if lighting is not in the project?
KCKPS	An electrical engineer is currently developing plans for the installation of lights. As stated in the release the track/field coordinator should be prepared to coordinate with those efforts with the installation of conduits across the field. We anticipate 4 light poles, 2 on each side.
4	4.1.2 calls out removal of both sand pits and runways in south D-zone. Please confirm.
KCKPS	Confirmed. Please note section 4.1.7 & 4.1.8 on page 12
5	4.1.2 calls out removal of (2) concrete throwing pads in north D-zone. Please confirm.
KCKPS	Confirmed. These will not be replaced.
6	No call out for removal of 30'x70' asphalt high jump pad in north D-zone. Please confirm this is to remain.
KCKPS	We will issue an addendum to clarify removal of the high jump pad and replacement per section 4.1.9 page 12
7	4.1.7 calls out installation of (2) new long/triple jump pits with new concrete runway in south D-zone. Please confirm weather that implies one runway with a pit on either end or two new runways similar to existing set up.
KCKPS	Preferred would be one lane with pits at each end, but that will be determined by the submitted proposal of the selected vendor
8	4.1.8 calls out new pole vault runway, pad, and box in north D-zone. Please confirm location and length of this runway. Please clarify based on removal or remain of existing

	asphalt pad.
KCKPS	The pole vault runway should be sized per KSHSAA requirements.
9	4.1.9 calls out D-zone to be black synthetic track surface. Please confirm intended area/size/location. Will the entire D-zones north and south be converted to asphalt/track up to certain distance off goal posts?
KCKPS	It is intended for the entire D-zones to be converted to asphalt/track material, at a safe distance behind the goal posts. Please indicate suggested distance on the proposal.
10	4.1.13 calls out install of (2) new play clocks. Are there existing play clocks? Will new play clocks go in same location? Are we replacing foundations and posts as well or are those to remain? If remaining, what size are existing posts? Is there sufficient 120V power at these locations? If not, where will we be pulling power from?
KCKPS	There are not existing play clocks. These will be new and installed per suggested manufacturers recommendations. It is anticipated the power will pull from the adjacent field house.
11	4.1.14 calls out install of new scoreboard. Will new score board be in same location as existing? Are we replacing foundations and posts as well or are those to remain? If remaining, what size are existing posts? Is there sufficient 120V power at these locations? If not, where will we be pulling power from?
KCKPS	The scoreboard is intended to be in the same location, which has existing electrical supply. The District is dependent on the responding vendors to include any necessary revisions to install per manufacturers recommendations in their proposals.

2. No Other Changes: No other changes or modification are intended by this Addendum. All other terms and conditions of the solicitation remain in effect.

WE HEREBY ACKNOWLEDGE AND UNDERSTAND THE ABOVE NOTED CHANGES TO THE ORIGINAL BID DOCUMENT AND AGREE TO FURNISH THE ITEMS ON WHICH PRICES ARE QUOTED IN ACCORDANCE WITH ALL TERMS AND CONDITIONS PREVIOUSLY LISTED AND ANY ATTACHED SPECIFICATIONS AND AMENDMENTS.

BY: _____ DATE: _____
TITTLE: _____ PHONE: _____
FIRM _____