



THE CITY OF DAYTONA BEACH OFFICE OF THE PURCHASING AGENT

Post Office Box 2451
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080
Fax (386) 671-8085

ADDENDUM NO. 5

DATE: April 9, 2020
PROJECT: ITB 20391
FENCING INSTALLATION, REMOVAL, AND REPAIR
OPENING DATE: April 20, 2020

This addendum is hereby incorporated into the Bid Documents for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~striketrough~~.

1. Questions and Answers:

Q1: Which spec over rides which. Does the Bid Sheet override the Written Spec or Vice Versa? On bid sheets are we bidding the All, Usage or the HC in the Excel Forms?

A1: This is a line item bid. Contractor MUST bid on all items in order to be responsive. The Contractor will use the excel spreadsheet and enter the unit price. Extended price and totals will be calculated. The written spec should mirror the Bid Schedule. If discrepancies are found please submit question for clarification.

Q2: 2.2 G Removal of Materials only. No removal of Brush, stumps, trees. City clears right of way?

A2: The Contractor will remove any brush, stumps, or trees and drag them to the nearest right-of-way. City will clear the right-of-way.

Q3: H. If there is not a way to do the job without damage can we note it upfront? Is the City doing their own locate since 811 does not do Private Property?

A3: Contractor is responsible to communicate with the city any potential damages before work begins. City will locate their own utilities and underground improvements with adequate (72 hour) advanced notice of need by contractor. Per Section 2.2 B. - Location of all other utilities are the responsibility of the contractor.

Q4: Q. Do we include cost from fuel and employee time to pull permit?

A4: Contractor will include their requested cost for permitting with adequate details for City to audit and verify cost for permitting.

Q5: 2.3 F. 4. c. Chain Link specs for Field & Barb Wire Fence? Field & Barb Wire do not tie like Chain Link.

- A5: Edit 2.2 F. 4. C to: Contractor will conform to the technical specs for ~~chain-linked~~ Field and Barb Wire fencing. Wire will be wrapped and tied and at the following locations:
- Q6: 2.3 F 4 d. Vinyl Rail??? Under Field & Barb Wire Fence?
- A6: ~~Vinyl railing will be 1 1/2" x 5 1/2" x 16' and line post will be a minimum of six feet (6') six inches (6") in length.~~
- Q7: 2.3 F 4 e. Where are the specs & Exhibit III for Split Rail Fence at?
- A7: Contractor will conform to the technical specifications ~~listed on Exhibit III~~ for Split Rail Fencing.
- Q8: 2.3 F 5. 45 degree angle on top of Barb Wire Fence? This can be done on Chain Link Fence, but Barb Wire?? d. Barb Arms are made for Chain Link Post but not for Wood Post.
- A8: 2.3 F 5. a., b., and c. should be moved to 2.3 A. new item #9 under Chain Link Fence Requirements category.
- Q9: 2.3 K. 2. Contractor should not be responsible for bringing in fill to fill holes. There could be multiple holes 2 plus feet deep.
- A9: City will provide fill as needed.
- Q10: 2.3 E. Specify on Bid Sheet; 2 rail, 3 rail or 4 rail. Picture is of 3 rail with Finials.
- A10: Addendum to Bid Sheet will be for 3 rail as pictured in 2.3 E.
- Q11: 2.3 E 1. a. Need specs on wall thickness on Post, Pickets and Rails. So we are all quoting the same. Residential, Commercial & Industrial? Warranty will only be on Commercial or Industrial.
- A11: Commercial grade material is required so that the City will get the warranty. All material will be Commercial grade.
- Q12: 2.3 E 1. b. Specs on Powder Coating? Existing City sites have Pressed Spears. Finials cost much more and there are more than one style so it would need to be specified.
- A12: Type of pressed spears and finials will be specified on an as needed bases per project.
- Q13: 2.3 E 2. a. Contractor responsible for Final Grade before install? City should be responsible for this. Contractor should level around each post after setting.
- A13: Site GC or the City will perform final grading.
- Q14: 2.3 E 2. f. With Aluminum install you install panels as you are setting post so the post cannot set for 24 hours due to this.
- A14: Per 2.2 J. - All materials and installation requirements will meet Florida Chapter International Fence Industry Association's Florida Fencing standards.
- Q15: 2.3 E 2. j. Hot dipped galvanized gate hardware on Aluminum? Not aluminum?
- A15: ~~j. All gate hardware will be hot dipped galvanized.~~
- Q16: 2.3 A. 1. Written specs has Black Vinyl and Bid sheet had Black or Green?
- A16: Color will be specified per project.
- Q17: 4/7. On a sharp radius can SS20 be used instead of Sch 40 due to bending purposes?
- A17: Yes

- Q18: 2.3 A 8. d. Steel on beachside, not aluminum due to rust issues?
- A18: Wire ties for attaching fabric to tension wire will be twelve (9) gauge annealed galvanized steel wire at twenty-four (24") inches O.C.
- Q19: 2.3 C. 3. a. Can Bull Dog Hinges be used instead of 180 degree Hinges?
- A19: Yes
- Q20: 2.3 C. f. This is for Roll Gates not Swing Gates.
- A20: Strike section 2.3 C. c. through f.
- Q21: 2.4 Reads Semi-annual & annual on spec sheet, but Semi-annual on bid sheet?
- A21: All motorized gate motor preventative maintenance will be performed semi-annually (every 6 months) based on list provided by Project Manager.
- Q22: 2.4 C. Change batteries on emergency vehicle operator. Can you be more specific?
- A22: Battery replacement is for any battery operated device connected to the motorized gate motor (battery back-up, safety edge, photo-cell safety, Fire Dept. Knox box device, etc.)
- Q23: 2.5 A-B Specs read Black Vinyl. Bid sheet reads Black or Green Vinyl? Also Top Rail is not stated on the Bid Sheet or in this area on the spec sheet.
- A23: Color will be specified per project. Top Rail is listed on line item #7 of Bid Schedule.
- Q24: 2.5 H. PVC fence does not have Tension Wire. I. Timber does not use Tension Wires or Fittings. Specs on Trex Fence?
- A24: 2.5 H. PVC fencing includes PVC, line posts, post caps, concrete footings, ~~tension wires, and fittings. Terminal post, stretcher bar, top rail, and hardware not included.~~
- 2.5 I. Timber & Trex includes fabric, line posts, concrete footings, ~~tension wires, and fittings. Terminal post, stretcher bar, top rail, and hardware not included.~~
- Q25: 2.5 M. Level existing grade. Does not require additional fill?
- A25: City will provide fill as needed.
- Q26: 2.5 O. 1. Can you be more specific on Frame work, Post, Top Rail, Middle Rail, Bottom Rail, Braces?
- A26: Pricing for this spec item will follow Bid Schedule line items # 111, 112 and 113.
- Q27: 2.5 P. 2. Service Call is only after hours, weekends and holidays? It takes a lot of time to go to the site, measure the jobs and put the quote together. Service call should be included in all approved jobs.
- A27: Pricing for this spec item will follow Bid Schedule line items # 121.

2. All other terms and conditions remain the same.

The Bidder shall acknowledge receipt of this addendum on the Bid Proposal Form.

The City of Daytona Beach
Kirk Zimmerman, CPPB
Buyer

Posted online at <https://www.codb/841.us>