



Terry McKee, IT & Procurement Director

901 N. Broadway • Knoxville, TN 37917-6699

865.403.1133 • Fax 865.594.8858

purchasinginfo@kcdc.org

www.kcdc.org

Addendum

Solicitation Name	Demolition Services at Taylor Homes C19003	Addendum Number	2	Date	09-14-18
-------------------	--	-----------------	---	------	----------

This addendum answers questions raised about this solicitation. To aid in readability, the questions are in black, the answers are in **bolded blue** and the answers follow immediately below.

Q1	Can site be left rough graded with no standing water?
	That is the general intent. Please refer to specification section 02 22 10 Part 3.3 for additional information.
Q2	Will catch basin and storm sewer lines (if damaged) be repaired by contractor at his expense?
	Please refer to the plans and specifications regarding protection of existing utilities and construction to remain. If the contractor damages existing storm sewer that is intended to be used in the future, contractor would be responsible for the damage.
Q3	Will chain link fence be required around entire site? And if so, will contractor remove fence when job is completed?
	Yes, chain link fence will be required around the entire perimeter of the site. The contractor will leave the fence in place at the completion of the demolition project and coordinate with the Owner to transfer responsibility of the fence to others.
Q4	Will soil erosion person have to be on site that has completed sediment control class?
	Yes
Q5	Can grading of site be completed using on site dirt?
	Yes
Q6	Will owner cover cost of water for dust control?
	Yes
Q7	On drawing C903, will the two types of storm drain inlet detailed be required on each storm drain (roadway storm inlet and internal site silt fence drop inlet)?
	No, only one type of inlet protection will be used at each storm inlet depending on the inlet location (roadway or internal site).
Q8	Do all footings and foundations have to be removed?
	Yes.

