

**ADDENDUM NO. 1 TO CONTRACT DOCUMENTS**

Project: Highway 70 Sewer Replacement H&S Project No. 30906-302  
Owner: City of Havelock Date: February 22, 2023

To All Bidders:

Contractors submitting proposals for the above-named project shall take note of the following changes, additions, deletions, clarifications, etc., in the Contract Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Contract Documents, and all such shall be taken into consideration and be included in the Contractor's Bid Proposal.

Refer to attached sheet(s)

**The return receipt requested with the communication will be deemed evidence the bidder has received this Addendum and has followed the instructions outlined herein. Please sign, date, clearly print company name, and email this sheet back to [Hwy70SewerBid@hazenandsawyer.com](mailto:Hwy70SewerBid@hazenandsawyer.com) and [Bids@havelocknc.us](mailto:Bids@havelocknc.us).**

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Acknowledgment of Receipt

\_\_\_\_\_  
Date

**CITY OF HAVELOCK**  
**HAVELOCK, NORTH CAROLINA**  
**HIGHWAY 70 SEWER REPLACEMENT**

**Addendum No. 1**

**General:**

- Minutes from the pre-bid meeting are provided in **Attachment 1**.

**Contract Documents:**

**CONTRACT SPECIFICATION 31 74 22**

- Replace Section 2.02-C-1 in its entirety with the following: “Wet Density: Wet density (unit weight) of the LDCC shall be not less than 40 pcf, plus or minus 5 pcf, at the point of placement, unless a higher density is required to achieve strength requirements.”

**CONTRACT DRAWING C-00 – CONSTRUCTION SEQUENCE**

- Note 7 – In the first sentence, replace “Area 2” with “Area 4”.

**CONTRACT DRAWING C-01 – STA 0+00 to 8+00**

- Note 5 – Add the language shown in bold to the second sentence: “In paved areas or within 5 feet of a roadway, sewer to be filled with cement grout with a minimum compressive strength of 500 psi **or filled with low-density cellular concrete to meet Specification 31 74 22** and shall have a consistency to flow and be vibrated in order for the mixture to flow uniformly into the pipe to be filled.

**CONTRACT DRAWING C-02 – STA 8+00 TO 16+00**

- Note 6 – Replace Note 6 in its entirety with the following: “Existing sanitary sewer to be filled with flowable fill, cement grout, or low-density cellular concrete.”
- Add the following note:
  - “18. The guardrail on both sides of Woodhaven Drive where construction entrances are shown was installed after the project survey and is not shown on the Drawings. Contractor to temporarily remove and replace to City of Havelock roadway standards and requirements. Contractor to coordinate with the City of Havelock Public Utilities and Public Works Departments. Payment for this work is incidental to sewer installation.”

### CONTRACT DRAWING C-03 – STA 16+00 TO 24+00

- Add the following note:
  - “8. Contractor to remove fence and gate from within the LOD from approximate STA 21+00 to 24+00 and reinstall after construction. Payment for this work is incidental to sewer installation.”

### CONTRACT DRAWING C-04 – STA 24+00 TO 30+81

- Add the following notes:
  - “8. At time of bidding, there were religious statues within the LOD. These statues are to be removed by the property owner prior to construction.”
  - “9. Existing temporary emergency sanitary sewer bypass between Manhole G111 and MH G100 shall remain in place and shall be operated by the City of Havelock as an emergency bypass only and is not to be used for construction. Contractor to coordinate with the City of Havelock so the emergency bypass piping is not in conflict with project construction. Any temporary interruption of this bypass line must be reinstated at the end of each workday. Payment for this work is incidental to sewer installation.”

### CONTRACT DRAWING D-02 – DETAILS

- Add the following Note 3 to the notes for Detail 5 and Detail 6:
  - “3. Provide manhole vents where shown on Drawings. Vents shall be 4” factory welded and fabricated “hot-dipped” galvanized pipe. Vent pipe to be factory cast in place in manhole top. Vent opening to be screened.”

## **Addendum No. 1, Attachment 1**



**HAVELOCK**  
NORTH CAROLINA

**CITY OF HAVELOCK HWY 70 SEWER REPLACEMENT  
PRE-BID MEETING  
FEBRUARY 14, 2023 @ 1:00 PM**

**1. Introductions**

- City of Havelock – Owner
- Hazen and Sawyer – Design Engineer

**2. Project Description (Not all inclusive)**

- Installation of approximately 3,080 LF 18-inch PVC
- Three Jack and Bore Trenchless Crossings
- Removal of ~1880 LF and abandonment of ~1200 LF of existing sewer
- Installation of 24 new manholes
- Removal of 13 manholes and abandonment of 5 manholes on existing sewer

**3. Bid Opening**

- Tuesday, February 28<sup>th</sup>, 2023, at 2:00 p.m. EST  
Havelock City Hall  
1 Governmental Ave., Room 134  
Havelock, NC 28532
- No bids accepted by City of Havelock in any other location.

**4. Interpretation of Contract Documents**

- All questions to Hazen and Sawyer attention, [Hwy70SewerBid@hazenandsawyer.com](mailto:Hwy70SewerBid@hazenandsawyer.com) with copy to [bids@havelocknc.us](mailto:bids@havelocknc.us). All questions must be emailed.
- Questions should reference the Drawing or Specification page to help expedite the response.
- Last day for questions: seven (7) days prior to bid opening.
- Only questions answered by formal written addenda will be binding.
- Must submit emailed or mailed acknowledgement of all addenda.

**5. Bid Security**

- Certified Check, Bank Money Order, or Bond in an amount equal to not less than five percent (5%) of the Bid.
- Section 00 20 00 – Instruction to Bidders (Article 10)

**6. Contract Time**

- Substantial Completion – 210 days
- Final Completion – 240 days
- Reference Section 00 52 00 – Agreement, for Liquidated Damage information

**Hazen**

## **7. Bid Form**

- Submit Section 00 40 00 – Bid Form and all other required documents per Article 9. Do not strike through any wording of the form. Do not remove any pages from the bound documents.
- Total Single Prime Base Bid Price (Unit Price Basis)

## **8. Bids to Remain Open**

- 60 days per Section 00 40 00 – Bid Form

## **9. Award of the Contract**

- Refer to Section 00 20 00 – Instruction to Bidders.
- Anticipate NTP approximately April 2023.

## **10. Project Funding**

- The City of Havelock will fund this project through American Rescue Plan Act (ARPA).
- Bidder shall meet requirements of Section 00 53 00

## **11. Sales Tax**

- See Section 00 20 00 – Instructions to Bidders.
- The Bidder shall include North Carolina Sales and Use Tax in the Bid. See Section 00 73 00 – Supplementary Conditions, for more details.

## **12. Construction Sequencing at Ford Dealership**

- Reference Drawing C-00 for specific project constraints and temporary bypassing.

## **13. Examination of Site**

- May inspect the site today
- Additional site visits can be made by contacting [bids@havelocknc.us](mailto:bids@havelocknc.us) and [Hwy70SewerBid@hazenandsawyer.com](mailto:Hwy70SewerBid@hazenandsawyer.com).
  - Requests shall be made at least 72-hours in advance of proposed Site visit and at least five (5) days prior to opening of Bids.

