



ADDENDUM #1
COUNTY ROAD 12 WIDENING
Requisition No. ENGR-030122

FEBRUARY 24, 2022

Addendum #1 is being issued in regards to this project to reflect the following changes in the scope of work.

1. Addition of water valves and a fire hydrant. Riviera Utilities will provide the materials and the contractor will be responsible for the installation.
2. Addendum 1 Plan Sheets titled Existing Condition & Demo Plan, Sheet No. C4 and C5 are provided.
3. Revised Price Sheet reflecting additional work noted in line item 30. This price sheet should be utilized when bidding.

Please include this Addendum with your bid and acknowledge receipt of Addendum #1 on page 3 of the original bid packet.

Rachel Keith
Project Manger
City of Foley



Summary of Quantities and Unit items

The following unit prices shall include all charges of labor, materials, equipment, supervision, general expenses, taxes, insurances, overhead and profit, but not limited to, for accomplishment of the unit price items in place. The Bidder understands that the Owner reserves the right to reject any and all bids or adjust the quantities as required. The Bidder understands that he must submit this document complete with the bid. If an error is found in the estimated cost, the unit cost will prevail.

ITEM	DESCRIPTION	ESTIMATED QUANTITIES	UNITS	UNIT COST	TOTAL COST
1	Mobilize/De-mobilize including clean up and debris removal and Traffic Control	1	LS		
2	Strip Topsoil	140	CY		
3	Removal of Existing Curb	168	LF		
4	Excess Topsoil Haul off	70	CY		
5	Removal of Existing Pavement	2329	SF		
6	Sodding (Bermuda)	600	SY		
7	Inlet Protection	4	EA		
8	Straw Wattles (12")	10	EA		
9	Temporary Grassing	0.33	ACRE		
10	Mulching	0.33	ACRE		
11	Unclassified Excavation & Haul off Excess	655	CY		
12	Borrow Select Fill	540	CY		
13	Modify Subgrade	1090	SY		
14	Fine Grade/Compaction	1090	SY		
15	Crushed Aggregate Base Course, 6" thickness	1245	SY		
16	Tack Coat	5755	SY		
17	Asphalt, Wearing Surface Layer (165lbs/sy)	87	TON		



18	Asphalt, Binder Layer (220lbs/sy)	116	TON		
19	Asphalt, Mill and Overlay (1.5")	2990	SY		
20	Concrete Curb, Valley Gutter	62	LF		
21	Concrete Curb, Type-N	62	LF		
22	Temporary Striping	1	LS		
23	Solid White, Class 2, Type A Traffic Stripe (5" wide)	2000	LF		
24	Solid Yellow, Class 2, Type A Traffic Stripe (5" wide)	2050	LF		
25	Dotted, Class 2, Type A Traffic Stripe (5" wide)	100	LF		
26	Traffic Control Markings and Legends	1	LS		
27	Stop Sign	1	EA		
28	Removal of Existing PVC Water Main	1125	LF		
29	10" Water Main (Ductile Iron CL-350)	1125	LF		
30	Installation of Riviera supplied Water valves, Fire Hydrant and fittings	1	LS		
BID TOTAL					

Company: _____

Submitted By: _____

State of Alabama Contractor's License Number: _____

Address: _____

Phone: _____