

**ADDENDUM #4**

**TO**

**SPECIFICATION AND CONTRACT DOCUMENTS**

**February 5, 2019**

TO: ALL PLAN HOLDERS

FOR: ITB-003-2019  
JET-A 15,000 GALLON FUEL TANK AND SKID SYSTEM

The purpose of addendum #4 is to change item listed on Page 3 and 4 and to answer additional questions received.

**Contractor must acknowledge receipt of all addenda with proposal on the form provided herein.**

1. Would the Saddles welded to the tank be considered the steel foundation?

**Answer: Yes**

2. Do you want the skid pack with all of the equipment mounted on a deck and installed in front of the tank and piped to the appropriate inlets and outlets? If yes, do you want a rain shelter added to the tank to shield the skid pack from the environment?

**Answer: Yes. We want the skid pack system and all equipment mounted in a weatherproof cabinet with a roll-up style door located in front of the tank but separate from the tank.**

3. Or should the tank be equipped with a cabinet as in the picture in addendum 3 and all of the equipment mounted in the cabinet of the tank that is built into the tank?

**Answer: No.**

**CHANGES:**

**Change item h. on Page 3 to: h. Clock tank gauge**

**Change item Z. on Page 4 to: z. The tank must be mounted on a saddle system. It also must fit on a 15 foot by 45 foot concrete pad.**

No. 1 Dated \_\_\_\_\_

Signature: \_\_\_\_\_

No. 2 Dated \_\_\_\_\_

Signature: \_\_\_\_\_

No. 3 Dated \_\_\_\_\_

Signature: \_\_\_\_\_

No. 4 Dated \_\_\_\_\_

Signature: \_\_\_\_\_

**THIS FORM MUST BE INCLUDED WITH PROPOSAL**