

SCHEDULE OF BID ITEMS - ADDENDUM 1

May River Streetscape - Phase II

Bluffton, SC

August 2, 2017

201613-02



DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
A. Site Preparation and Earth Work				
1. Fine Grading/ Plant Bed Preparation	97,500	SF	_____	_____
2. Soil Amendments	97,500	SF	_____	_____
3. Herbicide	97,500	SF	_____	_____
Site Preparation and Earth Work Subtotal				_____
B. Landscaping				
Trees				
1. CECA Cercis canadensis/ Red Bud/ 2" CAL / 8'-10'. H/ #45	2	EA	_____	_____
2. CHVI Chionanthus virginicus/ White Fringetree/ 1.5"-2" CAL/ 6'-8'H/ #30/ Single Trunk	24	EA	_____	_____
3. COFL Cornus florida/ Eastern Dogwood/ 1.5"-1.75" CAL/6'-8'H min./ #30	5	EA	_____	_____
4. GIBI Gingko biloba 'Autumn Gold'/ Maidenhair Tree/ 2.5"-3" CAL/ 12'-14'H/ Cont.	2	EA	_____	_____
5. LAIT Lagerstroemia indica 'Tuscarora'/ Crape Myrtle/ 1.75"-2" CAL/ 10'-12'H/ #30/ Multi-Trunk	9	EA	_____	_____
6. QUVI Quercus virginiana/ Southern Live Oak/ 2.5" CAL / 12'-14' H/ #65	37	EA	_____	_____
7. SAPA Sabal palmetto/ Cabbage Palm/ 15'-16'H/ Hurricane Cut	7	EA	_____	_____
Shrubs				
1. AZEN Azalea Encore TM/ Encore Azalea/ 3 GAL / 15"- 18" H min./ Full and single variety	237	EA	_____	_____
2. AZIF Azalea indica 'Formosa'/ Formosa Azalea/ 7 GAL / 28" H min./ Full	345	EA	_____	_____
3. ILGL Ilex glabra/ Inkberry Holly/ 7 GAL/ 28" min./ Full	132	EA	_____	_____
4. SERE	369	EA	_____	_____

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
Serenoa repens/ Saw Palmetto/ 7 GAL/ 18"-24"				
5. VITA	12	EA		
Vitex agnus-castus/ Chaste Tree/ 15 GAL/ 4'-6'				
Ground Covers + Vines				
1. GELS	94	EA		
Gelsemium sempervirens 'Carolina'/ Yellow Jessamine/ 3 GAL/ 2'-2.5' Staked				
2. DIIR	50	EA		
Diets iridioides/ Fortnight Lily/ 3 GAL/ 24" H/ Full				
3. MUCW	121	EA		
Muhlenbergia capillaris 'White Cloud'/ White Muhly Grass/ 3 GAL/ 15"-18"/ Full				
4. TRAS	2,848	EA		
Trachelospermum asiaticum 'Asiatic'/ Asiatic Jasmine/ 1 GAL/ 6"-12" Spread				
Other				
1. SOD	40,342	SF		
Cynodon dactylon 'Celebration'/ Celebration Bermuda Grass				
2. MULCH	50,500	SF		
Longleaf Pine Straw - 3" deep				
3. IRRIGATION (N.I.B)				
Landscaping Subtotal				
C. Fence				
1. Living Fence	564	LF		
2. Black Vinyl Coated Chain Link Rolling Gate (length varies)	4	EA		
Fence				
D. Irrigation				
1. Irrigation System (excluding sleeving & boring)	1	LS		
Irrigation				
E. Maintenance				
1 Year Maintenance (Landscape & Irrigation)	1	YR		
Maintenance				
TOTAL				

F. Alternate - Landscape

Trees

1. **CECA**

2 EA

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
Cercis canadensis/ Red Bud/ 1.75" CAL / 8' H/#30				
2. CHVI	24	EA		
Chionanthus virginicus/ White Fringetree/ 1.5"-1.75" CAL/ 4'-6' H/ Single Trunk/ #30				
3. COFL	5	EA		
Cornus florida/ Eastern Dogwood/ 1"-1.5" CAL/ 4'-6' H/ #15				
4. GIBI	2	EA		
Gingko biloba 'Autumn Gold'/ Maidenhair Tree/ 2"-2.5" CAL/ 8' H min.				
5. LAIT	24	EA		
Lagerstroemia indica 'Tuscarora'/ Crape Myrtle/ 1.5" CAL/ 6' H/ #15/ Multi-Trunk				
6. QUVI	37	EA		
Quercus virginiana/ Southern Live Oak/ 2" CAL / 10'-12' H/ #45				
Shrubs				
1. AZIF	345	EA		
Azalea indica 'Formosa'/ Formosa Azalea/ 3 GAL / 18"-24" H min./ Full				
2. ILGL	132	EA		
Ilex glabra/ Inkberry Holly/ 3 GAL/ 18"-24" min./ Full				
3. SERE	369	EA		
Serenoa repens/ Saw Palmetto/ 3 GAL/ 15"				
4. VITA	12	EA		
Vitex agnus-castus/ Chaste Tree/ 7 GAL/ 3' H.				
Ground Covers + Vines				
1. GELS	121	EA		
Gelsemium sempervirens 'Carolina'/ Yellow Jessamine/ 1 GAL/ 318"-24"Staked				
2. DIIR	50	EA		
Dietes iridioides/ Fortnight Lily/ 1 GAL/ 12"-18"/ Full				
3. MUCW	121	EA		
Muhlenbergia capillaris 'White Cloud'/ White Muhly Grass/ 1 GAL/ 10"-12"/ Full				
4. TRAS	2,848	EA		
Trachelospermum asiaticum 'Asiatic'/ Asiatic Jasmine/ 4" CONT./ 4"-6" Spread				
Alternate - Landscaping Subtotal				

G. Alternate - Site Furnishings

1. Gisco Tabby Flower Pot (Buff Tabby)	51	EA		
2. 6' DuMor 3 Arm Bench 165 (Recycled Plastic)	20	EA		
3. 6' DuMor Backless Bench 166 (Recycled Plastic)	4	EA		

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
4. DuMor Trash Receptacle 70-22 (Recycled Plastic)	12	EA		
Alternate - Site Furnishings				

H. Alternate - Irrigation Sleeving

1. Irrigation Sleeving & Boring Driveways & Streets	1	LS		
---	---	----	--	--

Alternate - Irrigation Sleeving

Note: Quantities estimated above are to be used as an aid for clarification of units and a checklist for the contractor to compare with their own estimates