



PURCHASING AND
MATERIALS MANAGEMENT

City of Myrtle Beach
S O U T H C A R O L I N A
ADDENDUM 002

(843) 918-2170
FAX: (843) 918-2182

Grand Linear Park Trail

20-B0043

July 21, 2020

The following questions have been asked and answered:

1. Section 0300 on the Bid Proposal states that this will be a Lump Sum Contract, when asked at the Pre-Bid we were informed that this was a Unit Price Contract. Please Advise. **Unit Price Contract, Please include a total cost of the project at the bottom of the bid tab.**
2. Plan details do not show metal backing on silt fence, during Pre-Bid we were told to use metal backing. Please Advise. **Yes metal backing required**
3. Please confirm that inspection will not be the responsibility of the contractor. **City has hired a third party inspector.**
4. Please confirm that surveying is not the responsibility of the contractor. **Surveying is the responsibility of the contractor. The City will provide a beach mark.**
5. Plan details show underdrain at retaining wall if required. Will underdrain be required? **Yes underdrains are required**
6. What type of PVC will be required for the 8" Cross Drain sections and will Geogrid be required along these areas as well? **PVC is Schedule 40 / Geogrid is required**
7. Will there be any tree removal or just limb trimming for the trail placement? **See line item in bid tab for Clearing & Grubbing**
8. The plan details show two different signage details. One is 2lb U-Channel and the other is 4lb U-Channel. Please advise. **4lb U-Channel is preferred**
9. What type of RCP will be required, (Class and Gasket connection)? **Class 3 non gasket. Each joint will have mastic and fabric over the joint.**
10. What is the normal pond elevation? **install the trail in the location and elevation shown on the profile in the plan set**
11. The existing retaining wall at approximately STA 18+50, will this stay in place or need to be removed? **Stays in place**
12. Please elaborate on the two Allowances. (1. Remove and dispose offsite, 2. Unclassified remove and dispose offsite.) **These items were included if needed**
13. Will turbidity curtain be required at pipe ends? **No**
14. Do pipe ends need to be beveled.? **Yes**
15. Will prime coat be required on the 8" GABC? **No**

Thank you,

Ruth Burleson Garigen/Buyer

MAILING ADDRESS: CITY OF MYRTLE BEACH • P.O. BOX 2468 • MYRTLE BEACH, SOUTH CAROLINA 29578-2468
OFFICE ADDRESS: CITY OF MYRTLE BEACH • 3231 -10th AVENUE NORTH EXT. • MYRTLE BEACH, SOUTH CAROLINA 29577