


**ADDENDUM NO. 1  
INVITATION FOR BID  
HOSPITAL DRIVE LIFT STATION PROJECT – PHASE 2**

**Date:** September 23, 2020

**Contracting Agency:** Raton Water Works  
224 Savage Avenue  
Raton, New Mexico 87740  
(575) 445-3861

**Issued By:** Karen Stearns, P.E. 

**Attachments:** N/A

Solicitors are instructed to incorporate the following information into their bid for the above-referenced Invitation for Bid. Questions from potential bidders and Engineer answers are denoted with “Q” and “A,” respectively.

<b>Bid Document</b>	<b>Page</b>	<b>Section</b>	<b>Revision</b>
Technical Specifications	TS-7, TS-8	HDPE Sanitary Pipeline Requirements	<b>Q:</b> Will the required HDPE Pipe need to have any special markings such as a green strip on the side to mark it as Force main? <b>A:</b> Yes, HDPE pipe shall have a green stripe on the side.
Technical Specifications	TS-7, TS-8	HDPE Sanitary Pipeline Requirements	<b>Q:</b> Will the required HDPE PIPE need to have a white/grey interior for camera inspection purposes? <b>A:</b> No.
Technical Specifications; Drawings	TS-2, TS-4; C-2.2	Item 4 and General; Plan and Profile	<b>Q:</b> Bid sched indicates 2 EA manholes while plans show 1 EA please clarify. <b>A:</b> The bid schedule is correct – the scope includes two (2) manholes on the 8” line, per the specifications.
Technical Specifications; Drawings	TS-1, TS-2, TS-4; C-2.0, C-2.2	Item 2, Item 3, and General; Plan and Profiles	<b>Q:</b> Bid sched quantities for pipe exceed the quantities on the plans, please clarify. <b>A:</b> The bid schedule is correct – the bid schedule lists the correct quantities as described in the technical specifications.
Technical Specifications; Drawings	TS-1, TS-2; C-2.1	Item 2 and Item 3; Plan View	<b>Q:</b> Please provide a detail for the cleanouts at ST 9+78. <b>A:</b> Cleanouts are deleted from the scope of work.

<b>Bid Document</b>	<b>Page</b>	<b>Section</b>	<b>Revision</b>
Technical Specifications	TS-2, TS-8	Item 3 and PVC Sanitary Pipeline	<p><b>Q:</b> Is 8" SDR35 PVC acceptable for the 8" gravity sewer run from ST 19+93 to ST23+71?</p> <p><b>A:</b> 8" SDR35 PVC is only allowed for trench installation in unpaved areas that are outside of NMDOT right-of-way.</p>
Technical Specifications	TS-7, TS-8	HDPE Sanitary Pipeline Requirements	<p><b>Q:</b> Can DR21 fusible PVC be used in lieu of HDPE for horizontal directional drilling?</p> <p><b>A:</b> Yes. Thermally butt-fused DR21 FPVC is acceptable for HDD installation.</p>
Technical Specifications	TS-4	General	<p><b>Q:</b> Is the lift station (pump, control panel, generator, wet well, valve vault) included in the scope of work?</p> <p><b>A:</b> No. This project is for construction of Phase 2, which is for the gravity and force mains downstream from the recently built lift station.</p>