



SANTA ROSA COUNTY PROCUREMENT DEPARTMENT

6495 Caroline Street, Suite L | Milton, Florida 32570 850-983-1870 procurement@santarosa.fl.gov

ADDENDUM FORM

SRC Procurement Form ADM_029_00_082819

TO: PLANHOLDERS
FROM: PROCUREMENT OFFICE
DATE: 01/24/2020
REF: ADDENDUM # 1, FOR SOLICITATION # 20-008, TIBET DRIVE DRAINAGE IMPROVEMENTS

The following clarifications, amendments, additions, deletions, revisions and modifications form a part of the contract documents and change the original documents in the manner and to the extent stated.

I. SPECIFIC QUESTIONS AND ANSWERS

1. Question – On page 3 of 8, note 4, it says we can not occupy the right of way or street with equipment. Per the scope of work, we will have no choice but to occupy the street with equipment, and without a doubt will have to close it down. Does this note actually apply?

Answer – The note has been revised to clarify that materials shall not be stored on streets, driveways or public walkways unless specifically noted in these plans.

2. Question – On page 3 of 8, note 14, it states that all trenches must be closed at the end of the day. It will not be feasible for this projects time frame to backfill the entire trench each day.

Answer – The note has been revised to “all trenches must be secured at the end of the day.”

3. Question – Page 4 of 8 has a note saying the contractor is responsible for adjusting the location of existing utilities, transformers, and cable boxes that will be in conflict. There will for sure be transformers, existing utilities, and cable boxes in conflict. We will not be able to accurately estimate a cost for these items. Can a bid item be made that will have an allowance for this portion of work? Historically, we have never been able to get an estimate on moving such items

Answer – The note has been revised to” The contractor shall coordinate utility adjustments with the utility companies” and a line item has been added to the Bid Tab

4. Question – Page 5 of 8 has a note that says backfill to be 90% of a modified proctor, and a 95% modified for the pipe envelope. Is this for the entire project or for just under the roadway? It is a little much to get that kind of compaction on non-roadway areas, when all you really need to do is achieve the density of the existing soil.



SANTA ROSA COUNTY PROCUREMENT DEPARTMENT

6495 Caroline Street, Suite L | Milton, Florida 32570 850-983-1870 procurement@santarosa.fl.gov

Answer – A note has been added that standard proctor will be allowed for areas with no traffic loading.

5. Question – There is a bid item for new landscaping. I can't seem to find what we are replacing; can you clarify what we are to replace please?

Answer – This line item has been removed from the Bid-Tab

6. Question – Since we are working within feet of the houses that are built on a swamp that we will be dewatering around, will vibration monitoring be required?

Answer – No. This would be means and methods for the contractor to determine. However, it is highly suggested.

7. Question – With construction costs and the boom of the industry, I believe that the estimate is on the very low side for the project. Does the county have a contingency amount in place, and if the project over runs the estimate, will the project actually get off the ground? Second to that, 120 days may not be sufficient forgetting the pipe and structures and getting the work done. Working in such tight quarters, this will be a very slow-moving project. Could that time be extended to say 220 days?

Answer – Contract time will be extended to 220 days. Funding has not been allocated for this project. The road is failing, so the project is a priority pending BOCC Approval.

This Addendum is furnished to all known prospective Proposers. **Please sign and include one copy of this Addendum, with original signature, with your proposal as an acknowledgement of your having received same.**

NAME/TITLE: _____ SIGNATURE: _____

COMPANY: _____ DATE: _____

End of ADDENDUM #1.