


### **ADDENDUM NO. 3**

DATE: July 25, 2017

TO: All Bidders

FROM:  Boyce H. Evans, Purchasing Agent

SUBJECT: Addendum No. 3 – Grainger Avenue Bridge Project

BIDS TO BE OPENED: August 2, 2017, at 11:00:00 a.m. Eastern Time

This addendum is being published to respond to questions asked by potential bidders regarding the Grainger Avenue Bridge Project. This addendum becomes a part of the Contract Document and modifies the original specifications as noted.

Question #1: Can you provide a copy of the pre-bid meeting sign in sheet?

Response: The pre-bid meeting sign in sheet is attached to this addendum.

Question #2: Due to the amount of utility work, would the City consider extending the contract longer than 270 days?

Response: The City of Knoxville will extend the total construction contract time by 95 days to be a total of 365 calendar days from the date of the Notice to Proceed to Construction. We anticipate this to be approximately October 1, 2017 – September 30, 2018.

Question #3: Does a company have to be certified to conduct work for KUB in order to work on the sanitary sewer line?

Response: Since the sanitary sewer line will not require relocation, no certification will be required.

Question #4: Can the contractor use precast prestressed deck panels or metal decking for the bridge deck in lieu of wooden forms?

Response: Bridge deck forms for the concrete deck can be constructed using either removable forms or permanent forms. Permanent forms may be either remain-in place steel or precast prestressed concrete panels. In either case, the forms shall be attached by means other than welding to the main structural members or reinforcing steel. In the event that prestressed precast panels are used, a special design will be required to be submitted by the Contractor for approval.

The camber for each beam will also be required to be adjusted as noted on sheet B4 of the plans if panels are elected for use.

Question #5: Would the City be willing to add a pay item for “Foundation Preparation”?

Response: All foundation preparation shall be included in the price of the other bid items.

Question #6: Can the Contractor use recycled concrete for the backfill of the abutments?

Response: Recycled concrete may not be used in lieu of natural aggregate.

Question #7: Will the utility poles and lines overhead of the project area be relocated in advance of this project?

Response: Yes, the City is currently working with utility companies to get these overhead lines relocated in advance of construction beginning on this project.

Question #8: Will Pay Item 209-65.04 Temporary In Stream Diversion only be paid for under the initial diversion or is it paid for by linear foot each time a diversion occurs?

Response: The “In-Stream Diversion”, Item No. 209-65.04 shall only be paid for the initial diversion and not for additional adjustments.

Question #9: What should the Contractor do if bedrock is not encountered in the vicinity of boring #2 when working on the concrete encasement of the sanitary sewer line? Would KUB consider relocating the entire sanitary sewer line?

Response: Bedrock is anticipated at the location of boring #2. If unsuitable subsurface conditions are encountered, a change order will be issued if required.

**END OF ADDENDUM NO. 3**

NAME OF ATTENDEES

COMPANY NAME

ADDRESS

PHONE

EMAIL ADDRESS

[illegible]

TO OPEN ON 8/2/17 AT 11:00A.M. (EASTERN TIME)

NAME OF ATTENDEES	COMPANY NAME	ADDRESS	PHONE	EMAIL ADDRESS
Mark McKinnon	McKinnon Construction	7255 Corporate Park Dr London TN 37774	605-468-3550	MMcKinnon@bellsouth.net
Donnie Davidson	Wilson Const.	129 Lions Park Rd Athens, TN, 37303	423-745-0600	Kwilson@wilsonbuilds.com
Michael Edwards	Adams Contracting	501 Darby Creek Rd Lexington Ky	606-594-2174	michael@adamscontractingky.com
PHILIP NELSON	CIVIC ENGINEERING & IT	25 LINDSLEY AV, NASHVILLE, TN 37218	615-456-2798	nelson@civicinc.com
GEORGE DAVIS	CITY OF KNOXVILLE	3131 MORRIS AVENUE	865-215-6121	gdavis@knoxvilletn.gov

Boyd H. Evans (7/19/17)  
Boyd H. Evans  
Purchasing Agent  
City of Knoxville