



# St. Johns River Water Management District

Michael A. Register, P.E., Executive Director

4049 Reid Street • P.O. Box 1429 • Palatka, FL 32178-1429 • 386-329-4500 • www.sjrwmd.com

DATE: January 3, 2024

TO: Interested Firms

FROM: Breanna Pierce, Procurement Specialist

SUBJECT: Addendum 2 for Quote Request 39358 – Removal and Replacement of Fence and Gate at Sunland Citrus Mitigation Area SJ56 FY 23/24

As a result of questions received from potential respondents, please be advised of the following changes to the subject Quote Request:

1. The time and date for the submittal of responses has been extended until **2:00 p.m., January 10, 2024.**
2. **EXHIBIT 1 – STATEMENT OF WORK, Paragraph II. Objectives:** Delete paragraph and replace with the following paragraph:

## **II. Objectives**

The overall goal of this project is for removal/replacement of the entrance gate and approximately 60-110 feet of old wire fence, and the addition of four board wooden fence on western end only. Work includes removal of one 18-foot heavy duty metal gate and replacing with a 16-foot pipe gate, addition of approximately 32 feet of four board wooden entrance fence on the western end only, and removal and addition of 60-110 feet of five wired barbed wire in location indicated on the drawing (Figure 2). Currently the gate is damaged, and the existing barbed fences are failing. All removed materials will need to be removed from the property and disposed of properly by the winning Contractor. The barbed wire fencing placement may require minor clearing to install. For specific details of work and products see Table 1. To be considered all potential contractors must fill out Table 1 and it is highly suggested that they attend the pre-bid meeting to know the full scope of the project.

3. **EXHIBIT 2 — QUOTE COST SCHEDULE, REMOVAL AND REPLACEMENT OF FENCE AND GATE AT SUNLAND CITRUS MITIGATION AREA SJ56 FY 23/24:** Delete cost schedule and replace with the revised and attached cost schedule identified as “EXHIBIT 2 — QUOTE COST SCHEDULE (REVISED)”.

**NOTE:** Please acknowledge receipt of this Addendum in your submittal.

If you have any questions regarding this addendum, contact Breanna Pierce at (386) 643-1168 or via email at bpierce@sjrwmd.com.

Attachments:

EXHIBIT 2 — QUOTE COST SCHEDULE (REVISED)

**EXHIBIT 2 — QUOTE COST SCHEDULE (REVISED)  
REMOVAL AND REPLACEMENT OF FENCE AND GATE AT  
SUNLAND CITRUS MITIGATION AREA SJ56 FY 23/24**

(Note: This page must be submitted with response.)

**DUE BY: NO LATER THAN 2:00 PM, January 10, 2024 - RESPONSES SHALL BE SUBMITTED TO THE PROCUREMENT SPECIALIST AS IDENTIFIED ON THE FIRST PAGE OF THIS REQUEST.**

Award shall be based on the lowest total cost project cost, while meeting all requirements specified in the Quote Request. The quote shall include all labor, materials, equipment, site prep, and any necessary licensing, and insurance for removal and replacement of fence and gate as described in the Statement of Work.

<i><b>BID SCHEDULE</b></i> - Removal and Replacement of Fence and Gate at Sunland Citrus Mitigation Area SJ56 FY 23/24 (Not to exceed the amount of \$10,000.00)			
<i><b>Material/Work</b></i>	<i><b>Estimated Amount</b></i>	<i><b>Unit Cost</b></i>	<i><b>Total</b></i>
Steel Gate Replacement with Hardware and Chain	1 – Galvanized Tubular Gate, 16 ft. (L) x 50 in. (H), 19 gauge, 6 bars	_____ / each	\$ _____
Gate Posts	2 - 6 in. to 8- in. diameter post set in concrete 36 inches deep	_____ / each	\$ _____
Board Fencing with 4 Boards, Post and Face Boards	Approximately 32 LF of fence with post 4–5-inch diameter by 6.5 ft tall set in 24 inches deep (refer to all board fence specifics in write up above)	_____ / LF	\$ _____
Barbed Wire Fencing (5 Strand) with Post	Approximately 110 LF (refer to all barbed wire fence specifics in write up above and detail map for locations)	_____ / LF	\$ _____
Removal of All Old Materials From Site and Disposed of Properly Off-Site	Gates, posts, metal barbed fence, dug up stumps or tree debris removal		\$ _____
Misc. Charges	TBD		
		Total	\$ _____