

Bid No. 022-005 Re-Roofing Public Safety Building

Addendum: 2

Front Arched Concrete Roof Area

Contractor may install new 1/8" tapered Iso / EPS insulation sloping from front to rear at valley locations with the remainder of the deck substrate covered with 1/2" cover board and 60 mil PVC membrane.

MAR 1 22 1:31PM