

Ground Section> F:\5 projects\2017\2017-071 FCPS Parking Lot\20200224existemployee.sc

Final Section> F:\5 projects\2017\2017-071 FCPS Parking Lot\20200224designcar.sct

Processing 0+25.00 to 4+50.00

Total Cut : 310227.87 C.F., 11489.92 C.Y.

Total Fill: 2752.19 C.F., 101.93 C.Y.

Cut to Fill Ratio: 112.72

Station	Cut(sf)	Fill(sf)	Interval	Cut(cy)	Fill(cy)	Run Cut(cy)	Run
0+25.00	532.45	1.31					
			25.00	962.69	11.42	962.69	11.
0+50.00	1546.96	23.36					
			25.00	1334.87	18.09	2297.56	29.
0+75.00	1336.37	15.71					
			25.00	1216.21	11.72	3513.78	41.
1+00.00	1290.65	9.59					
			25.00	1149.48	6.17	4663.25	47.
1+25.00	1192.21	3.74					
			25.00	1037.12	2.20	5700.37	49.
1+50.00	1047.97	1.00					
			25.00	877.81	1.27	6578.19	50.
1+75.00	848.11	1.75					
			25.00	693.04	2.03	7271.23	52.
2+00.00	648.87	2.64					
			25.00	563.68	3.01	7834.92	55.
2+25.00	568.69	3.85					
			25.00	524.36	2.80	8359.27	58.
2+50.00	563.92	2.19					
			25.00	492.62	1.38	8851.90	60.
2+75.00	500.15	0.78					
			25.00	447.57	0.50	9299.47	60.
3+00.00	466.59	0.30					
			25.00	400.27	0.52	9699.74	61.
3+25.00	398.00	0.82					
			25.00	339.40	0.66	10039.14	61.
3+50.00	335.11	0.60					
			25.00	278.18	0.44	10317.31	62.
3+75.00	265.75	0.34					
			25.00	295.08	4.15	10612.39	66.
4+00.00	371.62	8.62					
			25.00	524.79	19.79	11137.18	86.
4+25.00	761.92	34.13					
			25.00	352.74	15.80	11489.92	101.
4+50.00	0.00	0.00					