

“City of Havelock
Public Services Storage Building”
Addendum 3
July 2, 2020

Questions Received During Site Visits

1. How is the electric line to covered rock, paving, etc.?

Trench for electric line is to be covered by six inches of ABC stone.

2. I had one question in regards to item number #22 on addendum #1. It states that if Base bid only is accepted than we must install the receptacles on the columns at the front and rear of the building. However, we are only told to install the receptacles if Additive #2 is accepted. Can you please clarify that any electrical work is to only be completed if Additive #2 is accepted?

Receptacles are to be installed only if additive 2 to is accepted?

3. Addendum 2 Questions 5 clarification?

Change answer to R-30 rigid.

4. Are roof panels to be screwed down or standard?

See answer on question 12 addendum 1.

Roof panels can be screw or standing seam 24-gauge R-30 standard vinyl.

5. Additive 1 what type of panel is to be used to enclose building?

Standard metal panels.

6. What type of insulation for roof and walls?

R-30 rigid for roof and R-19 for walls.