



- NOTES**
- All exposed surfaces to be trowel finished except as shown. See M.A.G. Section 340.
  - Contraction joint spacing shall be 10' maximum or as directed by the Inspector.
  - Construct curb and install 1/2" mastic expansion joints, A.S.T.M. D-1751, per M.A.G. Sec. 340 & 729.

Two working days before you dig.  
**CALL FOR THE BLUE STAKES**  
 263-1100  
 800-782-5348  
 Blue Stake Center

**NOTE:**  
 ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MOST RECENT EDITION OF THE CITY OF AVONDALE'S SUPPLEMENT TO THE M.A.G. SPECIFICATIONS AND STANDARD DETAILS CURRENTLY ON FILE AND AVAILABLE AT THE CITY OF AVONDALE'S ENGINEERING DEPARTMENT OR ONLINE AT THE CITY OF AVONDALE'S WEBSITE.

**WOOD/PATEL**  
 MISSION: CLIENT SERVICE  
 (602) 335-8500  
 WWW.WOODPATEL.COM

**ALAMAR**

DESIGNER: BROOKFIELD LAKIN, LLC  
 PROJECT NAME: ALAMAR - PHASE 1  
 PLAN TYPE: PAVING, STORM DRAIN, SIGNING AND MARKING PLAN  
 AVONDALE BLVD., BROADWAY RD., AND ALAMAR PARKWAY

SEAL: PROFESSIONAL ENGINEER  
 3188 FRANK MINGFENG HOO  
 EXPIRES 2/1/2019

EXPRES 12/31/21  
 PLAN DATE: 2/1/2019  
 LATEST REVISION DATE: 2/1/2019

SHEET NUMBER: 20 OF 30  
 PROJECT NUMBER: 174612.04

ENG 18-0208