

**LAKIN COMMUNITY FACILITIES DISTRICT
AVONDALE, ARIZONA**

**ALAMAR CFD PHASE 1 INFRASTRUCTURE IMPROVEMENTS
IFB SOLICITATION / PROJECT - EN 19-083**

ADDENDUM NO. 3

June 10, 2019

In reference to the Approved Plans and Specifications for the subject project, please note the following items which shall be added or changed:

INSTRUCTION TO BIDDERS:

ITEM NO. 1 Addendum No. 1 posted to Bidders at www.avondaleaz.gov/procurement on June 4, 2019 should be amended to read "Addendum No. 2".

PROJECT SPECIAL PROVISIONS AND BID SCHEDULE:

ITEM NO. 1 **For all Ductile Iron Pipe (DIP)**, Field lock gaskets are required at all straight joints. Bends such as tees, crosses, 90, 45, 22.5 and 11.25 requires "Mega Lug" for restraints, no thrust blocks. Tapping sleeves or connection to any existing lines require thrust blocks.

ITEM NO. 2 Bidder shall bid a 30" Class III RGRCP for Bid Item 13. Plan view and storm drain note on Sheet 21 of 30 calling out 24" Class III RGRCP is incorrect. The profile view is correctly calling out 30" RGRCP.

ITEM NO. 3 **Alamar Parkway** – 24" storm drain bid item has been removed from the Bid Schedule as it is not part of the approved plans.

ITEM NO. 4 Delete the Bid Schedule in Addendum No. 2 in its entirety and add the revised Bid Schedule labeled Appendix 1 – Addendum No. 3 included herein.

LIST OF ATTACHMENTS:

Appendix 1: Bid Schedule, Bid Addendum No. 3 – Excel Format (17 pages)

Contractor's Signature

Date

Note: A signed copy of this Addendum shall be returned with the Contractor's proposal and /or the Contractor shall acknowledge this Addendum in the space provided on the Proposal.