

Item Number	Item	Estimated Quantity	Unit	Unit Price	Line Item Total
1	Mobilization	1	LS		
2	Maintenance of Traffic	1	LS		
3	Clearing and Grubbing	0.25	AC		
4	Demolition	1	LS		
5	Earthwork Excavation By Machine	455	CY		
6	Earthwork Excavate, Haul, and Install On-site	650	CY		
7	Saw Cut Existing Concrete, up to 6" Thick	24	LF		
8	Rubblize Existing Concrete Swale, relocate and Install on-site	1	LS		
9	Install Wood Skimmer	1	LS		
10	Cut and Patch Gravel Driveway	197	SY		
11	1.5" Type SP-12.5 Asphalt Driveway	24	SY		
12	4" Fiber Reinforced Concrete Driveway	114	SY		
13	Lateral Pavement Patch per County Detail (6" GAB)	268	SY		
14	8" Stabilized Subgrade	138	SY		
15	FDOT Type F Curb and Gutter	67	LF		
16	Fiber Reinforced Concrete Flume	11	SY		
17	Fiber Reinforced Concrete Ditch	660	SY		
18	7' Dia. FDOT Type J Bottom, 6'-12' Deep	1	EA		
19	4' Dia. Stormwater Manhole, 0'-6' Deep	1	EA		
20	4' Dia. Stormwater Manhole, 6'-12' Deep	4	EA		
21	FDOT Type G Ditch Bottom Inlet, 6'-12' Deep	1	EA		
22	FDOT Type D Ditch Bottom Inlet, 0'-6' Deep	1	EA		
23	Connect to Existing Storm Structure	2	EA		
24	18" RCP, 0'-6' Deep	25	LF		
25	24" RCP, 6'-12' Deep	1479	LF		
26	14"x23" ERCP, 0'-6' Deep	31	LF		
27	19"x30" ERCP, 6'-12' Deep	71	LF		
28	24"x38" ERCP, 0'-6' Deep	159	LF		
29	18" MES	1	EA		
30	14"x23" MES	2	EA		
31	19"x30" MES	1	EA		
32	24"x38" MES	5	EA		
33	Relocate Fire Hydrant	1	EA		
34	Relocated 6" Crepe Myrtle	3	EA		
35	Sod	2480	SY		
36	Seed and Mulch	4563	SY		
37	Silt Fence	3500	LF		

TOTAL BID =	
-------------	--