

Crocket St Drainage Improvements Bid Form Revised

Item Number	Item	Estimated Quantity	Unit	Unit Price	Line Item Total
1	Mobilization	1	LS		
2	Maintenance of Traffic	1	LS		
3	Clearing and Grubbing	0.05	AC		
4	Demolition	1.00	LS		
5	Install Wood Skimmer	1	LS		
6	Cut and Patch Gravel Driveway	197	SY		
7	1.5" Type SP-12.5 Asphalt Driveway	24	SY		
8	4" Fiber Reinforced Concrete Driveway	114	SY		
9	Lateral Pavement Patch per County Detail (6" GAB)	268	SY		
10	8" Stabilized Subgrade	138	SY		
11	FDOT Type F Curb and Gutter	67	LF		
12	Fiber Reinforced Concrete Flume	11	SY		
13	7' Dia. FDOT Type J Bottom, 6'-12' Deep	1	EA		
14	4' Dia. Stormwater Manhole, 0'-6' Deep	1	EA		
15	4' Dia. Stormwater Manhole, 6'-12' Deep	4	EA		
16	FDOT Type G Ditch Bottom Inlet, 6'-12' Deep	1	EA		
17	Connect to Existing Storm Structure	2	EA		
18	18" RCP, 0'-6' Deep	25	LF		
19	24" RCP, 6'-12' Deep	1479	LF		
20	14"x23" ERCP, 0'-6' Deep	31	LF		
21	19"x30" ERCP, 6'-12' Deep	71	LF		
22	24"x38" ERCP, 0'-6' Deep	159	LF		
23	18" MES	1	EA		
24	14"x23" MES	2	EA		
25	19"x30" MES	1	EA		
26	24"x38" MES	5	EA		
27	Relocate Fire Hydrant	1	EA		
28	Relocated 6" Crepe Myrtle	3	EA		
29	Sod	920	SY		
30	Seed and Mulch	4563	SY		
31	Silt Fence	3500	LF		
				TOTAL BID =	