



Terry McKee, IT & Procurement Director

901 N. Broadway • Knoxville, TN 37917-6699

865.403.1133 • Fax 865.594.8858

purchasinginfo@kcdc.org

www.kcdc.org

Addendum

Solicitation Name	Clifton Road Site Preparation Work C19014	Addendum Number	3	Date	02-12-19
--------------------------	---	------------------------	---	-------------	----------

This addendum answers questions raised about this solicitation. To aid in readability, the questions are in black, the answers are in **bolded blue**, and the answers follow immediately below.

Q1	Sheet C4.01 has specific direction regarding the undercut in the low area with potential unsuitable soils. The recommendation is for removing the unsuitable soils and replacing with geogrid, stone, and compacted fill. Will the removal of unsuitable soils and replacement of engineered fill be paid as part of the allowances/unit prices with the cost of the stone and geogrid figured separately?
	Area noted on sheet C4.01 should be included in the base bid (undercut, grid, stone, and compacted fill). The allowances for unsuitable soils undercut and replacement are to be used for areas outside of the area identified on the plans.
Q2	For clarification on Addenda 2 Question #1, in the mass grading contract we are only placing topsoil in stockpiles at each site for distribution by another contractor at a later date? If this is the case would the site be temporary seeded in the mass contract and another contractor would be responsible for permanent seeding and erosion control matting at a later date?
	Since the scope of this project is to provide mass grading/subgrade preparation, it is anticipated that only temporary seeding will be used. Temporary seeding will be required based on construction phasing/scheduling and must meet the requirements established in the Construction General Permit for either 7 days or 14 days depending on steepness of the slopes.

