



USD 250 Pittsburg Community Schools

Pittsburg Community Schools - 510 Deill, PO Drawer 75, Pittsburg, KS 66762

Phone: (620) 235-3100 Fax: (620) 235-3106

Section 2.00 – Specifications Pittsburg High School Flooring Project 2021

Scope of work:

Remove approximately 7,425 square feet of existing carpeting and related base. Install the same quantities of VCT and base in the existing classrooms. Bidder will be responsible for all on-site measurements.

Pre-bid meeting scheduled for Thursday, April 29, 10:00 am CST at Pittsburg High School, 1978 E. 4th St, Pittsburg Kansas.

All work will be completed no later than Friday, July 30, 2021 and will not begin before Tuesday, May 25, 2021.

Materials Specifications:

The VCT will be Armstrong Standard Excelon Imperial Texture #51904 Sterling. Adhesive will be Armstrong S-515 thin spread. The base will be 4 inch Tarkett TA4 Gateway. Transitions will be metal base track with the appropriate snap-in transition to match the base color. The installer will be responsible for all measurements and quantities of the listed materials.

Qualifications:

Contractors shall be an established firm regularly engages in the installation of VCT flooring for a minimum of 10 years.

Preparation:

Once the existing carpet is removed, the installer will remove any existing adhesive residue so that no ridges or puddles are evident and only a thin smooth film remains. Patch floor as needed using polymer-modified patch compound. Allow all flooring material and adhesives to condition to room temperature for a minimum of 48 hours before installation. The installer will verify that all VCT of each color is from the same lot prior to installation

Installation:

Spread adhesive and install VCT per Armstrong Flooring's specifications. Once work is started is shall continue without interruption until project is completed, unless authorized in writing by Owner's Representative. Contractor will be responsible for implementation of local, state and national safety requirements.

Cleanup:

The installer will be responsible for the cleanup and removal from the site of all existing carpet and related installation materials including dumpster if needed for disposal of materials.

Shelf stock:

Installer will supply USD 250 with 3 cases of Armstrong Standard Excelon Imperial Texture #51904 Sterling (from the same lot number as the installed tile).