

	<h1>City of Wilson, NC.</h1> <h2>Addendum 1</h2>
<p><u>Please send inquiries and questions about this RFP to:</u></p> <p>Ricky Wilson  Purchasing Manager  <a href="mailto:rvwilson@wilsonnc.org">rvwilson@wilsonnc.org</a></p>	<p>RFP: 2023-55 – Demolition Services – 1615 Ward Blvd.</p> <p>RFP Due Date: <b>1/10/2024 at 2:00 pm</b></p> <p>Contract Type: Demolition Services</p>

Failure to acknowledge and return this addendum may subject your bid to be rejected based on the below information.

Vendor: \_\_\_\_\_

**Question 1: Has an asbestos survey been done on the building located at 1615 Ward Boulevard? Yes, this building was surveyed and came back clean with no ACM. This report is referenced as an attachment to the RFP.**

**Question 2: It was mentioned that outlying islands would need to be removed discussed at the pre-bid meeting, can you provide further detail on what is included? It has been determined that any outlying islands will not be included in this demolition. To clarify the demolition will include only the curb and guttering connected to the building area.**

**Question 3: Will the grease trap need to be removed or does it stay? The grease trap will need to be removed by the awarded demolition contractor.**

**Question 4: Does the shrubbery and trees need to be removed? Yes, they do. Any trees, shrubs, landscaping within the immediate building/curb/gutter area will need to be removed.**

**Question 5: Does the light pole within the immediate building area stay or is it to be removed in this demolition? It needs to stay. The awarded demolition contractor will need to work around it.**

**Question 6: Is there any sedimentation or erosion control plans for this particular demolition? No. However, standard safety precautions are to be observed during the entire demolition process.**

**Question 7: Are there any utilities that we will need to have capped or need to be turned off? Before the awarded contractor starts the demolition, the City contact will verify that all utilities are capped and cut off. Also, a utility locate will be done before work begins.**

**Question 8: There are storm drains in the immediate area. Are there any requirements as to prevent debris from entering the storm drains? There are at least two storm drains close to the Ward Blvd side**

of the property. All storm drains need to be protected from debris during the demolition process. This can be done using any method deemed appropriate by the awarded demolition contractor. (i.e./drain socks, etc.)