

**ACKNOWLEDGEMENT
RECEIPT OF ADDENDUM #2
ITB 17-PW07**

Upon receipt of documents, please email, fax or mail this page to:

City of Milton
Attn: Honor Motes, Purchasing Office
2006 Heritage Walk
Milton, GA 30004
Phone: 678-242-2507
Fax: 678-242-2499
Email: honor.motes@cityofmiltonga.us

I hereby acknowledge receipt of documents pertaining to the above referenced ITB.

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ STATE: _____ ZIP: _____

PHONE: _____ FAX: _____

EMAIL ADDRESS: _____

Signature
ADDENDUM #2

Date

This Addendum forms a part of the contract documents and **modifies** the original ITB documents as noted below:

****DUE DATE EXTENSION****

Please be advised, the new due date is May 19, 2017 at 2:00 p.m.

- 1) Based on Addendum #1 it looks like the Bid Schedule needs to be revised to add a pay item for the High Density Mineral Bond. Please advise.
See new bid schedule.
- 2) Based on the Variable Depth Milling quantity it looks like it includes the milling for the 2" Patching (on the Patching and Resurfacing roads identified on page 3 of Addendum #1) and the Variable Depth Milling for 3.5" and Edge Milling roads. If this is the case then the milling operation on the Patching and Resurfacing roads will be covered twice. It would simplify things if the Bid Schedule was revised to have a 2" Patching-19mm item for the Spot Patch and Top roads and a 2"-19mm item for the Patch and Resurfacing roads. Please clarify.
The variable depth milling is for Edge mill and 3.5" milling. Milling is considered incidental to the patching line item. 2" Patching has been eliminated as a line item.
- 3) On page 4 of Addendum #1 it states that the contractor will need to perform shoulder building and grassing on the Reconstruction and Resurfacing roads. What will be the width of the shoulder building?
Establishing a 4:1 slope is optimal.
- 4) Taylor Rd. calls for 2'-19mm and 1.5"-9.5mm. There is not a pay item for the 2"19mm unless the 2"-Patching pay item covers the work. A 2"-19mm pay item is needed. Please clarify.
See new bid schedule
- 5) Will the City be putting out a revised bid schedule with revised quantities for removing Springfield Creek Way and adding Double Springs Way as well as the Pay Item for the High Density Mineral Bond?
See new bid schedule for the High Density Mineral Bond. Quantities for the substitution will not change.
- 6) On the Bid schedule there's two patching Pay Items one for 2" patching and one for 3" patching. In addendum 1 it states patching at 3.5" then the question right after that it states all patches will be 3". Will the City please clarify the depth of all patching?
See question 2 above.

7) On page 3 of Addendum #1 the City of Milton has stated: **Utility coordination and relocation will be handled by the contractor.** Does this mean that the contractor should include the **COST** for relocation of any utilities in conflict or does this mean the contractor will handle the coordinating and locations with the utility companies **ONLY** – the City of Milton will be responsible for the cost of the relocations? Please clarify this statement.

Raising of water valves and hydrants would be considered incidental. Any others the contractor will handle the coordination and locations with the utility companies

*****SEE NEW BID SCHEDULE BELOW*****

THIS BID SCHEDULE REPLACES PAGE 18 OF ITB 17-PW07

[BIDDERS MUST RETURN THIS FORM WITH BID RESPONSE]

BID SCHEDULE - REVISED

NUMBER	DESCRIPTION		QUANTITY	PRICE	AMOUNT
150-1000	Traffic Control	LS	1		
301-2160	Soil-cement stabilized base, subbase, and shoulder course 13"	SY	13,000		
301-5000	Portland Cement	TN	500		
310-1101	Gr Aggr Base Crs, Incl Matl 4 in.	TN	400		
402-1802	Asphalt Concrete Patching including Bituminous Material & H Lime 3 in. 19mm	TN	4,400		
402-1802	Asphalt Concrete including Bituminous Material & H Lime 2 in. 19mm	TN	6,500		
402-3103	Recycled Asphalt Concrete 9.5 MM Superpave GP 2 Only Including Bituminous Material and H-Lime 1.5 in.	TN	7,500		
407-0010	Asphalt Rubber crack seal TP M	LS	1		
413-5000	Fog Seal	SY	23,000		
424-6201	Double Surface treatment, stn size 7+ 89 GP2 only with sand seal W10	SY	23,000		
432-5010	Mill Asphalt Conc Pvmt, Variable Depth	SY	66,000		
441-0104	5' Concrete Sidewalk Class A	SY	400		
441-6012	Curb & Gutter Type 2	LF	1,000		
441-Ramp	Concrete 9031 Ramps	EA	13		
653-0120	Thermoplastic Pavement Marking Arrow, Type 2	EA	10		
653-1704	Thermoplastic Solid Traffic Stripe, 24" White	LF	300		

653-2501	Thermoplastic Solid Stripe, 5" White	LM	12		
653-2502	Thermoplastic Solid Stripe, 5" Yellow	LM	12		
653-4501	Skip Traf Stripe, 5" White	LF	1,500		
700-9300	Sod	SY	250		
	High Density Mineral Bond	SY			
1	Concrete raised crosswalk per detail TC-3	EA	1		
2	Concrete raised crosswalk 6' top TC-3	EA	1		
3	Asphalt raised crosswalk per detail TC-3	EA	1		
4	Asphalt raised crosswalk 6' top TC-3	EA	1		
5	Asphalt speed hump per detail TC-2	EA	1		
6	Mini asphalt speed hump half size length, same height and width (6' long instead of 12') TC-2	EA	1		
7	Staining and stamping concrete	SF	1		
8	Pavers for raised crosswalk	SF	1		
9	Steel plate over gutter	EA	1		