

47th St. NW Storm Sewer Repair Project, GP 1241 (Phase 1) and
47th St. NW-Packard Ave. NW 78" Storm Sewer Rehab Project, GP 1198 (Phase 2)
The City of Canton Engineering Department

Addendum 2

City of Canton, Ohio
Purchasing Department
218 Cleveland Ave. SW, 4th floor
Canton, Ohio 44702

47th St. NW Storm Sewer Repair Project, GP 1241 (Phase 1) and
47th St. NW-Packard Ave. NW 78 Inch Storm Sewer Rehab Project, GP 1198 (Phase 2)

Item/Project

Engineering Department

Responsible Department

Monday, October 1, 2018 at 2:00 PM local time

Bids Due On or Before

Bid Proposal Submitted By:

Company Name

Street Address

City

State

Zip

Contact Person

Phone No.

Email Address

**47th St. NW Storm Sewer Repair Project, GP 1241 (Phase 1) and
47th St. NW-Packard Ave. NW 78" Storm Sewer Rehab Project, GP 1198 (Phase 2)
The City of Canton Engineering Department**

Request for Information 3:

Question:

With this being a storm line, should this be styrene free resin?

Answer:

The resin shall comply with the technical specifications provided.

Request for Information 4:

Question:

Would the City of Canton consider postponing the bid submission for two weeks, until 10/15/2018?

Answer:

Bid submissions are due as advertised on 10/1/18.

Request for Information 5:

Question:

When is the anticipated Notice to Proceed date?

Answer:

The Notice to Proceed is anticipated to be issued approximately one month after the project is awarded.

Request for Information 6:

Question:

Would the City consider changing the contract completion time from 120 days to 180 days due to the scope of work and the contractor's responsibility for any weather delays?

Answer:

The project duration is extended to 180 days.

Request for Information 7:

Question:

The Engineer's Estimate (EE) is approximately \$1.361 million. Will the project be awarded if the apparent lower bidder is greater than 15% of the EE? What is the total available funding for the project?

Answer:

The project will be awarded if the apparent lowest and best bidder is within 10% higher than the engineer's estimate. Total funding for this project consists of Ohio Public Works Commission (OPWC) funds along with City of Canton capital funds, if needed.

**47th St. NW Storm Sewer Repair Project, GP 1241 (Phase 1) and
47th St. NW-Packard Ave. NW 78” Storm Sewer Rehab Project, GP 1198 (Phase 2)
The City of Canton Engineering Department**

Request for Information 8:

Question:

Section VIII 1.03 C “The contractor shall determine an appropriate bypass pumping plan as needed to perform the CIPP lining and submit said plan to the City of Canton.” The data provided shows flows as little as 50 gpm to over 126,000 gpm. Would the City specify the minimum flow design that will be approved when submitted?

Answer:

It is the intent of this project to line the sewers only during dry weather. Constant flow is present in the sewers even during dry weather. However, the contractor shall consider the possibility of encountering increased flows in the sewer above constant flows, and implement an appropriate bypass pumping plan to allow for successful liner installation to occur based on his means and methods and within the project duration.

Request for Information 9:

Question:

Appendix C 1.2 B “The Installation Contractor shall operate under a quality management system that is third party certified to ISO 9001 or other internationally recognized organization standards. Proof of certification shall be submitted with the Bidder’s bid and required for approval.” Would internal, company specific displays of QA/QC be allowed in lieu of ISO 9001 or other third party systems for the Installation Contractor?

Answer:

The requirement for third party certification to ISO 9001 or other internationally recognized organization standards shall be satisfied.