

ADDENDUM NO. 3 TO CONTRACT DOCUMENTS

Project: Wastewater Treatment Plant
RAS Control Station Modifications H&S Project No. 30906-203-007

Owner: City of Havelock, North Carolina Date: July 12, 2018

To All Bidders:

Contractors submitting Proposals for the above named Project shall take note of the following changes, additions, deletions, clarifications, etc., in the Contract Documents, which shall become part of and have precedence over anything contrarily shown or described in the Contract Documents, and all such shall be taken into consideration and be included in the Contractor's Bid Proposal.

All other general items, conditions, drawings, and specifications shall remain the same. Please acknowledge the receipt of Addendum No. 3 with the Bid Form.

Refer to the Attached Sheets.

The return receipt requested with the communication will be deemed evidence that the bidder has received the Addendum and has followed the instructions herein. Please sign, date, clearly print company name, and email this sheet back to Lee Tillman, City of Havelock Finance Director, at ltillman@havelocknc.us immediately upon receipt.



Company Name

Acknowledgement of Receipt

Date

Handwritten signature of Todd W. Davis in black ink.

Todd W. Davis, P.E.
Principal Engineer
HAZEN AND SAWYER

**City of Havelock, NC
Wastewater Treatment Plant
RAS Control Station Modifications**

Addendum No. 3

PROJECT SCOPE:

1. The last bullet of Item 1 of Materials Furnished by Owner shall be revised to state the following:

"Up to two (2) total days of Manufacturer field services (one day for each valve and actuator assembly) for startup and testing."

2. The following shall be added to the last bullet of Item 2 of Materials Furnished by Owner:

"Both magnetic flow meters should be tested on the same day. One or both magnetic flow meters may be placed into operation untested by Manufacturer's representative for a period of up to three (3) days to allow for both meters to be in service for completion of Manufacturer's field services."

3. The word "equipment" shall be deleted from the second to last sentence of Construction Note 3. The following sentence shall be added at the end of Note 3:

"Materials furnished by Owner (plug valve/actuator package and magnetic flow meters) do not require coating; however, the Contractor shall protect factory provided coatings, and repair any damage to coatings as a result of the Contractor's failure to protect the coating at no additional expense to the Owner."

4. The Application column of the Painting Schedule shall be modified by deleting the words "mechanical equipment, valves" so the column reads, "All new piping".

CONTRACT DRAWINGS:

5. The following shall be added as Note 9 on Drawing M1

"The Owner will provide a vacuum truck to transport collected spillage from inside the existing RAS pipes to the influent pump station at the plant site. The Contractor shall provide means to cover and seal the vault drain to prevent spillage from entering into the drain, containment liner(s) as required to contain all spillage, and all necessary cleanup to remove any spillage not contained by the liner."