Georgetown County, South Carolina 129 Screven Street, Suite 239



129 Screven Street, Suite 239
Post Office Drawer 421270
Georgetown, SC 29442-4200
(843) 545-3083 • Fax (843) 545-3500
E-Mail • purch@gtcounty.org
Website • http://www.gtcounty.org

ADDENDUM #1 TO RFP #23-046

BID NUMBER: 23-046 ISSUE DATE: Tuesday, March 12, 2024

REVISED OPENING DATE: Wednesday, April 3, 2024

OPENING TIME: 3:30 PM (ET)

Pre-Bid Conference/Site Inspection: [n/a]

PROCUREMENT FOR: <u>Choppee Splash Pad</u>

This addendum will amend <u>RFP #23-046, Choppee Splash Pad</u>. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: <u>www.gtcounty.org</u>, select "Bid Opportunities" from the Quick Links section.

Question 1: Total Budget is \$215k for a recirculating splash pad with min of 6 features with

max GPM of 80 for the design?

Response: Splash pad is to be supplied by public utility water source using a max flow of

50GPM. No recirculation. All public utility. Conventional Domestic Single-Pass System Design a cost-effective splash pad when water consumption is unregulated. Domestic single-pass systems are ideal for limited use and/or

minimum water consumption.

Question 2: Where will the skid mounted system be housed? DHEC has requirements for size

of room for space around equipment.

Response: No recirculation; no skid mounted system.

Question 3: Will water, sanitary sewer and electricity be brought to within 15' of the pad?

Response: All utilities are on-site. **Ouestion 4:** If a recirculation system is required, will Georgetown County be submitting the DHEC required permits and costs associated with the stamped engineered plans? **Response:** No recirculation is required. The max flow is listed at 50 GPM. That restriction is most used for a flow through **Question 5:** water management system. The RFQ requires a recirculating system. **Response: Answered in Question 1. Question 6:** What size is the splash pad? **Response:** Size is NOT specified. Vendor to provide a plan based upon budget provided. **Question 7:** What design theme/interactive requirements do you have for the splash pad? (Nature, Explora, Nautical, etc) Theme NOT specified. Vendor to provide a plan based upon budget provided. **Response: Question 8:** The total budget including installation is \$215K. If recirculating water system is required, then the budget would need to be at least \$350K. That doesn't include the mechanical building which would have to be constructed to hold the equipment. A GC would be needed to include that part of the Construction as it would be outside a splash pad manufacturer's scope of work. **Response:** Not applicable. See Response for Question 1. **Question 9:** RFP deadline is 3/27. More time is needed to design the Splash Pad and include installation pricing in the bid. Is a later date possible? **Response:** The deadline is being revised to allow more time for vendors to respond. See updated timeline below.

REVISED DEADLINE BELOW:

| Item | Date | Time | Location* |
|-------------------------------------|---|----------------------------|----------------|
| Advertised Date of Issue: | Wednesday, March 6, 2024 | n/a | n/a |
| Pre-Bid Site Inspection: | Voluntary, on own | n/a | n/a |
| Deadline for Questions: | Wednesday, March 20ne 24, | 3 3 :00 <u>P</u> PM | n/a |
| | 20240 | ET | |
| Bids Must be Received on/or Before: | Wednesday, April 3ne 24, 20240 | 3 <u>:</u> 3 <u>0PM</u> | Electronic |
| | | <u>ET3:00PM</u> | |
| | | ET | |
| *Public Bid Opening & Tabulation: | Wednesday, April 3 ne 24 , 20240 | 3 <u>:</u> 3 <u>0PM</u> | Virtual Hybrid |
| | | <u>ET3:00PM</u> | |
| | | ET | |

[The Remainder of the page is intentionally left blank]



ADDENDUM ACKNOWLEDGEMENT

RFP #23-046 Choppee Splash Pad

To be returned with the final proposal submission to Georgetown County.

| COMP | ANY NAME: | | _ |
|------|----------------------------|---------------|---|
| 0 | Addendum #1 Received Date: | Initialed By: | |
| | Addendum #2 Received Date: | Initialed By: | |
| | Addendum #3 Received Date: | Initialed By: | _ |
| | Addendum #4 Received Date: | Initialed By: | |

| Addendum #5 Received Date: | _Initialed By: |
|----------------------------|----------------|
| Addendum #6 Received Date: | _Initialed By: |