Indian River County Purchasing Division 1800 27th Street Vero Beach, FL 32960 Phone (772) 226-1416



ADDENDUM NO. 1

Date: March 19, 2019

Project Name: WABASSO CAUSEWAY FISHING PIER DEMOLITION PROJECT (IRC-1712)

Bid Number: **2019035**

Bid Opening Date: Wednesday, March 28, 2019 at 2:00 p.m.

This addendum is released to provide clarification and plans update. All information provided herein is hereby incorporated into the bid documents.

- Q: The instructions state that the "bidder must have at least five years' experience in the construction of similar projects of this size and larger". For the purpose of meeting this requirement, will the experience of the bidder's principals, management, and supervisory staff be considered? In other words, if the firm does not meet this requirement but its staff does, will the bidder be qualified?
- A: The Experience of the bidder's principals, management and supervisory staff will be considered to meet this requirement as long as that staff is assigned and responsible for direct oversight of the project activities. This experience and the proposed staff's associated experience must be clearly identified as part of the submitted bid package.
- Q: The instructions state that the "bidder must have successfully constructed, as prime CONTRACTOR, at least three projects similar in scope to this project". Can this be amended to state "the bidder and/or its subcontractors must have..."? Also, will the County consider striking "as prime contractor" from this requirement? The experience is the same regardless of the firm's role in the overall project and it is likely that all (or most) of the bidders will be using subcontractors for portions of the work. Some firms may have not been the prime on similar projects but are nonetheless qualified.
- A: Due to the unique nature of the scope of work set forth in this Contract, requiring both bridge demolition and offshore reef deployment, the County is amenable to amending the bid requirements to reflect "the bidder and/or its subcontractors must have" and replacing the 'Prime Contractor' term with 'Contractor Team'.
- Q: At the prebid, it was stated that a survey would be provided. Will this survey include both the project site and the travel route shown in the bid documents? Bidders need this information ASAP in order to determine whether the material has to be trucked away from the site. If the material has to be trucked, can the County property on Wabasso Island Lane be available for use?

A: Please see the survey attached in this Addendum No. 1. Two areas have been identified for material storage, the area available for staging on the east side of the project is delineated in the plans. An approximate 100' x 40' section, sketch is attached with Addendum No.1, of the parking lot on the west side of the bridge will be provided for the Contractor to use.

Attachments:

- 1. Pre-Bid Conference Minutes
- 2. Pre-Bid Conference Sign-In Sheet
- 3. Updated Itemized Bid Schedule, and updated Page 2 of Specifications Division 2 Technical Provisions
- 4. Wabasso Fishing Pier Demolition and Debris Removal, Bid Plans, March 2019
- 5. Permit Boundary and Potential Deployment, Artificial Reef Zone 5
- 6. Bathymetric Survey
- 7. Original Plan "Fishing Walks at Structure B over Indian River", Drawing 1, 1968
- 8. Wabasso Fishing Piers Rehabilitation, 2006
- 9. Available staging area on the west side of the bridge

**************This Addendum must be acknowledged with submittal package and/or by return of this Acknowledgement with your submittal package **********

Company Name		
Name:	Title:	
(Type / Printed)		
Authorized Signature:	Date:	
Telephone:	Email:	



Board of County Commissioners

1801 27th Street Vero Beach, Florida 32960-3365 Telephone: (772) 567-8000 Fax: (772) 778-9391

PRE-BID MEETING MINUTES March 7, 2019 at 10:00 AM INDIAN RIVER COUNTY ADMINISTRATION BUILDING Room A1-303 Building A WABASSO CAUSEWAY FISHING PIER DEMOLITION PROJECT Project No. IRC-1712

The following meeting notes set forth our understanding of the discussions and decisions made at the subject meeting. If no objections, questions, additions, or comments are received within three (3) working days from issuance of the meeting notes, we will assume that our understandings are correct. The project will move forward according to the bid plans and specifications and the understandings herein.

PROJECT NAME:	Wabasso Causeway Fishing Pier Demolition Project
PROJECT NUMBER:	IRC-1712
BID NUMBER:	2019035

INTRODUCTIONS/SIGN IN SHEET

Attendance at this conference by all bidders was **MANDATORY**. No bidder arriving after the meeting has begun was allowed to sign in. This meeting was recorded as part of the project records.

PROJECT DESCRIPTION:

The project consists of the demolition and disposal of the existing Wabasso Causeway Fishing Pier, approach sidewalks and associated debris. The pier was severely damaged during Hurricane Matthew in 2016, with eight sections displaced and laying at the river bottom. The entire pier and support structure, which is in two sections and is approximately 1000 feet long, will be removed and placed at a permitted offshore artificial reef site.

CONTRACT DETAILS

Bid Opening:	Thursday, March 28, 2019 at 2:00 PM
Contract Time:	60 days to substantial completion
	90 days to final completion
Engineer's Estimate:	\$1,614,300.00 (Includes Force Account)
Liquidated Damages:	\$1,665.00 per day

CONTACTS BIDDING PROCESS

All communications concerning this bid shall be directed to Indian River County Purchasing

Division at purchasing@ircgov.com.

PROJECT CONSULTANTS:

Atkins, Melbourne, Florida – Kenneth M. Good, PE

UTILITIES:

FP&L – A known electric cable is running along the waterway bottom to the south of the pier. Other utilities shall be located by the One-Call System.

PERMITS:

All permitting for the project has been completed. The permits include: Department of the Army Permit - SAJ-2016-02916 (SP-AWP) Department of the Army Permit – SAJ-2017-00473 (NWP-CMM) Department of Environmental Protection – 31-0354699-006-EE

OTHER ISSUES

- Review and comment with questions and clarifications as soon as possible, no further comments 10 days prior to bid opening (Monday, March 18, 2019).
- The Notice to Proceed tentative of Contract Award.
- Maintenance of Traffic:
 - Contractor shall submit a Maintenance of Traffic Plan to the Indian River County, Traffic Division for acceptance.
 - The Maintenance of Traffic Plan shall meet the FDOT Index 600, January 2018 Edition and shall be signed and sealed by a Florida P.E.
 - Traffic Signs approved by FDOT may be required for Trucks/Equipment entering/leaving the park from the CR-510 Wabasso Bridge Traffic Lanes.
 - James Ennis (IRC-Assistant Public Works Director) stated that the Wabasso Causeway Bridge falls under FDOT jurisdiction and any operation from the bridge would need approval from FDOT, which would include the Contractor obtaining a permit from FDOT any MOT device or signage to be installed. The County has no ability to grant permission to operate from the structure.
 - Driveway, business and road access shall be maintained at all times
- The Contractor will be permitted to restrict the boat ramp usage of the boat ramp for up to 30 min two times a day for loading and unloading.
- Staging area is shown on the plan, space is limited for staging and contractor may need to arrange for frequent removal of unsuitable material and construction debris.
- The Contractor shall be responsible for removal of all debris generated by the marine & land-based demolition operations, along with restoration of the impacted areas. Excavated material such as the concrete sidewalk, is to be removed and disposed of by Contractor.
- Preparation of Concrete for Reef Deployment all metal or exposed reinforcement shall be removed as close to the concrete as possible, and extend no more than 6 inches, per the permit requirements. Removed metal material shall be disposed of in an approved manner.
- All clean concrete sections over 500 lbs shall be prepared and deployed within the

permitted OIARC reef area located approximately 3 miles off shore and about 5 miles south of the Sebastian inlet. Contractor shall comply with all conditions and requirements of the permits.

- James Ennis (IRC) stated, the reef shall be deployed in Reef Zone 5, Sub-Section C of the attached Plan (Center Coordinates: -80.34668584, 27.82888667), all material must to be placed within a 100-foot radius of the provided coordinates, in a uniform fashion with a maximum relief of 12 feet. The County will confirm the depths with a sound depth finder. If Contractor exceeds this maximum relief, they will be responsible for removing material to meet permit requirements.
- All demolition, removal, and disposal work shall be conducted from a barge or vessel. No work shall be conducted from the CR-510 Highway Bridge.
- Contractor will be responsible for Notifying the US Coast Guard for a Notice to Mariners.
- Work hours IRC work hours are from 7AM to 5PM, however on-water work time will also be limited to ½ hour after sunrise through ½ hour before sundown. Night time demolition/construction operations will not be allowed, work on weekends or holidays will need approval from IRC.
- James Ennis (IRC) emphasized the following requirements found in the Contract Documents:
 - A minimum two (2) week notification prior to material deployment is required under the Department of the Army Permit SAJ-2016-02916 (SP-AWP).
 - Pre-deployment dives are required by the Permit and will be conducted by County staff.
 - Maximum deployment at each Reef Zone is 1000 tons, as per Department of the Army Permit SAJ-2016-02916 (SP-AWP),
 - Barge for deployment is required to have Hydrostatic Number Charts to confirm the tonnage of material deployed.
 - Army Corps requires clean concrete with no rebar sticking out more than 6 inches See Department of the Army Permit SAJ-2016-02916 (SP-AWP).
 - Handrails shall be removed on all sections and this is to be considered as part of the pay item for disposal of each deck section.
 - Site restoration item on bid sheet shall include all concrete removal not suitable for deployment or broken concrete (pieces less than 500 lb)
- Ken Good (Atkins) stated that post-tensioning and pre-tensioning cables which are exposed will require removal and would fall under the rebar removal requirement

DISCUSSION

Questions & Answers

- Q: Will FPL buoy their line?
- A: It will be up to the contractor to coordinate with FP&L as to how they want their line protected during construction.
- Q: What is the anticipated timing for Notice to Proceed?

- A: Approximate 4 weeks after bid opening, the Bid Opening and/or Notice to Proceed will not be delayed due to the typical conditions favorable to deployment.
- Q: Is there a specific reason for 5-day work week?
- A: Regular working hours are defined as Monday through Friday 7AM to 5PM. Cost of inspection or testing during overtime work will be paid by the contractor, see Section 0800, Supplementary Conditions to the General Conditions, Article SC-6.02. Overtime Rate for Inspectors: \$50.00/ per hour for county inspector for 8 hours minimum and \$110.00/ hour for Atkins' Engineers.
- Q: Lead time for diving inspection.
- A: A minimum two (2) week notification prior to material deployment is required under the Department of the Army Permit SAJ-2016-02916 (SP-AWP). County staff will conduct the preand post-deployment dives required for permit reporting. The total number of anticipated deployments necessary to deploy up to 1000 tons of bridge material will be required at the time of the two (2) week notification.
- Q: Will a County inspector be on site at all times?
- A: Yes, the County or an engineering consultant will be onsite.
- Q: Can the Contractor work on both sides of the bridge demolition at the same time? A: Yes.
- Q: Can deployment of the material be taken out to the sea after hours?
- A: There are no restrictions on the transportation time of the material by the contract or permit.
- Q: What happens if the site is not acceptable following the inspection dive?
- A: The rule is to move 500 ft from any newly identified hardbottom.
- Q: Can the dive be done a day before deployment?
- A: The site can be checked a few days before however, it's most likely County staff will be onsite the morning of the first deployment to complete a pre-deployment assessment. If a predeployment dive is conducted days prior to deployment of material, County staff will still be on site to observe and record material deployment for permit reporting purposes.
- Q: Will slabs be able to handle the removal of post tension cables, and what if concrete is crumbling once it has been removed?
- A: There are plans available from the rehabilitation and the contractor shall make his own judgement, pieces of concrete acceptable can be cut to 10 ft lengths with a minimum weight of 500 lb. Available drawings are attached to this document. Only exposed cables would need to be removed.
- Q: Is there a restriction on placement?
- A: It should be a uniform drop from the barge. For example, a loader can be used to push the material from the barge.

- Q: What type of turbidity boom will need to be used?
- A: The floating turbidity barrier type is at the contractor's discretion as necessary to achieve their demolition operation while meeting permit requirements. The Contractor shall be responsible for providing BMP's sufficient for the location and conditions.
- Q: Does the work area and sea grass area need to be protected by the turbidity booms.
- A: Yes, the sea grass shall be protected with turbidity barriers as shown on the contract drawings. The work area shall be protected with a floating turbidity barrier in accordance with the permit SAJ-2017-00473.
- Q: Will be additional park area made available?
- A: No, the intent of this project was, to have the deployment material be stored on the barge and not in the park area. A bathymetric survey of the channel from the pier south to the Intracoastal Waterway is attached.
- Q: Can the park be used to truck material off site?
- A: The area available for staging on the east side of the project is delineated in the plans. An approximate 100' x 40' section, sketch attached, of the parking lot on the west side of the bridge will be provided for the Contractor to use. Please be aware that the Contractor will be responsible for restoring the lay down areas to the condition prior to use.
- Q: Does all debris material need to be deployed to the reef?
- A: The Contractor shall use all suitable material from the existing bridge components to build an artificial reef located in reef zone 5C, center coordinates provided above.5C. Up to 1000 TN can be deployed at this location. No materials should be tampered with to minimize the amount of suitable material eligible for deployment.
- Q: What happens if the Army Corps finds the material not suitable during inspection? While it has been selected on established material criteria as outlined in the permits?
- A: Material staged for placement will be inspected by County staff and the Contractor to confirm it complies with all requirements outlined in the permit prior to any and all AOCE inspections pre-deployment. If any unforeseen conditions arise, they will be addressed at that time.
- Q: Do the piles have stingers?
- A: The details of the piles are not known.
- Q: What is the force account used for?
- A: Force Account Funds can be used by the County staff for unforeseen conditions, expenses or overrun on quantities due to additional work required. Any work proposed to utilize contingency funds must be identified and agreed upon before any work is performed and a Work Change Directive issued prior to any work being performed.
- Q: Bid Item No2.01 Crane, when will that be used?
- A: Revised bid sheets will be issued with this Addendum which remove this pay item. All equipment costs necessary for the project work to be completed shall be included in the respective pay items bid prices the work is associated with.

- Q: What if bids are exceeding the County's budgets?
- A: Options to address a low bid in excess of the current project budget will be evaluated at that time.
- Q: Is there a commercial diving requirement? OSHA? Commercial? Or Army Corps?
- A: It is up to the Contractor to follow their business requirements/OSHA/company policies. This is not an Army Corps project and specific dive requirements are not mandated by the County. An Army Corps dive plan is not required.

Meeting adjourned at 11:00AM

MANDATORY PRE-BID MEETING SIGN-IN SHEET INDIAN RIVER COUNTY ENGINEERING INDIAN RIVER COUNTY ADMINISTRATION BUILDING Room A1-303 Building A WABASSO CAUSEWAY FISHING PIER DEMOLITION PROJECT PROJECT No. IRC-1712 March 7, 2019 at 10:00 A.M.						
NAME	COMPANY & ADDRESS	PHONE # / FAX # / CELL #	EMAIL ADDRESS			
KEN GUOD	ATKINS-ENGINEER	321-775-6270	Iremeth. good eatkinsslobal			
Bob Bezano	LUSTOM BUILT MARIA E 2025TRUCTION	772-333-2383	bob Constan built marines. ~0			
Alain Peña	PosciDon Dredse & Marine		Alain P@ PDMasincinc. Com			
ED Williams	Shorehove Jourdation	954-985-0460	collians @shorelide foundation. Com			
Fony LANDRY	RUSH MARINE LLC	813-393-7375	+landry @rushinc, com			
Klishin Ceiendechs	IRC Eug	772-226-1327	Kleiendeckora iregov. com			
MIKE HELLER	IRCENG.	772-226-1585	mheller a Ircgou.com			
GRAHAM COFER	BALLARD MARING CONSTRUCTION	912-438-0542	graham, CoFer@bokaRDMC.COM			
Richard King	Mcculley Marineser	772-216-9716	richard@mccuiley marine, c			
And Soherch	JRC PW	772 - 226-1931	Asobusha ICC. gov			
Diane Lystlund	IRC Purchasing	772-226-1418	dystlund@ircgou.com			

F:\Public Works\ENGINEERING DIVISION PROJECTS\1712 Wabasso Fishing Pier-Bridge Removal\1-Admin\Meetings\Pre-Bid Meeting\1712_Pre-Bid Meeting Sign In Sheet_20190307.docx

MANDATORY PRE-BID MEETING SIGN-IN SHEET INDIAN RIVER COUNTY ENGINEERING INDIAN RIVER COUNTY ADMINISTRATION BUILDING Room A1-303 Building A WABASSO CAUSEWAY FISHING PIER DEMOLITION PROJECT PROJECT No. IRC-1712 March 7, 2019 at 10:00 A.M.					
NAME	COMPANY & ADDRESS	PHONE # / FAX # / CELL #	EMAIL ADDRESS		
	BCI 6526 S.KANNER THUY # 345 AFT				
ANDREW CONNELLY	UNFERMATER ENGINEERING	772-337-3116 Ph	LYZABROMERS CONSTRUCTION FL. CON aconnelly QUESI. COM ScoTTG MCCLULLEY MARINE, COM		
LYZA NICHOW ANDREW CONVELLY SCOT BACHMAN	SERVICES, INC. (LESD) MCCULLEY MARINE Z309 NOCOdere (-TP.ON	772-216-3907 Coll 772-489-6069 OFFC	ScoTO Macheley MARINE, can		

F:\Public Works\ENGINEERING DIVISION PROJECTS\1712 Wabasso Fishing Pier-Bridge Removal\1-Admin\Meetings\Pre-Bid Meeting\1712_Pre-Bid Meeting Sign In Sheet_20190307.docx

PROJECT NAME:WABASSO CAUSEWAY FISHING PIER DEMOLITION PROJECT

PROJECT NO. IRC-1712

BID NO. 2019035

BIDDER'S NAME

Item No.	Description	Unit	Quantity	Unit Price	Amount
2	MOBILIZATION/DEMOBILIZATION	EA	1		
3	DEMOLITION - WEST STRUCTURES				
3.01	FULL 50 FOOT SECTIONS ABOVE WATER, REMOVAL	EA	8		
3.02	40 FOOT SECTION/ABUTMENT	EA	1		
3.03	FULL PIERS	EA	11		
3.04	UNDERWATER SUPERSTRUCTURE SECTIONS (INCLUDES DIVERS, BMP'S ENVIRONMENTAL MONITORING), REMOVAL	EA	2		
3.05	PARTIAL PIERS TO BE RECOVERED	EA	5		
3.06	UPLAND SIDEWALK REMOVAL	SF	300		
4	DEMOLITION -EAST STRUCTURES		,		
4.01	FULL 50 FOOT SECTIONS ABOVE WATER, REMOVAL	EA	3		
4.02	30 FOOT SECTION/ABUTMENT	EA	1		
4.03	FULL PIERS	EA	5		
4.04	UNDERWATER SUPERSTRUCTURE SECTIONS (INCLUDES DIVERS, BMP'S ENVIRONMENTAL MONITORING), REMOVAL	EA	6		
4.05	PARTIAL PIERS TO BE REMOVED	EA	5		
4.06	PARTIAL PIERS TO BE RECOVERED	EA	5		
4.07	UPLAND SIDEWALK REMOVAL	SF	300		
5	DISPOSAL OF MATERIALS (OFFSHORE REEF DEPLOYMENT)	LS	1		
6	SITE RESTORATION	LS	1		
	WABASSO CAUSEWAY FISHING PIER DEMOLITION PRO) JEC	 T	SUB-TOTAL	
	FORCE ACCOUNT				\$220,000.00
т	OTAL PROJECT ESTIMATE (INCLUDING FORCE ACCOUI	NT)		TOTAL	
FOTAL	PROJECT BID AMOUNT IN WORDS				

NOTE: IF THERE IS A DISCREPANCY BETWEEN THE PLANS (SUMMARY OF PAY ITEMS) AND THE ITEMIZED BID SCHEDULE. THE BID SCHEDULE WILL BE UTILIZED FOR BIDDING PURPOSES.

SF=Square Feet LS=Lump Sum EA=Each PD=Per Day

SECTION 1 - MOBILIZATION/DEMOBILIZATION

Perform preparatory work and operations in mobilizing for beginning work on the project, including, but not limited to, those operations necessary for the movement of personnel, equipment, supplies, and incidentals to the project site and for the establishment of temporary offices, buildings, safety equipment and first aid supplies, and sanitary and other facilities. Include the costs of bonds and any required insurance and any other preconstruction expense necessary for the start of the work, excluding the cost of construction materials.

Demobilization shall be deemed to consist of all tasks necessary for removal of materials, plant, and equipment from the site upon completion of the work, restoration of the site and site access to original condition.


SECTION 2 - PREVENTION, CONTROL, AND ABATEMENT OF EROSION AND WATER POLLUTION

<u> PART 1 – GENERAL</u>

1.1 SCOPE

- A. This Section covers erosion control and the treatment of dewatering water and stormwater runoff from the construction site and work area. Pollution control measures shall prevent polluted or turbid waters from being discharged from the construction site or work area to undeveloped portions of the site or offsite, including but not limited to Multiple Separate Storm Sewer Systems (MS4s) and Waters of the State.
- B. The OWNER considers pollution from dewatering water and stormwater runoff from a construction site or work area to be a very serious offense. The CONTRACTOR is solely responsible for preventing pollution caused by dewatering water and stormwater runoff from the construction site or work area. Note that state regulations do not allow mixing stormwater and dewatering groundwater in the same release separate and independent discharges are required.
- C. Pollution control measures specified herein represent minimum standards to be adhered to by the CONTRACTOR throughout the Project's construction. The OWNER reserves the right to require the CONTRACTOR to employ additional pollution control measures, when in the sole opinion of the OWNER, they are warranted. If site specific conditions require additional erosion and stormwater pollution control measures during any phase of construction or operation to prevent erosion or to control sediment or other pollution,

WABASSO FISHING PIER DEMOLITION AND DEBRIS REMOVAL WABASSO, FL BID PLANS



Fl. Lic. No. 61687



Indian River County 1801 27th Street, Vero Beach, FL 32960 Project Manager: Kirstin Leiendecker

GENERAL NOTES

- 1. THIS PROJECT INCLUDES THE COMPLETE DEMOLITION AND REMOVAL OF THE ENTIRE EAST AND WEST SPANS OF THE WABASSO FISHING PIER, ALONG WITH THE CONNECTING SIDEWALKS AT EACH END. ALL COMPONENTS OF THE PIER (INTACT AND DAMAGED/DISPLACED), INCLUDING PILES, CAPS, DECK SECTIONS AND LOOSE DEBRIS, ARE TO BE REMOVED. THE ENINGEER OR OWNER SHALL BE INFORMED UPON DISCOVERY OF ANY DEBRIS UNRELATED TO WABASSO FISHING PIER.
- 2. CONTRACTOR SHALL COMPLY WITH ALL NOTES, CONDITIONS AND REQUIREMENTS GIVEN WITHIN THE DRAWINGS, SPECIFICATIONS, AND PERMITS. THE SPECIFICATIONS HAVE BEEN PREPARED BY INDIAN RIVER COUNTY STAFF INDEPENDENT OF THE PLANS. THESE SPECIFICATIONS COVER THE OFFSHORE PLACEMENT AND PROVIDE SUPPLEMENTAL INFORMATION AND REQUIREMENTS FOR THE DEMOLITION. IN THE EVENT THERE IS A DISCREPANCY BETWEEN THESE PLANS AND THE SPECIFICATIONS OR OTHER COUNTY SUPPLIED DOCUMENTS, IT IS THE CONTRACTORS RESPONSIBILITY TO REQUEST CLARIFICATION. GENERALLY THE MORE STRINGENT REQUIREMENT WILL PREVAIL.
- 3. ALL METAL RAILINGS, BRACKETS, EXPOSED REINFORCING, OR OTHER FITTINGS SHALL BE REMOVED AS CLOSE TO THE CONCRETE AS PRACTICABLE, WITH PROTRUSION NOT TO EXCEED 6 INCHES IN LENGTH FROM THE CONCRETE IT IS INCASED IN. SAID MATERIALS SHALL BE DISPOSED OF AT AN APPROVED UPLAND FACILITY.
- 4. ALL CLEAN CONCRETE COMPONENTS OVER 500 LBS SHALL BE DISPOSED OF AT 1 OF 12 OFFSHORE ARTIFICIAL REEF SITES LOCATED APPROXIMATELY FIVE MILES EAST-SOUTHEAST OF SEBASTIAN INLET. THIS REEF SITE WAS AUTHORIZED BY USACE PERMIT SAJ-2016-02916 (SP-AWP). CONTRACTOR SHALL COMPLY WITH ALL CONDITIONS AND REQUIREMENTS WITHIN AUTHORIZED PERMITS, UNLESS SPECIFICALLY NOTED OTHERWISE.
- 5. THE FOLLOWING IS A SUMMARY OF THE MAJOR PIER COMPONENTS TO BE REMOVED.
 - 11 INTACT 50' CONCRETE PIER DECK SECTIONS
 - 2 INTACT 25' CONCRETE PIER DECK ABUTMENT SECTIONS 8 - SUBMERGED/DISPLACED/DAMAGED CONCRETE PIER
 - DECK SECTIONS
 - 38 FULL LENGTH INTACT CONCRETE PILES 5 - PARTIAL/BROKEN/DISPLACED CONCRETE PILES
 - 16 INTACT CONCRETE PILE CAPS
 - 5 SUBMERGED/DISPLACED/DAMAGED CONCRETE PILE CAPS 1,530 SQ. FT. - CONCRETE SIDEWALK
- PIER COMPONENTS SHALL BE REMOVED FROM THE WATERWAY WITHOUT ADVERSELY IMPACTING AQUATIC NATURAL RESOURCES.
- 7. PIER COMPONENTS WILL BE LIFTED STRAIGHT UP AND NOT DRAGGED, SO THAT NO POTENTIAL SEAGRASS AND/OR HARDBOTTOM IS HARMED OR DAMAGED.
- 8. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTION TO PROTECT EXISTING STRUCTURES INCLUDING UNDERGROUND AND ABOVE GROUND UTILITIES. AN 811 UTILITY LINE LOCATION CALL (1-800-432-4770) SHALL BE CONDUCTED BY CONTRACTOR TO LOCATE ANY UTILITIES IN THE FACILITY. A KNOWN FPL ELECTRICAL CABLE(S) IS RUNNING ALONG THE WATERWAY BOTTOM JUST TO THE SOUTH OF THE PIER. THE CABLE(S)SHALL BE PROTECTED FROM DAMAGE DURING DEMOLITION OPERATIONS. THE CONTRACTOR SHALL COORDINATE DIRECTLY WITH FPL TO INSURE CLEARANCE AND PROTECTION REQUIREMENTS, APPROPRIATE FOR THE CONTRACTOR'S PROPOSED EQUIPMENT ARE MET. PRIOR TO MOBILIZATION, THE CONTRACTOR SHALL SUBMIT A PLAN, WHICH HAS BEEN APPROVED BY FPL, IDENTIFYING REQUIRED

7175 Murrell Road Melbourne, Florida 32940 321-242-4942 FBPR Certificate of Authorization No. 24 WABASSO FISHING PIER DEMOLITION AND DEBRIS REMOVAL INDIAN RIVER COUNTY GENERAL NOTES CLEARANCES AND PROTECTION METHODS.

- 9. SUBMERGED PIER SECTIONS WERE LOCATED WITH A DIVER AND HAND-HELD GPS UNIT. LOCATIONS ARE APPROXIMATE. THE ORIENTATION OF THE SUBMERGED DECK SECTIONS IS APPROXIMATE BASED ON DIVER OBSERVATIONS WITH LIMITED VISIBILITY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE POSITION, ORIENTATION, CONDITIONS, ETC. OF ALL PIER COMPONENTS AND DEBRIS PRIOR TO MOBILIZATION.
- COMPLETE REMOVAL OF THE PILES IS PREFERED. IF IT IS NOT PRACTICAL OR POSSIBLE TO COMPLETELY REMOVE A PILE, IT SHALL BE CUT OFF AT LEAST ONE FOOT BELOW THE MUDLINE, WITH ALL REINFORCING CUT FLUSH WITH THE CONCRETE. BASED ON CRANE CAPACITY LIMITS, DECK SECTIONS MAY BE CUT TO MINIMUM LENGHT OF 10 FEET.
- 11. ALL EQUIPMENT INCLUDING VESSELS AND TURBIDITY CURTAIN WILL BE REQUIRED TO FOLLOW PROPER U.S.C.G. PROTOCOL FOR OVERNIGHT STORAGE.
- 12. THE CONTRACTOR SHALL PROVIDE ALL WARNING SIGNS, LIGHTS, & SIGNALS AS REQUIRED TO ADEQUATELY WARN THE PUBLIC AGAINST DANGER AND TRESPASS WITHIN THE DESIGNATED CONSTRUCTION SITE.
- 13. ALL PIER DEMOLITION, REMOVAL, AND DISPOSAL WORK SHALL BE CONDUCTED FROM A BARGE OR SIMILAR VESSEL. NO WORK SHALL BE CONDUCTED FROM THE HIGHWAY BRIDGE, AND THE WORK SHALL NOT IMPACT TRAFFIC ON THE HIGHWAY BRIDGE.
- 14. NOTICE TO MARINERS: THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE U.S. COAST GUARD IN SUFFICIENT TIME TO ALLOW FOR PUBLICATION OF A NOTICE TO MARINERS. THE LOCAL COAST GUARD IS:

COMMANDER 7TH COAST GUARD DISTRICT BRICKELL PLAZA FEDERAL BUILDING 909 S.E. FIRST AVENUE, ROOM 406 MIAMI, FLORIDA 33131-3028 ATTN: (LNM) TELEPHONE: (305)415-6750 FAX: (305)415-6757

THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE U.S. COAST GUARD FOR ALL BUOYS, MARKERS, AND OTHER NAVIGATION AIDS PRIOR TO INSTALLATION. AIDS, LIGHTS OR TARGETS SHALL NOT BE PLACED OR COLORED IN A MANNER THAT THEY WILL OBSTRUCT OR BE CONFUSED WITH NAVIGATION AIDS.

15. GENERAL HOURS OF OPERATIONS WILL BE LIMITED TO ONE HALF HOUR AFTER SUNRISE THROUGH ONE HALF HOUR BEFORE SUNDOWN; NO NIGHTTIME OPERATIONS WILL BE ALLOWED. NO WORK SHALL BE PERFORMED ON SUNDAY'S OR HOLIDAYS WITHOUT PRIOR APPROVAL FROM THE OWNER OR ENGINEER

RESOURCE PROTECTION NOTES

- THE CONTRACTOR SHALL COMPLY WITH ALL WATER QUALITY REQUIREMENTS AND REGULATORY PERMITS ISSUED BY LOCAL, STATE AND FEDERAL AUTHORITIES PRIOR TO AND AT THE TIME OF CONSTRUCTION.
- 2. MANGROVES SHALL BE PROTECTED FROM DAMAGE DURING DEMOLITION OPERATIONS. A MINIMUM FIFTEEN FOOT WIDE BUFFER AROUND LANDWARD SIDE OF THE MANGROVES DRIP LINE SHALL BE FENCED OFF WITH ORANGE CONSTRUCTION SAFETY FENCE.
- 3. SEAGRASS SHALL BE PROTECTED FROM DAMAGE DURING DEMOLITION OPERATIONS. NO VESSELS OR EQUIPMENT SHALLOPERATE OVER OR TRAVERSE ATOP OF THE SEAGRASS BED. A MINIMUM TWENTY-FIVE FOOT BUFFER AROUND THE SEAGRASS BED SHALL BE PROTECTED WITH A FLOATING TURBIDITY BARRIER.



BETWEEN THE KEEL OR LOWEST PORTION OF THE VESSEL RUNNING GEAR AND THE BOTTOM OF THE WATERWAY SHALL BE MAINTAINED. WORK SHALL COMPLY WITH STANDARD MANATEE CONDITION FOR IN-WATER WORK, THE CONTRACTOR SHALL 8. COMPLY WITH THE FOLLOWING CONDITIONS INTENDED TO PROTECT MANATEES FROM DIRECT PROJECT EFFECTS: ALL PERSONNEL ASSOCIATED WITH THE PROJECT SHALL 7.1. BE INSTRUCTED ABOUT THE PRESENCE OF MANATEES 8.1. AND MANATEE SPEED ZONES, AND THE NEED TO AVOID COLLISIONS WITH AND INJURY TO MANATEES. THE CONTRACTOR SHALL ADVISE ALL CONSTRUCTION PERSONNEL THAT THERE ARE CIVIL AND CRIMINAL PENALTIES FOR HARMING, HARASSING, OR KILLING MANATEES WHICH ARE PROTECTED UNDER THE MARINE MAMMAL PROTECTION ACT, THE ENDANGERED SPECIES 8.2. ACT, AND THE FLORIDA MANATEE SANCTUARY ACT. 7.2. ALL VESSELS ASSOCIATED WITH THE CONSTRUCTION PROJECT SHALL OPERATE AT "IDLE SPEED/NO WAKE" AT ALL TIMES WHILE IN THE IMMEDIATE AREA AND WHILE IN WATER WHERE THE DRAFT OF THE VESSEL PROVIDES LESS THAN A FOUR-FOOT CLEARANCE FROM THE 8.3. BOTTOM. ALL VESSELS WILL FOLLOW ROUTES OF DEEP WATER WHENEVER POSSIBLE. 7.3. SILTATION OR TURBIDITY BARRIERS SHALL BE MADE OF MATERIAL IN WHICH MANATEES CANNOT BECOME ENTANGLED, SHALL BE PROPERLY SECURED, AND SHALL BE REGULARLY MONITORED TO AVOID MANATEE ENTANGLEMENT OR ENTRAPMENT. BARRIERS MUST NOT IMPEDE MANATEE MOVEMENT. 7.4. ALL ON-SITE PROJECT PERSONNEL ARE RESPONSIBLE FOR OBSERVING WATER-RELATED ACTIVITES FOR THE 8.4. PRESENCE OF MANATEE (S) . ALL IN-WATER OPERATIONS, INCLUDING VESSELS, MUST BE SHUTDOWN IF MANATEE (S) COMES WITHIN 50 FEET OF THE OPERATION. ACTIVITIES WILL NOT RESUME UNTIL THE MANATEE (S) HAS MOVED BEYOND THE 50-FOOT RADIUS OF THE PROJECT OPERATION, OR UNTIL 30 MINUTES ELAPSES IF THE MANATEE (S) HAS NOT REAPPEARED WITHIN 50 FEET OF THE OPERATION. ANIMALS MUST NOT BE HERDED AWAY OR HARASSED INTO LEAVING. ANY COLLISION WITH OR INJURY TO A MANATEE SHALL 7.5. BE REPORTED IMMEDIATELY TO THE FLORIDA FISH AND WILDLIFE CONSERVATION COMMISSION (FWC) HOTLINE AT 1-888-404-3922, COLLISION AND/OR INJURY SHOULD ALSO BE REPORTED TO THE U.S. FISH AND WILDLIFE SERVICE IN JACKSONVILLE (1-904-731-3336) FOR NORTH FLORIDA OR IN VERO BEACH (1-722-562-3909) FOR SOUTH FLORIDA, AND EMAILED TO FWC AT IMPERILEDSPECIES@MYFWC.COM A TEMPORARY SIGN CONCERNING MANATEES SHALL BE 7.6. POSTED PRIOR TO AND DURING ALL IN-WATER PROJECT 8.6. ACTIVITIES. ALL SIGNS ARE TO BE REMOVED BY THE CONTRACTOR UPON COMPLETION OF THE PROJECT. TEMOPORARY SIGNS THAT HAVE ALREADY BEEN APPROVED FOR THIS USE BY THE FWC MUST BE USED. ONE SIGN WHICH READS CAUTION: BOATERS MUST BE POSTED. A SECOND SIGN MEASURING AT LEAST $8\frac{1}{2}$ " BY 11" EXPLAINING THE REQUIREMENTS FOR "IDLE WABASSO FISHING PIER DEMOLITION AND DEBRIS REMOVAL 7175 Murrell Road INDIAN RIVER COUNTY Melbourne, Florida 32940 GENERAL NOTES 321-242-4942 FBPR Certificate of Authorization No. 24

ALL PIER REMOVAL OPERATIONS SHALL BE CONTAINED

DRAGGED, SO THAT ANY POTENTIAL SEAGRASS AND/OR

AT ALL TIMES, A MINIMUM 1 FOOT VERTICAL CLEARANCE

TO, TURBIDITY BARRIERS AND SILT FENCES.

HARDBOTTOM IS NOT DAMAGED.

WITHIN WATER QUALITY BMPS SUCH AS, BUT NOT LIMITED

PIER COMPONENTS SHALL BE LIFTED STRAIGHT UP AND NOT

SPEED/NO WAKE" AND THE SHUT DOWN OF IN-WATER OPERATIONS MUST BE POSTED IN A LOCATION PROMINENTLY VISIBLE TO ALL PERSONNEL ENAGAGED IN WATER-RELATED ACTIVITES. THESE SIGNS CAN BE VIEWED AT

HTTP://WWW.MYFWC.COM/WILDLIFEHABITATS/MANTEE _____SIGN__VENDORS.HTM.

QUESTIONS CONCERNING THESE SIGNS CAN BE FORWARDED TO THE EMAIL ADDRESS LISTED ABOVE.

- 8. WORK SHALL COMPLY WITH SEA TURTLE AND SMALLTOOTH SAWFISH CONSTRUCTION CONDITIONS. THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING PROTECTED SPECIES CONSTRUCTION CONDITIONS:
- 8.1. THE CONTRACTOR SHALL INSTRUCT ALL PERSONNEL ASSOCIATED WITH THE PROJECT OF THE POTENTIAL PRESENCE OF THESE SPECIES AND THE NEED TO AVOID COLLISIONS WITH SEA TURTLES AND SMALLTOOTH SAWFISH. ALL CONSTRUCTION PERSONNEL ARE RESPONSIBLE FOR OBSERVING WATER-RELATED ACTIVITIES FOR THE PRESENCE OF THESE SPECIES.
- 8.2. THE CONTRACTOR SHALL ADVISE ALL CONSTRUCTION PERSONNEL THAT THERE ARE CIVIL AND CRIMINAL PENALTIES FOR HARMING, HARRASSING, OR KILLING SEA TURTLES OR SMALLTOOTH SAWFISH, WHICH ARE PROTECTED UNDER THE ENDANGERED SPECIES ACT OF 1973.
- 8.3. SILTATION BARRIERS SHALL BE MADE OF MATERIAL IN WHICH A SEA TURTLE OR SMALLTOOTH SAWFISH CANNOT BECOME ENTANGLED, BE PROPERLY SECURED, AND BE REGULARLY MONITORED TO AVOID PROTECTED SPECIES ENTRAPMENT. BARRIERS MAY NOT BLOCK SEA TURTLE OR SMALLTOOTH SAWFISH ENTRY TO OR EXIT FROM DESIGNATED CRITICAL HABITAT WITHOUT PRIOR AGREEMENT FROM THE NATIONAL MARINE FISHERIES SERVICE'S PROTECTED RESOURCES DIVISION, ST. PETERSBURG, FLORIDA.
- 8.4. ALL VESSELS ASSOCIATED WITH THE CONSTRUCTION PROJECT SHALL OPERATE AT "NO WAKE/IDLE" SPEEDS AT ALL TIMES WHILE IN THE CONSTRUCTION AREA AND WHILE IN WATER DEPTHS WHERE THE DRAFT OF THE VESSEL PROVIDES LESS THAN A FOUR-FOOT CLEARANCE FROM THE BOTTOM. ALL VESSELS WILL PREFERENTIALLY FOLLOW DEEP-WATER ROUTES (E.G., MARKED CHANNELS) WHENEVER POSSIBLE.
- 8.5. IF SEA TURTLE OR SMALLTOOTH SAWFISH IS SEEN WITHIN 100 YARDS OF THE ACTIVE DAILY CONSTRUCTION/DREDGING OPERATION OR VESSEL MOVEMENT, ALL APPROPRIATE PRECAUTIONS SHALL BE IMPLEMENTED TO ENSURE ITS PROTECTION. THESE PRECAUTIONS SHALL INCLUDE CESSATION OF OPERATION OF ANY MOVING EQUIPMENT CLOSER THAN 50 FEET OF A SEA TURTLE OR SMALLTOOTH SAWFISH. OPERATION OF ANY MECHANICAL CONSTRUCTION EQUIPMENT SHALL CEASE IMMEDIATELY IF A SEA TURTLE OR SMALLTOOTH SAWFISH IS SEEN WITHIN A 50-FT RADIUS OF THE EQUIPMENT. ACTIVITIES MAY NOT RESUME UNTIL THE PROTECTED SPECIES HAS DEPARTED THE PROJECT AREA OF ITS OWN VOLITION.
- 3.6. ANY COLLISION WITH AND/OR INJURY TO A SEA TURTLE OR SMALLTOOTH SAWFISH SHALL BE REPORTED IMMEDIATELY TO THE NATIONAL MARINE FISHERIES SERVICE'S PROTECTED RESOURCES DIVISION (727-824-5312) AND THE LOCAL AUTHORIZED SEA TURTLE STRANDING/RESCUE ORGANIZATION.

ENGINEER OF RECORD: KENNETH M GOOD, PE LIC. NO. 61687





JOB No.

BART6907 ä Plotted 8:59am I 2019 90 March Wednesday, Time: Plot ଚ NOTES GENERAL Name: Layout SHEET.dwg COVER Files/CAD/C-0 Pier\Justin C:\Users\BART6907\Documents\Wabasso

Name:


Ele


4.


5.

6.

7.








WEST SECTION

	ID	Description	Position	Weight (TN)	ID	Description	Position	Weight (TN)
-	W-DS01	Concrete Deck Section (25')	In place and intact	12	W-DS07	Concrete Deck Section (50')	In place and intact	25
	W-CP01	Concrete Pile Cap	In place and intact	4	W-CP07		In place and intact	4
	W-PN01	14" Concrete Pile (North)	In place and intact	7	W-PN07	14" Concrete Pile (North)	In place and intact	7
	W-PS01	14" Concrete Pile (South)	In place and intact	7	W-PS07	14" Concrete Pile (South)	In place and intact	7
	W-DS02	Concrete Deck Section (50')	In place and intact	25	W-DS08	Concrete Deck Section (50')	In place and intact	25
	W-CP02	Pile Cap	In place and intact	4	W-CP08	Pile Cap	In place and intact	4
		14" Concrete Pile (North)	In place and intact	7		14" Concrete Pile (North)	In place and intact	7
	W-PS02	14" Concrete Pile (South)	In place and intact	7	W-PS08	14" Concrete Pile (South)	In place and intact	7
		Concrete Deck Section (50')	In place and intact	25		Concrete Deck Section (50')	In place and intact	25
- H		Pile Cap	In place and intact	4	W-CP09		In place and intact	4
		14" Concrete Pile (North)	In place and intact	7		14" Concrete Pile (North)	In place and intact	7
- H		14" Concrete Pile (South)	In place and intact	7		14" Concrete Pile (South)	In place and intact	7
r	W-DS04	Concrete Deck Section (50')	In place and intact	25		Concrete Deck Section (50')	Submerged, upright & intact	25
		Pile Cap	In place and intact	4	W-CP10		In place and intact	4
		14" Concrete Pile (North)	In place and intact	7		14" Concrete Pile (North)	In place and intact	7
	W-PS04	14" Concrete Pile (South)	In place and intact	7		14" Concrete Pile (South)	In place and intact	7
	W-DS05	Concrete Deck Section (50')	In place and intact	25		Concrete Deck Section (50')	Submerged, upright & intact	25
		Pile Cap	In place and intact	4	W-CP11		In place and intact	4
L -		14" Concrete Pile (North)	In place and intact	7	W-PN11	14" Concrete Pile (North)	In place and intact	7
-	W-PS05	14" Concrete Pile (South)	In place and intact	7	W-PS11	14" Concrete Pile (South)	In place and intact	7
		Concrete Deck Section (50')	In place and intact	25	W-SW	158LF Concrete Sidewalk	In place and intact	NA
- H		Pile Cap	In place and intact	4				
- H		14" Concrete Pile (North)	In place and intact	7				
-		14" Concrete Pile (South)	In place and intact	7				
	NOTES	S:						
	1. /	ALL DESCRIPTION SIZE	S ARE APPROXII	MATE A	ND BAS	ED ON INFORMATION II	N THE 2006 REHABILITA	TION
	F	PLANS, CONTRACTOR IS	S RESPONSIBLE	TO VE	RIFY AL	L DIMENSIONS FOR TH	EIR NEEDS.	
						ERVATION MADE BY A D		
						IBLE TO VERIFY THE CL		
					350113	IBLE TO VERIFT THE CO	IRRENT FUSITION AS	
		NECESSARY FOR THEIR						
-	3. /	ALL WEIGHTS WERE ES	TIMATED BASE	D ON IN	FORMA	TION IN THE 2006 REHA	BILITATION PLANS. PIL	E
	١	WEIGHTS ASSUME AN II	NTACT 60' LONG	PILE.	ACTUAL	PILE LENGTH IS NOT K	NOWN. CONTRACTOR	IS
	F	RESPONSIBLE TO VERI	THE ESTIMAT	ED WE	IGHTS A	AS NECESSARY FOR TH	EIR NEEDS.	
-	Λ		WABASSO FISH			ENGINEER OF RECORD: KENNETH M GOOD, PE LIC, NO, 61687	ARIVER COL JOB N 100	lo. 1055899
			DEMOLITION AND D	EBRIS R	EMOVAL	LU. NU. 01007	CAD F	ile
	7475		INDIAN RIVER	COUNT	Y	1		1
		Murrell Road ourne, Florida 32940				1		NUMBER
		242-4942	EXISTING PIER			1	* V-	102
		Certificate of Authorization No. 24	INVENTORY PL	4N —	WEST	1	TORIDA	IUL



E-CP03 Pile Cap

E-CP04 Pile Cap

E-CP05 Pile Cap

E-PN03 14" Concrete Pile (North)

E-PS04 14" Concrete Pile (South)

E-PN05 14" Concrete Pile (North)

E-PS05 14" Concrete Pile (South)

1. ALL DESCRIPTION SIZES ARE APPROXIMATE AND BASED ON INFORMATION IN THE 2006 REHABILITATION PLANS, CONTRACTOR IS RESPONSIBLE TO VERIFY ALL DIMENSIONS FOR THEIR NEEDS.

F-SW

2. SUBMERGED POSITIONS ARE BASED ON VISUAL OBSERVATION MADE BY A DIVER WITH LIMITED VISIBILITY ON 07/20/2017. CONTRACTOR IS RESPONSIBLE TO VERIFY THE CURRENT POSITION AS NECESSARY FOR THEIR NEEDS.

4

7

7

25

4

7

7

25

4

7

7

E-CP08 Pile Cap

E-CP09 Pile Cap

E-CP10 Pile Cap

E-PN08 14" Concrete Pile (North)

E-PS08 14" Concrete Pile (South)

E-PN09 14" Concrete Pile (North)

E-PS09 14" Concrete Pile (South)

E-PN10 14" Concrete Pile (North)

E-PS10 14" Concrete Pile (South)

120LF Concrete Sidewalk

E-DS10 Concrete Deck Section (50')

E-DS09 Concrete Deck Section (50') Submerged, rolled & intact

Submerged, unknown

Submerged, unknown

Submerged, unknown

Submerged, unknown

Submerged, unknown

In place and intact

In place and intact

In place and intact

Submerged, upright & intact

In place and intact

In place and intact

4

7

7

25

4

7

7

25

4

7

7


NA


In place and intact


Submerged, upright & intact


3. ALL WEIGHTS WERE ESTIMATED BASED ON INFORMATION IN THE 2006 REHABILITATION PLANS. PILE WEIGHTS ASSUME AN INTACT 60' LONG PILE. ACTUAL PILE LENGTH IS NOT KNOWN. CONTRACTOR IS RESPONSIBLE TO VERIFY THE ESTIMATED WEIGHTS AS NECESSARY FOR THEIR NEEDS.


ATKINS 7175 Murrell Road Melbourne, Florida 32940	WABASSO FISHING PIER DEMOLITION AND DEBRIS REMOVAL INDIAN RIVER COUNTY EXISTING PIER COMPONENT	ENGINEER OF RECORD: KEINETH M (2000), PE LIC. NO. 61687	THRIVER COUNTY	JOB No. 100055899 CAD FILE 1 SHEET NUMBER
Melbourne, Florida 32940 321-242-4942 FBPR Certificate of Authorization No. 24	EXISTING PIER COMPONENT INVENTORY PLAN – EAST		* ALORIDA	V-103















Map Date: 3/6/2019



LOCATION MAP 1" INCH = 3,000 FEET

SURVEY NOTES:

- GRID COORDINATES SHOWN ARE IN FEET, AND ARE REFERENCED TO THE FLORIDA STATE PLANE COORDINATE SYSTEM, EAST ZONE, NORTH AMERICAN DATUM OF 1983, ADJUSTMENT OF 1990 (NAD 83/90).
- 2. GRID COORDINATES ARE BASED ON MONUMENTS AS SHOWN IN THE CONTROL TABLE.
- 3. ELEVATIONS SHOWN ARE IN FEET AND ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).
- 4. ELEVATIONS ARE BASED ON MONUMENTS AS SHOWN IN THE CONTROL TABLE.
- 5. BATHYMETRIC INFORMATION DEPICTED ON THIS SURVEY REPRESENTS THE EXISTING CONDITIONS ON THE DATE OF THE FIELD SURVEY.
- 6. AERIAL IMAGERY WAS TAKEN IN 2015 BY ACA, INC. AND WAS PROVIDED BY THE FLORIDA DEPARTMENT OF TRANSPORTATION.
- 7. AERIAL IMAGERY IS DISPLAYED HEREON FOR INFORMATION PURPOSES ONLY, NO PHOTOGRAPHIC ACCURACY IS IMPLIED BY THIS MAP.
- 8. NOT VALID WITHOUT THE SIGNATURE AND ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.
- 9. UNDERGROUND UTILITIES AND IMPROVEMENTS NOT LOCATED.



BATHYMETRIC SURVEY INDIAN RIVER CHANNEL WABASSO PIER REMOVAL ROUTE INDIAN RIVER COUNTY, FLORIDA

-FOR-

ATKINS NORTH AMERICA

COMMISSION NO.: 35667-1 DATE: MARCH 27, 2018

PREPARED BY:

Morgan & Eklund Inc.

PROFESSIONAL SURVEY CONSULTANTS




4909 US HIGHWAY #1 VERO BEACH, FL 32967 PHONE: (772) 388–5364 FAX: (772) 388–3165 1612 NW 2D AVENUE SUITE 3 BOCA RATON, FL 33432 PHONE: (954) 421–6882 FAX: (954) 421–0425 LB #4298 SUITE 211 1001 NORTH AMERICAN WAY MIAMI, FL 33132 PHONE: (305) 364–5158

CONTROL TABULATION

	NAD 83/90	SPCS 0901	NAVD 88		
SNATION	NDRTHING	EASTING	ELEVATION	DESCRIPTION	STAMPING
.020	1231002. 76	843541, 55	10. 52	DISK IN CONCRETE MONUMENT	GPS 03 32 39 02 1020 1991
.48	1235024.63	842193, 32	9, 27	DISK IN CONCRETE MONUMENT	GPS 148 1998
200	1231522. 13	847420.47	2. 28	SET IRON ROD AND CAP	LB #4298
201	1231454.82	847446, 76	1, 18	SET IRON ROD AND CAP	LB #4298

VERTICAL DATUM DIAGRAM







SHEET INDEX				
SHEET NO.	DESCRIPTION			
1	COVER SHEET			
2	KEY MAP			
3–12	ELEVATION CONTOURS			
13	ROUTE PROFILE			

FIELD BOOKS: INDIAN RIVER 271, PAGES 1-2

SHEET 1 OF 13





ELEVATIONS	IN FEET (NAVD 88)	
Minimum Elevation	Maximum Elevation	Color
-16	-15	
-15	-14	
-14	-13	
-13	-12	
-12	-11	
-11	-10	
-10	-9	
-9	-8	
-8	-7	
-7	-6	
-6	-5	
-5	-4	
-4	-3	
-3	-2	

37+00

-6.6


-7.5 -7.2 -7.2


> -6.5 -6.6 -6.4

> -6.3

ۄٚ؋ٛ؋


GRAPHIC SCALE 50'






ELEVATIONS	IN FEET (NAVD 88)	
Minimum Elevation	Maximum Elevation	Color
-16	-15	
-15	-14	
-14	-13	
-13	-12	
-12	-11	
-11	-10	
-10	-9	
-9	-8	
-8	-7	
-7	-6	
-6	-5	
-5	-4	
-4	-3	
-3	-2	


	EL	EVATION CONT	OURS (I	NAVD 8	8)	
Y CERTIFY THAT THE INFORMATION ITH A RECENT FIELD SURVEY I IT IS TRUE AND CORRECT TO LIEF, AND MEETS THE STANDARDS		BATHYMETF INDIAN RIVE			,	<i>сомміззіон но</i> . 35667—1
FLORIDA BOARD OF PROFESSIONAL FLORIDA ADMINISTRATIVE CODE, RIDA STATUTES.	W	ABASSO PIER	REMOVA		ΓE	scale AS SHOWN
		- FO ATKINS NOR	DR – Ith Ame	RICA		<i>date</i> 4/2/18
S RVEYOR #3520	drawn by LFP	<i>снескед в</i> ү JRM	FIELD BOOK PAGE NO.	SEE COVER	date of survey 3/27/18	<i>ѕнее</i> т 5 <i>о</i> ғ 13







Con Franker	ELEVATIONS	IN FEET (NAVD 88)	
and the	Minimum Elevation		Color
E State and	-16	-15	
	-15	-14	
man	-14	-13	
	-13	-12	
	-12	-11	
	-11	-10	
	-10	-9	
	-9	-8	
	-8	-7	
	-7	-6	
	-6	-5	
	-5	-4	
	-4	-3	
	-3	-2	


				ELEVATIONS	IN FEET (NAVD 88)	
						Color
				No. of Concession, Name		
				100.0		
				and the second se		
				The second se		
				and the second s		
				and the second se		
				a los l		
				and the second se		
			-3. 4 -3. 6 -3. 7 -4. 0 -4. 2 -4. 4 -4. 6		-4. 3 -4. 4 -4. 6 -4. 7	
	10 10 10 100	100-00 100-00 100-00 100-00	-5.0		-4. 8 -5. 1 -5. 0	
100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+00 100+	32 100 100+00 100+00 100+00 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40	32 100 100+00 100+00 100+00 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40 40	-5. 6 -5. 8		✓ /-5. 4	
41	41	41	-5.9 -5.9		-5.6 -5.2 -5.4	
61 -53 940 940<	61 -53 940 940<	61 -53 940 940<	-6. 2	100+00		
un un 50 un un 100	un un 50 un un 100	un un 50 un un 100	-6.0 -6.1		-4. 5	~ ~
4.2 4.3 4.3 4.3 4.3 4.4 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.6 4.3 4.7	4.2 4.3 4.3 4.3 4.3 4.4 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.6 4.3 4.7	4.2 4.3 4.3 4.3 4.3 4.4 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.5 4.3 4.6 4.3 4.7		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	-4.4 ຠຠຎຠຎຒ 4830 കേക്യയെ ∞	3 8 3 9 9 6
- 6.2 - 1 - 1 - 1 - 6.3 - 5.7 - 6.7 - 7.6 - 7.7 - 7.6 - 7.6 - 6.9 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6	- 6.2 - 1 - 1 - 1 - 6.3 - 5.7 - 6.7 - 7.6 - 7.7 - 7.6 - 7.6 - 6.9 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6	- 6.2 - 1 - 1 - 1 - 6.3 - 5.7 - 6.7 - 7.6 - 7.7 - 7.6 - 7.6 - 6.9 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 6.9 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.7 - 7.6 - 7.7 - 7.6 - 7.6				
			-6.3		-4.0 -3.8 -3.9	
-7.6 -7.6 -7.7 -7.6 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.6 -7.8 -7.7 -7.7 -7.8 -7.7 -7.8 -7.8 -7.8 -7.8 -7.8 -7.7 -7.7 -7.7 -7.8 -7.7 -7.7 -7.7 -7.7 -7.8 -7.0 -7.7 -7.7 -7.8 -7.7 -7.8 -7.0 -7.7 -7.8 -7.0 -7.8 -7.0 -7.9 -7.9 -7.1 -7.4 -7.5 -7.6 -7.1 -7.7 -7.8 -7.1 -7.9 -7.1 -7.2 -7.9 -7.1 -7.2 -7.5 -7.6 -7.1 -7.7 -7.1 -7.2 -7.7 -7.1 -7.2 -7.5 -7.6 -7.1 -7.7 -7.1 -7.2 -7.7 -7.1 -7.2 -7.9 -7.1 -7.2 -7.7 -7.1 -7.2 -7.7 -7.1 -7.2 -7.8 -7.1	-7.6 -7.6 -7.7 -7.6 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.6 -7.6 -7.6 -7.6 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.7 -7.8 -7.8 -7.0 -7.8 -7.0 -7.7 -7.8 -7.7 -7.7 -7.7 -7.8 -7.8 -7.0 -7.9 -7.0 -7.9 -7.1 -7.7 -7.8 -7.7 -7.8 -7.9 -7.1 -7.9 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.8 -7.6 -7.9 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.9 -7.1 -7.9 -7.1 -7.1 -7.2 -7.7 -7.1 -7.8 -	-7.6 -7.6 -7.7 -7.6 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.7 -7.6 -7.6 -7.6 -7.6 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.6 -7.8 -7.7 -7.8 -7.8 -7.0 -7.8 -7.0 -7.7 -7.8 -7.7 -7.7 -7.7 -7.8 -7.8 -7.0 -7.9 -7.0 -7.9 -7.1 -7.7 -7.8 -7.7 -7.8 -7.9 -7.1 -7.9 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.8 -7.6 -7.9 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.7 -7.1 -7.9 -7.1 -7.9 -7.1 -7.1 -7.2 -7.7 -7.1 -7.8 -		L M	-4. 1	
-7.6 -7.6 -7.6 -7.9 -7.7 -7.7 -5.6 -5.6 -5.7 -5.7 -5.7 -5.7 -5.7 -5.7 -5.7 -5.7 -5.7 -5.7 -5.6 -7.7 -7.7 -7.8	-7.6 -7.6 -7.9 -7.9 -7.9 -7.9 -7.9 -5.6 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -7.0 -7.7 -7.8 -8.0 -7.7 -7.8 -7.8 -7.0 -7.7 -7.8 -7.8 -7.8 -7.0 -7.7 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8	-7.6 -7.6 -7.9 -7.9 -7.9 -7.9 -7.9 -5.6 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -8.0 -7.7 -7.8 -7.0 -7.7 -7.8 -8.0 -7.7 -7.8 -7.8 -7.0 -7.7 -7.8 -7.8 -7.8 -7.0 -7.7 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.8 -7.7 -7.8	-7.1 -7.5			~~~
nm - 1/3 1/3 1/4 5.7 nm - 1/3 1/4 5.0 nm - 1/3 1/4 1/4 nm - 1/4 1	nm - 1/3 1/3 1/4 5.7 nm - 1/3 1/4 5.0 nm - 1/3 1/4 1/4 nm - 1/4 1	nm - 1/3 1/3 1/4 5.7 nm - 1/3 1/4 5.0 nm - 1/3 1/4 1/4 nm - 1/4 1		\sim	-4. 8 -5. 0	
-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td>-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td>-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td></td><td></td><td>-5.7 -6.0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</td><td>060 C</td></t<></td></t<></td></t<>	-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td>-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td></td><td></td><td>-5.7 -6.0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</td><td>060 C</td></t<></td></t<>	-5.6 -7.8 -5.2 -7.8 -5.2 -7.8 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.4 -7.0 -5.5 -7.0 -5.9 -7.1 -7.8 -7.4 -7.6 -7.1 -7.7 -7.1 -7.6 -7.1 -7.7 -7.1 <t< td=""><td></td><td></td><td>-5.7 -6.0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0</td><td>060 C</td></t<>			-5.7 -6.0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	060 C
5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7	5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7	5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 5.5 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7 7.7	-6.8 -6.4		-7-0°27	TTY
-5.5 -6.0 -5.5 -7.0 -5.1 -7.0 -5.4 -7.0 -5.5 -7.0 -5.5 -7.0 -5.5 -7.0 -5.5 -7.0 -5.5 -7.2 -7.1 -7.4 -7.5 -7.6 -7.9 -7.1 -7.7 -7.7 -7.7 -7.7 -7.7 -7.0 <t< td=""><td>-5 -6 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -7</td><td>-5 -6 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -7</td><td>· · · · · · · · · · · · · · · · · · ·</td><td></td><td>-7.7 -7.7</td><td></td></t<>	-5 -6 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -7	-5 -6 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -5 -7 -7	· · · · · · · · · · · · · · · · · · ·		-7.7 -7.7	
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	-5.2 -5.5 -5.1			
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{c} -5.1 \\ -5.4 \\ -5.4 \\ -5.5 \\ -5.9 \\ -5.9 \\ -6.9 \\ -7.0 \\ -7.0 \\ -7.2 \\ -7.1 \\ -7.4 \\ -7.4 \\ -7.4 \\ -7.6 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ -7.0 \\ -7.8 \\ -7.6 \\ -7.6 \\ -7.9 \\ -7.1 \\ -7.8 \\ -7.6 \\ -7.6 \\ -7.9 \\ -7.1 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -$	$ \begin{array}{c} -5.1 \\ -5.4 \\ -5.4 \\ -5.5 \\ -5.9 \\ -5.9 \\ -6.9 \\ -7.0 \\ -7.0 \\ -7.2 \\ -7.1 \\ -7.4 \\ -7.4 \\ -7.4 \\ -7.6 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ -7.0 \\ -7.8 \\ -7.6 \\ -7.6 \\ -7.9 \\ -7.1 \\ -7.8 \\ -7.6 \\ -7.6 \\ -7.9 \\ -7.1 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -7.6 \\ -7.8 \\ -$	-5.0		-7.8 -7.7 -7.4	110
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	-5. 1	M	-7.2	
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	-5. 4 -5. 5		-6. 9	
$ \begin{array}{c} -6.8 \\ -7.1 \\ -7.4 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.1 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -$	$ \begin{array}{c} -6.8 \\ -7.1 \\ -7.4 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.1 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -$	$ \begin{array}{c} -6.8 \\ -7.1 \\ -7.4 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.6 \\ -7.1 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -6.8 \\ -6.7 \\ -6.9 \\ -6.8 \\ -$	-5. 9 -6. <u>1</u>		-6. 9	
$ \begin{array}{c} -7.4 \\ -7.5 \\ -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	$ \begin{array}{c} -7.4 \\ -7.5 \\ -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	$ \begin{array}{c} -7.4 \\ -7.5 \\ -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	-6. 5 -6. 8			
$ \begin{array}{c} -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	$ \begin{array}{c} -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	$ \begin{array}{c} -7.8 \\ -7.9 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.7 \\ -7.8 \\ \end{array} $	-7. 4 -7. 5		-7.6	
-7.7 -7.7 -7.7 -7.7 -7.8 -7.8 -7.3 -7.3 -7.2 -7.2 -7.0 -6.9 -7.0 -6.8 -6.8 -6.7 -6.9 -6.9 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0	-7.7 -7.7 -7.7 -7.7 -7.8 -7.8 -7.3 -7.3 -7.2 -7.2 -7.0 -6.9 -7.0 -6.8 -6.8 -6.7 -6.9 -6.9 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0	-7.7 -7.7 -7.7 -7.7 -7.8 -7.8 -7.3 -7.3 -7.2 -7.2 -7.0 -6.9 -7.0 -6.8 -6.8 -6.7 -6.9 -6.9 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0 -7.0	-7. 8 -7. 9		-7. 1 -7. 3	
-7.7 -7.7 -7.7 -7.8 -7.8 -6.9 -6.8 -6.7 -6.9 -6.9 -6.9 -6.7 -6.9 -6.7 -6.9	-7.7 -7.7 -7.7 -7.8 -7.8 -6.9 -6.8 -6.7 -6.9 -6.9 -6.9 -6.7 -6.9 -6.7 -6.9	-7.7 -7.7 -7.7 -7.8 -7.8 -6.9 -6.8 -6.7 -6.9 -6.9 -6.9 -6.7 -6.9 -6.7 -6.9	-7. 7 -7. 7		-7.3 -7.2	<
-6.8 -6.7 -6.9 -6.7 -6.8	-6.8 -6.7 -6.9 -6.7 -6.8	-6.8 -6.7 -6.9 -6.7 -6.8	-7.7		-6. 9	
			-7. 7 -7. 8			
-6. 9 -6. 7 -6. 8 -6. 8 -6. 8 -6. 5 -6. 4 -6. 4	-6.9 -6.7 -6.8 -6.8 -6.8 -6.5 -6.4 -6.4				-6. 8 -6. 7	
-6.8 -6.8 -6.5 -6.5 -6.4 -6.4	-6.8 -6.8 -6.5 -6.4 -6.4				-6. 9 -6. 7 -6. 8	
-5-5-4 -6-4	-5-5-4 -6-4				-6. 8 -6. 8	
					-6. 4 -6. 4	
						i the
						in the second
						- Care
10.	10	10'	10'			
100	100'	100'				
			50 100 E SCALE 50			









the same		
ELEVATIONS	IN FEET (NAVD 88)	
Minimum Elevation	Maximum Elevation	Color
-16	-15	
-15	-14	
-14	-13	
-13	-12	
-12	-11	
-11	-10	
-10	-9	
-9	-8	
-8	-7	
-7	-6	
-6	-5	
-5	-4	
-4	-3	
-3	-2	











Г					\mathcal{P}
		IN FEET (NAVD 88)			
	Minimum Elevation	Maximum Elevation	Color		
	-16	-15			
	-15	-14			J.
	-14	-13			$\mathbf{\nabla}$
	-13 -12	-12 -11			
	-12	-10			
	-10	-9			
	-9	-8		/	
	-8	-7			
	-7	-6			
	-6	-5			
	-5	-4			100
	-4	-3		55	
	-3	-2			-
					in the second se
		A d d d d d d d d d d d d d d d d d d d	μ φ φ φ φ φ φ φ φ φ φ φ φ φ		


		EVATION CONT	0UR\$ (1	NAVD 8	8)	
BY CERTIFY THAT THE INFORMATION WITH A RECENT FIELD SURVEY T IT IS TRUE AND CORRECT TO FLIEF, AND MEETS THE STANDARDS		<i>сомміззіо</i> м <i>мо.</i> 35667—1				
FLORIDA BOARD OF PROFESSIONAL FLORIDA ADMINISTRATIVE CODE, RIDA STATUTES.	W	scale AS SHOWN				
		<i>date</i> 4/2/18				
LS RVEYOR #3520	DRAWN BY	CHECKED BY	FIELD BOOK	SEE	DATE OF SURVEY	<i>ѕнее</i> т 12 <i>о</i> ғ 13
~	LFP	JRM	PAGE NO.	COVER	3/27/18	SHEET IZ OF IJ
















•	154	+00)	1	156	+00)	1	158	+00)	1	160	+00	D 61-	+00

		ROUTE PROFIL	LE (NAV	/D 88)		
BY CERTIFY THAT THE INFORMATION WITH A RECENT FIELD SURVEY AT IT IS TRUE AND CORRECT TO ELIEF, AND MEETS THE STANDARDS		BATHYMETF INDIAN RIVE				<i>сомміззіон но</i> . 35667—1
FLORIDA BOARD OF PROFESSIONAL 7, FLORIDA ADMINISTRATIVE CODE, RIDA STATUTES.	W	scale AS SHOWN				
		<i>date</i> 4/2/18				
PLS JRVEYOR #3520	DRAWN BY	CHECKED BY	FIELD BOOK	SEE	DATE OF SURVEY	<i>ѕнее</i> т 13 <i>о</i> г 13
	LFP	JRM	PAGE NO.	COVER	3/27/18	





	ESTIMATED FISHING WALK QUANTITIES	(Job 88	050-3505)
A NO.	ITEM	UNIT	RUANTITY
	Closs A Concrete (Superstructure)	Cu. Yd.	54
1-4	Class A Concrete (Substructure)	Cu. Yd.	39
1-2	Reinforcing Steel	Los	6700
30-1	Prestressed Tees (Type A)	Lin. Ft.	1897
-30-2	Prestressed. Tees (Type B)	Lin. Ft.	101
.3-1	Procost Concrete Piling Furnisted (14" Sq.) [Prestressed]	Lin.Ft.	1330
4-1	Precost Concrete Piling Driven (14" Sp) (pressressed]	Lin. Ft.	1330
9-11	Untooded Test Piles (Precost Concrete Piling) (14"Sp.) (Prestressed]	Lin.Ft.	160
.55-1	Plike Splices (14").	Each	10
1-1-2	Pipe Handrail (Aluminum)	Lin. Ft.	2013
		<u> </u>	

DESIGN	SPECIFICATIONS	- 1965
CONCR	<u>ETE :</u> -	Ì
	prestressed C	concrete - cla
•	Superstructure	and Substruc
REINE	ORCING : -	Inter
PILES	<u> </u>	14" So
		of 2
BORIN	105 1 -	For

INDIAN RIVER COUNTY DEPARTMENT OF PUBLIC WORKS

CONTRACT PLANS

R 39 E

ω

INDIAN RIVER COUNTY (880051) CR 510 OVER INTRACOSTAL WATERWAY WABASSO FISHING PIERS REHABILITATION


SHEET NO.	SHEET DESCRIPTION
B-1	KEY SHEET
BI-A	TABULATION OF QUANTITIES
BI-I	GENERAL NOTES
B1-2	STRUCTURAL NOTES
81-3	GENERAL PLAN & ELEVATION
B1-4	WEST PIER TYPICAL SECTION, PLAN & ELEVATION
B1-5	WEST PIER BULKHEAD REPAIR DETAILS
BI-6	WEST PIER PILE CAP REPAIR DETAILS
B1-7	WEST PIER BEAM REPAIR DETAILS I
B1-8	WEST PIER BEAM REPAIR DETAILS II
B1-9	WEST PIER DECK REPAIR DETAILS
BI-10	WEST PIER BEAM REPLACEMENT (SPAN 10)
BI-11	WEST PIER JACKING DETAILS
B1-12	EAST PIER DEMOLITION LIMITS
BI-13	EAST PIER NEW TYPICAL SECTION, PLAN & ELEVATION
BI-14 BI-15	EAST PIER NEW PILE CAP AND ABUTMENT MODIFICATION EAST PIER NEW DECK SLAB REINFORCING
BI-15	BAR LIST
BI-17	TYPICAL INVERTED-T BEAM DETAILS AND NOTES INDEX NO. 310
BI-18	INVERTED T BEAM - STANDARD DETAILS INDEX NO. 320
BI-19	INVERTED -T BEAM - TABLE OF BEAM VARIABLES INDEX NO. S-321
BI-20	STANDARD BAR BENDING DETAILS INDEX NO. 1300
BI-21	GENERAL ELECTRIC PLAN
BI-22	CONDUIT DETAILS
BI-23	LOAD CENTER DETAILS

INDEX OF FISHING PIER REHABILITATION

GOVERNING STANDARDS & SPECIFICATIONS. FLORIDA DEPARTMENT OF TRANSPORTATION, ROADWAY AND TRAFFIC DESIGN STANDARDS DATED JANUARY 2006 AND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION DATED 2004, AS AMENDED BY CONTRACT DOCUMENTS.


APPLICABLE DESIGN STANDARDS MODIFICATIONS 1-1-06

FOR DESIGN STANDARDS MODIFICATIONS CLICK ON "DESIGN STANDARDS" AT THE FOLLOWING WEBSITE. HTTP://WWW.DOT.STATE.FL.US/RDDESIGN



PROJECT MANAGER: CLIFFORD J. SUTHARD, P.E.

R 39 E



ROADWAY

31

32

REVISIONS

ITEM ND.	ITEM	UNIT	QUANTITY
101 - 1	Mobilization	LS	1.00
102 - 1	Maintenance Df Traffic	LS	1.00
102 - 74	Barricade (Temporary) (Type III)	ED	120.00
104 - 11	Turbidity Barrier Floating	LF	2340.00
110 - 3	Removal Df Existing Structures	LS/SF	4432.00
400 - 4	Concrete Class IV (Superstructure)	СҮ	123.66
400 - 4	Concrete Class IV (Substructure)	СҮ	21.70
400 - 134	Epoxy Material	GA	18.00
400 - 135	Inject And Seal Cracks	LF	31.00
400 - 143	Concrete Surfaces Cleaning And Coating	SF	17,836.00
400 - 153	Non-Shrinking Grout	CF	3.00
401 - 70	Restore Spalled Areas (Epoxy)	CF	70.00
413 - 149	Penetrant Sealer	GA	50.00
415 - 1	Reinforcing Steel (Superstructure)	LB	20,107.00
415 - 1	Reinforcing Steel (Substructure)	LB	4132.00
450 - 1	Prestressed Beams (Inverted T)	LF	1002.00
515 - 2	Pipe Handrail (Reinstall)	LF	1113.00
715 - 1	Conductors (F&I) (Insulated) (No 10)	LF	4479.00
715 - 1	Conductors (Remove)	LF	4479.00
715 - 2	Conduit (F&I – Underground) (PVC SCH 40) (3/4")	LF	410.00
715 - 2	Conduit (F&I – Surface Mount) (RGS) (3/4'')	LF	550.00
715 - 2	Conduit (F&I – Surface Mount) (FMC) (3/4")	LF	33.00
715 - 2	Conduit (F&I – Embedded) (RGS) (3/4")	LF	500.00
715 - 2	Conduit (Remove)	LF	550.00
715 - 7	Load Center (F&I) (Secondary Voltage)	ΕA	2.00
715 - 7	Load Center (Remove) (Secondary Voltage)	ΕA	2.00
715 - 11	Luminaire (F&I) (Curb Mount) (Special)	EA	11.00
715 - 11	Luminaire (F&I) (Curb Embedded) (Special)	ΕA	19.00
715 - 11	Luminaire (Remove) (Curb Mount) (Special)	EA	11.00
715 - 14	PullBox (F&I) (Roadside)	ΕA	3.00
715 - 14	PullBox (F&I) (Embedded)	ΕA	1.00
715 - 14	PullBox (F&I) (Surface Mount)	EA	12.00
715 - 14	PullBox (Remove) (Surface Mount)	EA	24.00
999 - 25	Initial Contingeny Amount	LS	1.00

102-1	Includes the cost to furnish Fishing Pier Closed sign an required traffic controlscheme during the construction
110-3	Includes the cost to remove and dispose of the entire prestressed beams and diaphragm) and substructure (p the partial removal of West Pier superstructure (prestres of Span 10.
400–4 (Superstructure)	Includes the cost of preparation, labor and materials to diaphragm,concrete sidewalk modifications and miscellar
400–4 (Substructure)	Includes the cost of preparation, labor and materials to and new concrete shear blocks.
400-153	Includes the cost of labor and materials to repair unde
401-70	Includes the cost of labor and materials to repair spall. deck, prestressed beams and diaphragms) and substruc
415−1 (Superstructure)	Includes the cost of labor and materials to install the r diaphragms.
415–1 (Substructure)	Includes the cost of labor and materials to install the r and diaphragms.

PAY ITEM NOTES

CESAR GRANADOS 1-16-07

						L HAVES	D.1704	4-10-2 1	,	<u></u>	and the second	SHEET TITLE.
DATE	8Y	DATE	BY	DESCRIPTION	DRAWN BY	AKB	DATES 8/06	ENGINEER OF RECORD. HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	
					CHECKED BY DESIGNED BY	CG CG		1000 SAWGRASS CORPORATE PKWY SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	-
					CHECKED BY	TJN	8/06 8/06	a 1 ET 00000	CR 510	INDIAN RIVER		- PROJECT NAME
					APPROVED BY	T.J. No	les, P.E.	Certificate of Authorization #171		TNDTAN KIVEK		

Angelina Bains

8/28/2006

and to implement any on phase.

re East Pier superstructure (deck, railing, curb, (pile caps and pile extension). It also includes essed beam, deck, curb, diaphragm and railing)

to provide new concrete curb, concrete deck, aneous concrete work.

to provide new concrete pile cap, pile extension

dermine Sidewalk at west pier.

alls at west pier superstructure (abutment, curb, ucture (shear blocks, pile caps and piles).

reinforcing for the new concrete curb, deck and

reinforcing for the new concrete pile, pile extension

		e official record of this sheet is the electroni
TABULATION OF QUANTITIES		: THE
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	NDTICE:
WABASSO FISHING PIER REPAIRS 2:35:24 PM G: 2418 Wabasso Fishing Pier Find New SvCostEstimite.dgn	BI-A	2

9 TLE U U

GENERAL NOTES:

1. GENERAL SPECIFICATIONS

FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR RDAD AND BRIDGE CONSTRUCTION (DATED 2004), AS AMENDED BY CONTRACT DOCUMENTS.

2. DESIGN SPECIFICATIONS

A. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTD) LRFD BRIDGE DESIGN SPECIFICATIONS (THIRD EDITION) AND APPROVED INTERIMS AS SPECIFIED IN THE STRUCTURES DESIGN GUIDELINES.

B. FDAT STRUCTURES DESIGN GUIDELINES JULY 2006.

C. FDOT ROADWAY AND TRAFFIC DESIGN STANDARDS, JANUARY 2006 EDITION, AS AMENDED AND MUTCD 2003 EDITION.

3. ENVIRONMENT

SUPERSTRUCTURE - EXTREMELY AGGRESSIVE SUBSTRUCTURE - CONCRETE: EXTREMELY AGGRESSIVE STEEL: EXTREMELY AGGRESSIVE

4. FIELD VERIFICATION AND CONDITIONS

DIMENSIONS SHOWN IN THE CONTRACT PLANS WERE OBTAINED FROM FIELD OBSERVATIONS, AND ARE INTENDED FOR INFORMATION AND ESTIMATING PURPOSES ONLY. FIELD VERIFY ALL DIMENSIONS AND CONDITIONS REQUIRED TO PERFORM THE REPAIRS. FAILURE TO FIELD VERIFY DIMENSIONS WILL NOT BE JUSTIFICATION FOR CLAIMS. IF ANY DISCREPANCIES ARE FOUND, IMMEDIATELY NOTIFY THE ENGINEER.

5. EROSION CONTROL

COMPLY WITH FOOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SECTION 104 "PREVENTION, CONTROL, AND ABATEMENT OF EROSION AND WATER POLLUTION". COMPLY AS WELL TO STATE, FEDERAL AND LOCAL LAWS, STATUTES AND ORDINANCES.

THE CONTRACTOR MUST PROVIDE MEANS TO PREVENT REMOVED MATERIAL FROM FALLING OR ENTERING THE WATERWAY.

6. MANATEE SIGN NOTE

THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 4 MANATEE AWARENESS SIGNS, POST MOUNTED AT EACH QUADRANT OF THE FISHING PIER. COUNTY PERSONNEL WILL GIVE INSTRUCTIONS ON EXACT LOCATION AND TYPE OF MOUNTING REQUIRED AT THE PRE-CONSTRUCTION MEETING. IN ADDITION, THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING MANATEE AWARENESS SIGNS ON ALL MOTORIZED VESSELS. INCLUDING BARGES WHICH ARE SUPPORTING DRIVING EQUIPMENT. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN SAID SIGNS FOR THE DURATION OF THE PROJECT. ALL COST ASSOCIATED WITH MANATEE SIGNS IS TO BE INCLUDED UNDER MOBILIZATION COST.

7. PROTECTION OF SURVEY MONUMENTS:

ANY PUBLIC LAND CORNER WITHIN THE LIMITS OF CONSTRUCTION IS TO BE PROTECTED. IF A CORNER MONUMENT IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED. THE ENGINEER SHOULD NOTIFY THE COUNTY.

8. MAINTENANCE OF TRAFFIC:

PROVIDE INFORMATION SIGN TO PUBLIC AND PROVIDE TYPE III BARRICADE TO CLOSE PIER. PAID FOR UNDER MAINTENANCE OF TRAFFIC.

9. NAVIGABLE WATERWAY:

AT NO TIME DURING THE REPAIRS WILL THE WATERWAY BE CLOSED TO NAVIGATION. LOCAL MARINE TRAFFIC CONSISTS OF SMALL RECREATIONAL BOATS FROM ADJACENT RESIDENCES AND BUSINESSES.

10. NOISE ORDINANCE:

CONTRACTOR SHALL COMPLY WITH LOCAL NOISE ORDINANCES.

11. INSPECTION:

THE CONTRACTOR SHALL PROVIDE SAFE ACCESS FOR THE ENGINEER AT ALL TIMES TO INSPECT ALL ASPECTS OF THE PROJECT. THIS INCLUDES (BUT IS NOT LIMITED TO) SCAFFOLDING, INSPECTION BOAT, SAFETY BOAT, MANLIFTS AND OTHER EQUIPMENT REQUIRED TO PROVIDE SAFE ACCESS FOR THE ENGINEER TO PERFORM ALL NECESSARY INSPECTIONS.

12. UTILITIES:

EXISTING UNDERGROUND AND ABOVE GROUND UTILITIES WITHIN THE CONSTRUCTION ZONE MAY NOT BE SHOWN ON THE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND AVOIDING ALL UTILITIES. BEFORE BEGINNING OF WORK CONTACT SUNSHINE ONE CALL FOR LOCATION OF EXISTING UTILITIES AT (800) 432-4770.


THE FOLLOWING UTILITIES EXIST OR MAY EXIST IN THE PROJECT VICINITY:


INDIAN RIVER COUNTY UTILITIES: 1840 25th STREET VERD BEACH, FL 32960 ATTN: MR. BILL McCAIN (561) 770-5325

BELL SOUTH: 3300 DKEECHDBEE RDAD FT. PIERCE, FL 34947 ATTN: MR. RONNIE LUTRELL (561) 562-1618

FLORIDA POWER & LIGHT: 810 CHARLOTTE AVENUE WEST PALM BEACH. FL 33401 ATTN: MR. LEDNARD CHIDCCA (561) 616-1618

COMCAST: 2501 SW 145 AVENUE MIRAMAR, FL 33027 ATTN: LEONARD MAXWEL (954) 444-5113





CERIZ GANADOS

A-16-07

		RE	VISIONS			NAMES DATES	ENGINEER OF RECORD.				SHEET TITLE.
DATE	BY	DESCRIPTION	DATE BY	DESCRIPTION	DRAWN BY	AKB 8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	1
					CHECKED BY	CG 8/06	1000 SAWGRASS CORPORATE PKWY				4
1					DESIGNED BY	CG 8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:
					CHECKED BY	TJN 8/06	Sunrise, FL 33323				
					APPROVED BY		Cesar A. Granados, P.E #64221 Certificate of Authorization #171	CR 510	INDIAN RIVER		
				ومعادية المحادث والمتحدين والمتحدين والمتحد والمتحد والمتحد والمتحد والمتحد	Lange and the second	1	Continuate of Authorization with	L		8 (08 (10000 0

Anaelina Bain

G: 2418_Wabasso Fishing Pler Find New S GeneralNotes.dgi 2:53:56 PM

STRUCTURAL NOTES:

1. DESIGN LOADS:			7. MATERIALS:		8. ALLOWABLE STRESSES REFERENCED DESIGN S
DEAD LOAD:	THE FOLLOWING UNIT LOADS SHALL BE USED IN CALCULATING DEAD LO		A. EPDXY MORTAR: ALL EPDXY MORTAR S FOOT STANDARD SPECIFICATIONS SU		SHOWN ON THE PLANS 9. EXISTING ELEMENTS T
	STRUCTURAL STEEL – 490 pcf REINFORCED CONCRETE – 150 pcf ALUMINUM – 165 pcf		B. REINFORCING STEEL: ALL REINFORCING UNCOATED ASTM A615 GRADE 60.	G STEEL SHALL BE	9. EXISTING ELEMENTS T EXERCISE SPECIAL THE STRUCTURE TH
2. DESIGN METHO			CONCRETE COVERS SHALL BE AS FOL SUPERSTRUCTURE:): REINFORCING. REP. THE ENGINEER, AN ARE DAMAGED DUR.
REINFORCE	D CONCRETE: LOAD AND RESISTANCE	FACTOR DESIGN	PRE- STRESSED BEAMS: TOP DECK SURFACE: ALL OTHER SURFACES:	2" 2!/ ₂ " 2"	COST TO THE COU
3. THERMAL FORC	ES:		SUBSTRUCTURE:		10. DIMENSIONS:
TEMPERAT	VARIATION: 'URE RANGE FOR DESIGN OF STRUCTO 'URE RISE = 30° F 'URE FALL = 40° F	JRE:	EXTERNAL FORMED SURFACES, PILE C SHEAR BLOCKS AND PILE EXTENSION NOT IN CONTACT WITH WATER:	'S 4"	SHALL BE SOLELY
	PERATURE = 70° F DEFFICIENT = 0.000006 PER DEGRE	E F	CONCRETE COVER SHOWN IN THE PL REINFORCEMENT PLACEMENT AND FAU UNLESS SHOWN AS "MINIMUM COVER FOR ALLOWABLE REINFORCEMENT PLA	BRICATION TOLERANCES ". SEE SPECIFICATIONS	WORK TO PROPERL
4. CREEP AND SH	RINKAGE:		C. PRESTRESSING STEEL: ALL PRE -STR	ESSING STEEL SHALL BE	
	AS PER AASHTD. NCRETE SHRINKAGE CDEFFICIENT =	0.0004 IN/IN	STRAND ASTM A416 GRADE 270, LOW	RELAXATION.	
	E FORMS ARE NOT PERMITTED DUE ENVIRONMENT.	TO EXTREMELY	PRESTRESSING PARAMETERS (STRAND APPARENT MODULUS: 28,000 ksi MAXIMUM JACKING STRESS: 216 ksi(
6. ALLOWABLE ST	RESSES/LOADS:		MAXIMUM ANCHORING STRESS AT AN 202 ksi(75% ULTIMATE)FOR PRETEN	CHOR:	
REINFORCED	CONCRETE: AS PER AASHTO.		STRAND DIAMETER: 0.60"		
PRESTRESSED			CONTRACTOR SHALL NOT RELEASE PI STRENGTH HAS BEEN ACHIEVED AS	SHOWN BY THE RESULTS OF THE	
	STRENGTH AT TRANSFER, f'ci= 0.8 STRENGTH AT 28 DAYS, f'c =	^r c = 6.8 ksi 8.5 ksi	TEST CYLINDERS AND APPROVED BY D. CONCRETE: (28 DAY CYLINDER STREN		
A. TEMPORARY	' STRESSES BEFORE LOSSES:		PRE- STRESSED CONCRETE BEAMS (
		= 4.08 ksi			
	(WITHOUT BONDED REINFORCEMENT) = (WITH BONDED REINFORCEMENT) =		CLASS VI f'c = 8,500 psi		
	IMIT STATES AFTER LOSSES, FULLY		CAST-IN-PLACE SUPERSTRUCTURE (L CURB)	BRIDGE DECK, DIAPHRAGMS,	
	FFECTIVE PRESTRESS AND IT LOADS =	0.45f'c (3.82 ksi)	CLASS IV f'c = 5500 psi		
DUE TO L	L AND 1/2 THE SUM OF EFFECTIVE		CAST-IN-PLACE SUBSTRUCTURE (PIL AND PILE CAPS)	.E EXTENSION	
PRESTRES	SING AND PERMANENT LOADS =	0.40f'c (3.40 ksi)	CLASS IV f'c = 5500 psi		
TRANSIEN	PRESTRESS, PERMANENT AND T/LIVE LOAD = (UNI ESS OTHERWISE NOTED)	0.6f'c (5.10 ksi) 0.280 ksi	E. MAXIMUM AGGREGATE SIZE FOR PREC	AST MEMBERS =¾"	
TENSIUN	(UNLESS OTHERWISE NOTED)	0.200 KSI	F. PROVIDE "%" CHAMFERS ON ALL EXPO OTHERWISE NOTED).	SED EDGES (UNLESS	

					i	·							
						-			62502 GRANAS 4-16-07	2.20			
DATE	ВҮ	SHEET TITLE, RI DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY CHECKED BY	NAMES AKB	8/06	IIIIKDIDI I G IIIKI(O TEKT SDA		VER COUNTY PUBLIC	WORKS DEPARTMENT	•
						DESIGNED BY	CG CG	8/06 8/06	1000 SAWGRASS CORPORATE PKWY SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME
						CHECKED BY	TJN	8/06 8/06 les, P.E.	Sunrise, FL 33323 Cesar A. Granados, P.E. #64221 Certificate of Authorization #171	CR 510	INDIAN RIVER		
L								1			\$USER\$	\$DATE	<u>-</u> \$\$\$

SES ARE IN ACCORDANCE WITH THE IN SPECIFICATIONS FOR ALL MATERIAL ANS.

S TO REPAIR:

TAL CARE NOT TO DAMAGE ANY ELEMENTS OF THAT ARE TO REMAIN, INCLUDING EXISTING REPAIR OR REPLACE, TO THE SATISFACTION OF ANY ELEMENTS THAT ARE TO REMAIN, WHICH DURING CONSTRUCTION AT NO ADDITIONAL COUNTY.

MENSION AND ELEVATIONS WITHIN THESE PLANS STRUCTION AND REPAIRS. IF ANY DISCREPANCIES ARE ATELY NOTIFY THE ENGINEER. THE CONTRACTOR FLY RESPONSIBLE FOR FABRICATION AND FIT OF HIS FERLY INTERFACE WITH THE EXISTING STRUCTURE.

61615-

RULE

UNDER

SEALED

AND


SIGNED


FILE

ELECTRONIC

SHEET IS THE

		THIS
		Р
		RECORD
		DFFICIAL
STRUCTURAL NOTES		THE
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	NDTICE:
WABASSO FISHING PIER REPAIRS	BI -2	<u></u>
\$TIME\$ \$FILE\$		-






TYPICAL CRACK REPAIR DETAIL

.

۰,

77

(For Cracks Between 1/25" to $\frac{1}{2}$ ")




Cracks between 1/25" and $\frac{1}{2}$ " shall be "veed" out to a depth of at least 1/4" prior to drilling. Voids greater than 1/4" wide by 1/4" deep shall be patched with epoxy repair paste.

STEP A

Clean out crack with hand tools, high pressure air blast, or vacuum clean surface.

STEP B


Drill holes for ports to a width and depth sufficient to assure a snug fit of the port. Clean out debris with high pressure air blasting. Insert ports and seal surface of crack with epoxy repair paste. Seal shall extend above concrete surface a minimum of $\frac{1}{16}$ " and extend a minimum of 1" to either side of crack. Allow a minimum of 6 hours curing before initiating injection process.



1/2"

STEP C

Inject epoxy polysulfide grout as detailed in the Specifications. Allow minimum of 6 hours curing time. Remove ports and grind surface smooth to remove a minimum amount of epoxy paste and sealer and to the satisfaction of the engineer.



DESCRIPTION

DATE BY


Space ports as detailed in the Specification. Epoxy injection starts at lower end of vertical crack and proceed upward to end of crack, or until thickness of crack decreases to less than 1/25". Patch beam stem with epoxy repair mortar to original lines.


Cource te Sawcut Line (TYp.) Existing Crack	
TYPICAL CRACK REPAIR – CHASE AND F (For cracks wider than $\frac{1}{2}$ ")	PATCH Repair Spalls as Indicated On This Sheet
Front Face of Concrete Sawcut Line Dutline of	
<u>SECTION A-A</u> Not to Scale	
CRACK REPAIR NDTE: Concrete shall be cut along cracks to form a chase Chased area shall be cleaned by sandblasting before thin coat of cement paste or 1:1 mortar. Fill approved patching material. Repair Undermining ~	applying
Existing Sidewalk Fill Void with Concrete Grout	Existing Fish Pier
	Repair Spalls of Indicated On T Sheet
SIDEWALK UNDERMINING DETAIL	WEST_BULKHEAD_PLAN

Crack	Location	Defi	ciencies	R	?emarks		
	Bulkhead–South End 10'x	1'x8'' Spall	E>	xposed an	d Corroded Reb	par	
	Bulkhead–North End 20'x	(2'x1' Spall – 3	Significant Section Loss Ex	xposed an	d Corroded Reb	oar NDTE: SEE S	SPALL RE
			CE 547 GRAVADE 4-16-07	52			
DATE BY DESCRIPTION	DRAWN BY	IAMES DATES AKB 8/06 CG 8/06	Intellet i de Intello v Eko Ebi	INDIAN RIV	ER COUNTY PUBLIC	C WORKS DEPARTMENT	SHEET TITLE
		CG 8/06	1000 SAWGRASS CORPORATE PKWY SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME
		TJN 8/06 T.J. Noles, P.E.	Sunrise, FL 33323 Cesar A. Granados, P.E #64221 Certificate of Authorization #171		INDIAN RIVER		

\$DATE\$

.






DEFICIENCIES								
ciencies	Remarks							
f Bottom Face	Bleeding							
ace								
f SW Corner								
rner								
of Cap-15% Section Loss	Exposed and Corroded Rebar							
of Cap-20% Section Loss	Exposed and Corroded Rebar							
of Cap-20% Section Loss	Exposed and Corroded Rebar							
of Cap	Bleeding							
Corner	Exposed and Corroded Rebar							
E Corner	Exposed and Corroded Rebar							
ce								
of East Face	Exposed and Corroded Rebar							
of NE Corner	Bleeding							
er								

BRIDO		FICL
WEST PIER PILE CAP REPAIR DETAILS		: THE OF
"CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	ICE:
WABASSO FISHING PIER REPAIRS	BI-6	עם
\$TIME\$		

	TABLE OF DEFICIENCIES	
Location	Deficiencies	Remarks
SPAN NO.1		
Beam 1–West End	1'-10½" x 8" Deterioration	Exposed and Corroded Reba
Beam 2	2'x9"x2" Spall of Bottom Face of Flange	Bleeding
SPAN NO. 2		
Beam 1	10'Long Crack up to 1" Wide	
Beam 1	Minor Spall of Bottom Face of Stem	
Beam 1	10'x1' Delamination with 1/4" Crack in Bottom Face	
End Diaphragm	3'x1'x6'' Spall of East Face	
Beam 2	6"x3"x1" Spall of Bottom Face of Stem	
End Diaphragm	2'x8"x6" Spall	
SPAN NO. 3		
Beam 1	8"x8"x1" Spall of Bottom Face of Stem	Exposed and Corroded Reba
Beam 1	8"x5"x1" Spall of Bottom Face of Stem	Exposed and Corroded Reba
Beam 1	6"x4"x1" Spalls (3) of Bottom Face of Stem	Exposed and Corroded Reba
Beam 2	8"x8"x1" Spall of Bottom Face of Stem	
Beam 2	3"x4" Spall of Dutside Face of Stem	
Beam 2	8"x4"x1" Spall of Dutside Face of Stem	
Beam 2	1'Long Delamination	
SPAN NO. 4		
Beam 1	8"x4"x1" Spall of Bottom Face of Stem	Exposed and Corroded Reba
Beam 1	4"x4"x1" of Bottom Face of Stem	Exposed and Corroded Reba
Beam 1	12'Long Crack up to 1/4" Wide	
Beam 1	1/4 Span Length x 8" Delaminated Patch with 1/4" Crack	<
Beam 2	Bleeding and Cracks up to 1/4"	
SPAN ND. 5		
	2'x8/ ₂ "x2" Spall of Bottom Face of Stem	Exposed and Corroded Rebo
Beam 1	6"x6" Spall of Bottom Face of Flange	Exposed and Corroded Rebo
Beam 1	(2) Small Spalls at Bottom Face of Flange	Exposed and Corroded Rebo
Beam 2	6"x3"x1" Spall of Dutside Face of Flange	Exposed and Corroded Rebo
SPAN ND. 6		
	8"x6"x4" Spall of Bottom Face	Exposed and Corroded Rebo
Beam 1	(2) 5"x2" Spalls at Bottom Face of Flange	Exposed and Corroded Rebo
Beam 1	Span Length Longitudinal Cracking	Corrosion Staining
Beam 2	Staining, Bleeding and Cracks	
Beam 2	6" Long Delamination	Staining
SPAN NO. 7		
Beam 1	(2) 2'Long Delaminations of Inside Corner of Flange	
Beam 1	5'x1'-6''x7'' Spall of Dutside Face of Flange	Exposed and Corroded Rebo
Beam 1	7'Long Delamination of Bottom Face of Stem	·
Beam 1	Large Crack	
Beam 1	2'x1'-6''x3'' Spall of Bottom Face of Flange	Exposed and Corroded Rebo
Beam 2	(4) 6"x6" Spalls of Bottom Face of Stem	Exposed and Corroded Rebo
Beam 1	3"x4" Spall of Bottom Face of Stem	Exposed and Corroded Rebo

	TABLE OF DEFICIENCIES	
Location	Deficiencies	Remarks
SPAN NO. 8		
End Diaphragm	Up to 40% Section Loss at Support	
SPAN NO. 9		
Beam 1	14" x Stem Width x 4" Spall of Dutside Face	Exposed and Corroded Rebar
Beam 1	1'-6''x8'' Spall Near Midspan	Exposed and Corroded Rebar
Beam 2	9"x7"x2" Spall of Bottom Face of Flange	Exposed and Corroded Rebar
Beam 2	7"x7"x1" Spall of Outside Face of Stem	Exposed and Corroded Rebar
Beam 2	Stem Width x 8" Spall of Bottom Face of Stem	Exposed and Corroded Rebar
Beam 2	1/2Stem Width x 12" Spall of Bottom Face of Stem	Exposed and Corroded Rebar
SPAN ND. 10		
Beam 1	1/3 Span Length x 4" Spall and Delamination	Exposed and Heavily Corroded Rebai
Beam 1	1'x6''x4'' Spall of Stem at Support	Exposed and Corroded Rebar
Beam 2	2'x6" Spall of Dutside Corner of Flange	Exposed and Corroded Rebar
Beam 2	1'x6" Spall of Dutside Corner of Flange	Exposed and Corroded Rebar
End Diaphragm	8"x4"x2" Spall of East Face	
SPAN NO. 11		
Beam 1	8"x4" Spall of Inside Corner of Stem	Exposed and Corroded Rebar
Beam 1	2'x2''x4'' Spall of Bottom Face of Deck	
Beam 1	3"x3" Spall of Dutside Face of Flange	
Beam 1	5"x3"x1" Spall of Bottom Face of Flange	Exposed and Corroded Rebar



<u>T-BEAM SECTION</u>

NOTES:

joint.

CESA	R-Gi	ZINA	ses	ł
	4-16	07		


									4-10-01				
	TRAFFIC TO A CONTRACT OF T		REVISIO	DNS			NAMES	DATES	ENGINEER OF RECORD.	[SHEET TITLE.
DATE	ВҮ	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	1
						CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY	L			4
1						DESIGNED BY	CG	8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME
						CHECKED BY	TJN	8/06	Sunrise, FL 33323				
				1		APPROVED BY			- Cesar A. Granados, P.E #64221 Certificate of Authorization #171		INDIAN RIVER		
										and the second second	+USE0+	\$DATE	°¢ \$

\$USER\$

\$DATE\$

S 1. There are other small cracks and delaminations in the beams at various locations 2. There is bleeding on the outside face of the flanges at every deck 3. Replace Beam 1, Span 10 due to extensive damage (see sheet no. B1–10). BRIDGE ND. 880051 WEST PIER BEAM REPAIR DETAILS I SHEET NO. CR 510 OVER INTRACOASTAL WATERWAY WABASSO FISHING PIER REPAIRS BI -7

\$TIME\$ \$FILE\$



			RE	VISIO	SNC		1	NAMES	DATES	ENGINEER OF RECORD.				SHEET TITLE.
DAT	E	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	
							CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY				-
							DESIGNED BY	CG	8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME.
1							CHECKED BY	TJN	8/06	Sunrise, FL 33323 Cesar A. Granados, P.E #64221	00 510	INDIAN RIVER		
							APPROVED BY	T.J. Nol	les, P.E.	Certificate of Authorization #171	CR 510			
												AUCERA	\$DATE	* *

4x4-W2.9x2.9 Galvanized Wire Fabric Tied to Anchor Bolt 1#3 Adhesive Hook Anchor Set in Epoxy (2" Min. Embedment)

Replace Spalled Area with Epoxy Mortar

CONCRETE RESTORATION PROCEDURE (SPALLS)

1.Sawcut $1'_{2}$ " along perimeter of area to be restored.

2.Remove all unsound concrete within the sawcut limits by chipping to sound concrete. Any reinforcing steel that is damaged is to be repaired at no cost to the Indian River County.

3.Sandblast the exposed concrete surfaces and any reinforcing steel to remove all bond-inhibiting materials.

4. Provide an aggregate-fracture surface with a minimum surface profile amplitude of l_{16} " by use of scrabbler or other appropriate means as necessary.

5. Apply an approved epoxy coating to all existing reinforcing steel. (Cost to be included in the unit price for restoring spalled areas).

6. When the depth of concrete removal exceeds 2", install galvanized wire fabric and adhesive hook anchors.

7.Wet exposed concrete surfaces with clean fresh water: substrate shall be saturated, surface dry.


8. Apply an epoxy-bonding agent to the exposed concrete surfaces.

9.Place epoxy repair mortar. Match repair mortar surface to surrounding concrete surfaces. Provide "V" groove construction joints to match any existing.

11. For location of deficiencies see table on Sheet No. B1-7.

BRIDGE N	0. 880051
WEST PIER BEAM REPAIR DETAILS II	
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.
WABASSO FISHING PIER REPAIRS	B1 -8
\$TIME\$ \$FILE\$	

	TABLE OF DEFICIENCIES	
Location	Deficiencies	Remarks
SPAN NO. 1		
Post No. 1	Cracks on North and South Curb	
Drainage Hole	Cracks on North and South Curb Between Posts	
Drainage Hole	Cracks on South Curb Beyond Post No. 3	Previously Repaired
Post No. 4	Cracks in South Curb Near Post No. 4	
Joint	Up to 1/8" Cracks on Deck at North and South Sides	
SPAN NO. 2		
Post No. 1	Cracks on South Curb	
Post No. 5	Delamination on Inside Face of South Curb	
Post No. 7	Delamination on Inside Face of South Curb	
Joint	Cracks on Deck at North and South Sides	
SPAN NO. 3		
Post No. 1	Crack on South Side Near Post No. 1	Previously Repaired
Post No. 3	3"x3" Spall of Top Face of South Curb	
Joint	Cracks on Deck at North and South Sides	
SPAN NO. 4		
Post No. 1	Crack on South Side Near Post No. 1	Previously Repaired
Joint	Rust Stains	
Post No.8	Crack on North Curb	
SPAN NO. 5		
Joint	Cracks on Deck at North and South Sides	
Joint	Crack on North Curb Near Joint	
SPAN ND. 6		
Joint-Span No. 5 and 6	Cracks Across Deck	
Post No. 8	Crack on North Curb Near Last Post	
Joint-Span No. 6 and 7	Bleeding Crack on North Curb Near Joint	
SPAN ND. 7		
Post No. 3	Cracks Across Deck	
Joint–Span No. 7 and 8	Cracks and Spalling	
Joint-Span No. 6 and 7		
SPAN NO. 9		
Joint-Span No. 9 and 10	D Rust, Cracks, and Spalls	
Drainage Hole	Crack on North Curb Near Last Drainage Hole	
SPAN NO. 10		
Post No. 1	Crack on South Curb	
SPAN ND. 11		
North Curb	Chipping Along East Half of Span	



<u>TYPICAL CONCRETE DECK REPAIR</u> (Railing Not Shown for Clarity)

NOTES:

1. Cracks are up to 1/16" wide.

2. Posts are numbered from west to east per span.

3. Drainage holes lie halfway between posts.

4. Span No. 8 is in good condition.

GESLE	CRANAD	29
4-1	6-07	

									· ·				
		REV	ISIC	NS			NAMES	DATES	ENGINEER OF RECORD.				SHEET TITLE.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RIV	VER COUNTY PUBLIC	WORKS DEPARTMENT	
						CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY				
					•	DESIGNED BY	CG	8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME
						CHECKED BY	TJN	8/06	Sunrise, FL 33323				C
	·			}					Uesar A. Granados, P.E. #04221		INDIAN RIVER		
						APPROVED BY	T.J. Nole	es, P.E.	Certificate of Authorization #171				
											\$USER\$	\$DATE	\$ \$T IM

.



CONCRETE REPAIR PROCEDURE


All dimensions must be verified in the field by Contractor before proceeding with work.

2. See concrete restoration procedure notes on Sheet No. B1-8.

3. See crack repair details on sheet no. B1-5.


BRIDGE N	0. 880051	DFF1C14
west pier DECK REPAIR DETAILS		THE
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	TCF:
WABASSO FISHING PIER REPAIRS	BI -9	LUN LUN
\$TIME\$ \$FILE\$		

S



Angelina Bain

G:\2418_Wabasso Fishing Pier\Final\New S\BEAM02.L 2:27:33 PM



SUPERSTRUCTURE JACKING NOTES:

1.Span jacking shall be used to repair beam stems at bearing location.

2.Submit to County Resident Engineer Jacking Plan and Procedure signed and sealed by Contractor's Engineer Registered in the State of Florida.

3.Dbtain flat self locking Jacks with 10 ton capacity for end of span. 4.Place Jacks as shown on cap. 5.Raise the ends of a span simultaneously. A set of jacks is required for each span. Dperate the jacking system such that the vertical movement of the deck is even across the bridge. 6.Dnce superstructure is raised and before the commencement of any work, Contractor shall either secure jack pressure or provide temporary supports to hold superstructure at desired elevation. Contractor shall submit shop drawing for Engineer's approval on how to secure jack pressure or how to temporarily support the superstructure.

7.Lower superstructure after stem repair is completed, while keeping the jack loads at the same magnitude.

8.During the repair, live load shall not be permitted.

9.Payment for span jacking shall be included in Restore Spalled Areas.


									GESAR GRANNDE	25			
									4-16-07				
		RE	EVISI	ONS			NAMES	DATES	ENGINEER OF RECORD:				SHEET TITLE
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	
2						CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY				
						DESIGNED BY	CG	8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:
						CHECKED BY	TJN	8/06	Sunrise, FL 33323	CD FIO	INDIAN RIVER		1
						APPROVED BY	T.J. Noi	les, P.E.	Cesar A. Granados, P.E #64221 Certificate of Authorization #171	CA 510	INDIAN RIVER		
											\$USER\$	\$DATE	\$\$

4

BRIDGE	ND. 880051	Ĩ.
west pier JACKING DETAILS		: THE OF
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	ICE
WABASSO FISHING PIER REPAIRS	BI-11	LON
\$TIME\$ \$FILE\$		

F.A.C.

61615-23.003,





.


EXISTING TYPICAL PIER SECTION AT PILE CAP


EXISTING TYPICAL SPAN ELEVATION

						4			CESSE GRANAD	2:3			
DATE	BY		DATE	BY	DESCRIPTION	DRAWN BY	NAMES AKB	DATES 8/06	ENGINEER OF RECORD. HARDESTY & HANOVER, LLP	INDIAN RIV	VER COUNTY PUBLIC	C WORKS DEPARTMENT	SHEET TITLE:
						CHECKED BY DESIGNED BY CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY SUITE 544 Sunrise, FL 33323	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:
		, jaka sa kata na mangang na mangang na mangang sa kata kata na mangang kata sa kata na mangang kata sa kata na			a support of the supp	APPROVED BY	T.J. Nole	s, P.E.	Cesar A. Granados, P.E #64221 Certificate of Authorization #171	CR 510	INDIAN RIVER	\$DATE	\$ _\$\$\$7










MA	RK	LENGTH	NO.	TYPE	S	ΓΥ			DE	ETAIL D	IMENSIC	NS .	<u> </u>			
SIZE		FEET	BARS		A	G	В	С	D	E	F	H	J	K	Ø	N
		R - SPAN					odo	L								
4	5703	3'-6"	75	11	1	1	6''	1'-0"	1'-0"							
5	ST04	5'-111/2"	100	1			5'-11/2"									
4	ST05	3'-3''	100	32			2"	1'-5"	1'-8"							
5	ST06	3'-81/2"	100	1			3'-81/2"									
		<u> </u>														
4	SL.01	49'8''	36	1			49'-8"									
		-														
5	DS02	3'-2''	42	4	1	1	6"	6"								L
																<u> </u>
5		3'-2¾"	12	1			3'-2¾"									ļ
5	DL.04	2'-11¾"	12	1			2'-11¾"									
														L		
													L	l	L	
		R DECK -			7		-					······			·	
5	ST01	7'-4"	951	1		ļ	7'-4"							<u> </u>		
4	ST02	2'-10"	951	28			5"	2'-0"		2"						
4	ST03	3'→6''	713	11	1	1	6'' ·	1'-0"	1'-0''			ļ				┥───
						ļ,	4								ļ	
5	DS01	4'-2''	348	4	1	1	1'-0"	6"								
~	DI OI	3'-0"	220	1			3'-0"				<u> </u>	+				+
5 5		3'-15/8''	58	1			3'-15/8"									+
5	DLUZ	5 -178	30	1			5-178									
FAG	T DIF	I R DECK –	SPAN'	18		I	_ I		<u> </u>		1	"ł			J	
4	SI 02	49'-4"	12	1			49'-4"	1				T	1	1		
	52.02	75 7	12											· · · ·		1
FAS	T PIF	R DECK -	SPANS	5 19-2	6	1		1				_h		· · · · ·		
4		49'-8''	108	1		1	49'8"				1	1			1	
						1										
EAS	ST PIE	R DECK -	SPANS	5 18												
4	SL03	25'-6"	12	1			25'-6"									
EAS		R SUBSTR	UCTURE													
6		8'-2"	100	11			7'-0"	7"	7"							
4		7'-0"	20	1]	7'-0"	ļ						ļ	<u> </u>	<u> </u>
10		4'-1¾"	80	10		<u> </u>	3'-1¾"	1'-0"								
5		8'6''	100	4	1	1	2'-4"	1'-4"			ļ				ļ	
4		4'-4''	60	4	1	1	10"	10"							ļ	
4		3'-2"	40	11			2"	1'-6"								
4		4'-0''	70	11		<u> </u>	1'-0"	1'-6"	1'-6"							
4	S08	4'-0"	20	11			1'-0''	1'-6''	1'-6"						1	1

,



SECTION THRU BEAM WEB AT INSERT FOR DIAPHRAGM REINFORCING

INSERT NOTES:

Insert shall be 1" Ø, zinc-electroplated, ferrule wing nut, UNC threads, I/O minimum gage wire, not more than 4" in depth and shall have a minimum ultimate tensile strength of 4,000 psi concrete.
 For locations for inserts, see sheet no. B1-18.

C253	12	 Ġ	2,4	NADOS
			and the	rywege .

										4-16-07				
Ŀ			RE	VISIO	NS			NAMES	DATES	ENGINEER OF RECORD.				SHEET TITLE.
	DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	: WORKS DEPARTMENT	I
		1					CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY	5010 10	0000077	FINANCIAL PROJECT ID	i i
							DESIGNED BY	CG	8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME
1							CHECKED BY	TJN	8/06	Sunrise, FL 33323	00 510	INDIAN RIVER		CF
							APPROVED BY	T.J. Nol		Cesar A. Granados, P.E #64221 Certificate of Authorization #171	CH STU	TNDIAN KIVER		
			an an ann an				والارد والمحمد والتشارين الخري					Angelina Bains	8/28/2	2006 2:34:

÷ ,


7				
	 Face	of	Beam	Web
_[

-Insert

BRIDGE NO.	880051	
BAR LIST		ļ
CR 510 OVER INTRACOASTAL WATERWAY	SHEET NO.	
WABASSO FISHING PIER REPAIRS	BI-16	
2:34:47 PM G: 2418_Wabasso Fishing Pier Final New S RebarListOl.dgn		'

61015 ELECTRON THE S SHEET

.



BEAM NOTES

- All bar dimensions are out-to-out.
 Place two (2) Bars 5Z at each end, and then one (1) Bar 4K each location as detailed alternating the direction of the ends for each bar (see "ELEVATION AT END OF BEAM").
- 3. Bars 4L shall be bent prior to the beam leaving the of the beams.
- 4. Caution should be used with Bars 4L in the ends of
- properly oriented so that the bar will be embedded in 5. Strand N shall be either ASTM A416, Grade 250 or (to 10,000 lbs.
- 6. Unless otherwise noted, the minimum concrete cover :7. At option of the Contractor, welded deformed wire for as noted below for skewed end conditions. The wire Standard Beam Details sheet for these bars. In this lower outstanding leg provided that two longitudinal wi first (lower) wire shall be located || from the end of wire, but no less than $|_{4}$ of the beam depth from mi to ASTM A497. When welded deformed wire fabric is reinforcing.
- 8. Bars 4K and 5Z shall be placed and fied to the fully 9. Bars 3D shall be bent around a l" diameter pin.
- IO. For Bearing and Framing Details, see Structures Pi II.For Camber and Build-up Details, see Structures Pla
- 12. For referenced Dimensions, Angles and Case Number Structures Plans.

CESAL	Gervades
4-10	-07

									((- (
REVISIONS							NAMES	DATES	ENGINEER OF RECORD.				SHEET TITLE,
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY	AKB	8/06	HARDESTY & HANOVER, LLP	INDIAN RI	VER COUNTY PUBLIC	C WORKS DEPARTMENT	
0/3/05		Standard Drawing Issue Date				CHECKED BY	CG	8/06	1000 SAWGRASS CORPORATE PKWY				1
						DESIGNED BY		8/06	SUITE 544	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:
									Fr 20000				FROSECT WAREL
						CHECKED BY	TJN	8/06	Cesar A. Granados, P.E #64221	CR 510	INDIAN RIVER		Ĭ
						APPROVED BY	T.J. No.	les, P.E.	Certificate of Authorization #171				
										<u>.</u>	¢IISED¢	\$/\ATE	¢ \$7

.

ن ا
4
LL.
Ľ,
8
ň
Ņ
ά
1
ž
Ľ
2
цс,
R
ğ
£.
~
品
¥.
ĘŲ,
S
Q
₹
~
S.
3
S
щ
2
2
2
2
F.
Ч
Ľ.
뛷
F
S
7
1
Ē
Ъ
US
H
1.
Ъ
~
R
2
Ц
¢
ᅻ
÷.
2
Ľ.
G
Ē
5
\tilde{C}
С
711CE: THE DFFICIAL RECORD DF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE BIGIS-23.003, F.A.C.

prestressing yard. Bars 4L shall be bent parallel to the end	Is
exterior beams to assure the bent portion of the bar is a the diaphragm concrete. Grade 270, seven—wire strands $\frac{3}{6}$ " ϕ or larger, stressed	
for reinforcing steel shall be 2". Fabric may be used in lieu of Bars 3D, 4K and 4L except e sizes and spacing shall match those shown on the sevent, Bars 4K may be fabricated with the omission of the vires are placed (welded) at the lower end of the bar. The E Bars 4K and the second wire 2" minimum from the first mid-depth of the beam. Welded wire fabric shall conform is used, the end Bars 5Z shall remain conventional mild	e u com
v bonded strands (see "STRAND PATTERN").	
Plans. ans. rs see Inverted–T Beam – Table of Beam Varlables In	е ВОО51 DTES SHEET NO. BI-17
BRIDGE ND. 88	80051
TYPICAL INVERTED T-BEAM DETAILS AND NO INDEX NO. 310	DTES
	SHEET NO.
CR 510 OVER INTRACOASTAL WATERWAY	
	BI-17







TABLE OF BEAM VARIABLES																						
LOCATION CONCRETE PROPERTIES STND. PLAN VIEW END OF BEAM AND BEARING D										EARING DIME	RING DIMENSIONS ** BEAM DIMENSIONS *					REINFORCING STEEL						
SPAN		00/10	STRENGT		PTRN.		ASE	ANGL							5A *	31	0/	31	D2	4K	NO. OF SPACES BARS 4K	SPACING FOR BARS 4K *
NO.	NO.	CLASS	28 Day	Release			END 2		END 2	DIM KI	DIM K2	DIM L	DIM R	DIM T	Length	В	Length	В	Length	NO.	SI	VI
10	/	VI	8500	6800	1	1	/	90.00°	90.00°	/"	/"	49'-10"	3/16 "	5"	49'-1"	1'-8"	2'-//"	1'-8"	2'−11"	53	48	/'0"
10	1&2	V/	8500	6800	,		1	90.00°	90,00°	/"	1"	49'-6"	3/16 "	16"	48'-9"	1'-8"	2'-//"	/'-8"	2'-11"	53	48	/'-O"
19-26	1 &2	VI	8500	6800	1	/	1	90.00°	90.00°	/"	1"	49'-10"	3/16 "	16"	49'-1"	/'-8"	2'-//"	1'-8"	2'-11"	53	48	/ ¹ -0 ⁿ
27	1&2	VI	8500	6800	2	1		90.00°	90,00°	/"	2"	25'-7"	0"	16"	49'-10"	/'-8"	2'-11"	/'-8"	2'-11"	29	23	1'-0"




BEAM CAMBER AND BUILDUP NOTES:

The buildup values given in the table are based on theoretical beam cambers. The Contractor shall monitor beam cambers for the purpose of predicting camber values at the time of the deck pour. If the predicted cambers based on field measurements differ more than $+/-\frac{1}{2}$ " from the theoretical "Net Beam Camber @ 120 Days" shown in the table, modify the buildup dimensions as required. When the measured beam cambers create a conflict with the bottom mat of slab steel, notify the Engineer a minimum a 21 days prior to casting.








Fully Bonded Strand (Typ.) <u>9 sp</u>.@ 2" 3''

NOTE: Work this sheet with the following drawings: Index No. 310 - Typical Inverted-T Beam Details and Notes Index No. 320 - Inverted-T Beam - Standard Details



TYPE (2) 🚊 STRANDS

STRAND DESCRIPTION: Use _0.6" Diameter, Grade _270, LOW RELAXATION Strands stressed at 43.9 kips each. Area per strand equals 0.217 sq. in. per strand.

REVISIONS DATE BY DESCRIPTION DATE BY DESCRIPTION 07-30-04 SD0 Semi-Standard Drawing Issue Date Description Description	DRAWN BY AKB 8/06	1000 SAWGRASS CORPORATE PKWY	NRIVER COUNTY PUBLIC WORKS DEPART		VERTED-T BEAM - TABLE OF BEAM VARIABL INDEX NO. S-321 (MODIFIED)	ES HI
	DESIGNED BY CG 8/06 CHECKED BY TJN 8/06 APPROVED BY T.J. Noles, P.E.	SUITE 544 Suncise, FL 33323 Cesar A. Granados, P.E. #64221 CR 5 Certificate of Authorization #171		PROJECT NAME CR	R 510 OVER INTRACOASTAL WATERWAY WABASSO FISHING PIER REPAIRS	SHEET NO.
		CEBAR GRANADES 4-10-07	\$USER\$	\$DATE\$ \$TIME	E\$	

BUILDUP & DEFLECTION DATA									
	D THEORE P OVER € E		NET BEAM CAMBER	DEAD LOAD DEFLECTION					
BEGIN SPAN M "B"	AT € SPAN DIM "C"	AT END SPAN DIM "D"	(PRESTRESS - DEAD LOAD OF BEAM) @ 120 DAYS	DURING POUR @ 120 DAYS DIM "A"					
5/ "	0"	5/8 "	5/8 "	11/4 "					
5/8 "	<i>O</i> "	5/8 "	5/8 "	1/4 "					
5/8 "	0"	5/8 "	5/8 "	1/4 "					
0"	<i>O</i> ″	0"	0"	0"					

AT BEGIN

SPAN

DIM "B"

LOCATION

SPAN BEAM

NO.

1

1&2

1 & 2

1 & 2

NO.

10

18

19-26

27


DIMENSION NOTES

* All longitudinal beam dimensions shown on this on this sheet with a single asterisk (*) are measured along the top of beam at the centerline of beam.


** End of beam bearing dimensions "J" and "K" are measured along the bottom of the beam.

BRIDGE NO. 880051

VD7



\$USER\$







v with NEC 2005 and allloca	lordinanc	e and							
ns. nate electrical work with structural work. ans are diagrammatic and are not to be scaled. s shown are approximate. Exact locations shall be ed based upon approved shop drawings.									
ATIONS:									
Single Phase Compact Fluorescent Junction Box Light Emitting Diode National Electrical Code National Electrical Manufacture Stainless Steel	ers Assoc	siation							
LEGEND:									
Circuit Breaker		Fuse							
Control Relay Coil	Ŧ	Ground							
Control Relay Contact		Hidden Line							
Curb Embedded Luminaire		New Line							
Curb Mounted Luminaire	35	Transformer							
Existing Line									
		BRIDGE ND. 880051							
General ele	CTRICAL	PLAN							
		SHEET NO							

CR 510 OVER INTRACOASTAL WATERWAY	SHEET
WABASSO FISHING PIER REPAIRS	BI

-21





\$USER\$

Attachment

Available staging area 100' x 40' at the parking lot on the west side of the bridge.

